

Conts - No 84

Exterior Lines

Eya,  
Coster

Exterior Lines

N. H. Gates

Manuscript compared with  
Washington transcript

Washington transcript made  
H. J. J.

Manuscript compared with  
Notes H. C.

We, Allen Thompson, and Lester Potter,  
do solemnly swear that we will faithfully  
execute the duties of chain carriers; that we  
will level the chain upon uneven ground,  
and plumb the tally pins, whether by sticking  
or dropping the same; that we will report  
the true distance to all notable objects, and  
the true length of all lines that we  
assist in measuring, to the best of our  
skill and ability.

Allen Thompson (chairman)  
Lester Potter (chairman)

Subscribed and sworn to before me this  
eighteenth day of August A.D. 1859.

W. C. Murray  
County Clerk  
Wasco County Oregon

I, Benjamin Athy, do solemnly swear that I will well and truly perform the duties of Arman according to instructions given me, and to the best of my skill and ability.

Benjamin Athy (Arman)  
Subscribed and sworn to before me,  
this eighteenth day of August A.D.  
1859.

Wm. Mowbray  
County Clerk  
Wasco County Oregon

I, J. A. Pownall, do solemnly swear that I will faithfully execute the duties of compassman according to instructions given me, and to the best of my skill and ability

J. A. Pownall (Compassman)

Sworn and subscribed to before me this eighteenth day of August A. D. 1859.

W. C. Murray  
County Clerk  
Wasco County Oregon

J/D

No. N. B. 28. 2  
No. N. B. 29. 2  
No. N. B. 30. 2

27	26	25	24	23	22	16	15	15	14	14	13	8	7	7	6	5
26	5	4	3	2	1	56	5	4	3	2	1	5				
207	8	9	10	11	12	7	8	9	10	11	12					
19	18	17	16	15	14	13	12	11	10	9	8					
18	19	20	21	22	23	24	19	20	21	22	23	24				
30	29	28	27	26	25	30	29	28	27	26	25	2				
31	32	33	34	35	36	31	32	33	34	35	36	2				

Field Notes of the Survey of the Exterior  
boundaries of Township No 3 North of Range  
No 29 East of the Willamette Meridian, in  
the State of Oregon, by N. W. Gates,  
Deputy Surveyor, under his contract  
bearing date the 22<sup>nd</sup> day of July  
A. D. 1859.

commenced Sept 12<sup>th</sup> 1859  
completed Sept 14<sup>th</sup> 1859

10-10

3 N. of R. 29 E.

From the established corner to Townships  
2 and 3 North of Ranges 28 and 29 East, run  
chains North between Sections 31, and 36,

40.00 Set post for  $\frac{1}{4}$  Section corner in Earth  
mound, established as per instructions

80.00 Set post for corner to Sections 30 and 31,  
25, and 36, in mound of earth estab-  
-lished as per instructions

Land gently Rolling; Soil good 2<sup>nd</sup> rate.

chains North between Sections 30, and 25.

Variation  $19^{\circ} 35'$  East.

40.00 Set post for  $\frac{1}{4}$  Section Corner, in Mound  
of Earth, established as per instructions,

80.00 Set post for corner to Sections 19, and 30,  
24, and 25, in a mound of earth  
established as per instructions.

Land level,

Soil good 2<sup>nd</sup> rate.

September 12<sup>th</sup> 1859

T. B. N. of R. 29 E.

11  
11

chains North between Sections 18 and 24.

Variation  $19^{\circ}30'$  East

23.00 Trail, Course E. & W.

40.00 Set post for  $\frac{1}{4}$  Section Corner, in Earth mound, established, as per instructions.

45.25 Immigrant Road, Course East & West.

80.00 Set post for  $\frac{1}{4}$  Section Corner to Sects 18, and 19, 13, and 24, in mound of earth, established as per Instructions.

Land level; Soil 2<sup>nd</sup> rate.

chains North between Sections 18, and 13.

Variation  $20^{\circ}30'$  East.

40.00 Set post for  $\frac{1}{4}$  Section corner in mound of Earth, established as per Instructions.

60.00 Unmatilla Bottom, Course E. & W.

80.00 Set post for corner to Sections 7 and 18, 12, and 13, in mound of earth, established as per Instructions.

Land level; Soil 1<sup>st</sup> and 2<sup>nd</sup> rate.

September 13<sup>th</sup> 1859

12 <sup>12</sup> N. 3 N. of R. 29 E.

chains North between Sections 7, and 12,

Variation  $19^{\circ} 30'$  East

40.00 Set post for  $\frac{1}{4}$  section corner in mound of earth, established as per instruction.

80.00 Set post for corner to Sections 6, and 7, 11, 12, in mound of earth, established as per instructions.

Sand level prairie bottoms;  
Soil good 2nd rate.

---

chains North between Sections 6, and 1,

Variation  $20^{\circ}$  East

40.00 Set post for  $\frac{1}{4}$  section corner, in mound of earth, established as per instructions

45.25 Slough 2 chains wide, course N.W.

54.00 Slough 2 chains wide, course N.W.

80.00 Set post for corner to Townships 3, and 4, North, of Ranges 28, and 29 East, in earth mound, established as per instructions.

Sand level prairie bottoms;  
Soil 1st rate.

28 T. 3 N. of R. 28 E.

## General description.

This Township contains but little 1<sup>st</sup> rate land, its soil being chiefly <sup>composed</sup> of a very sandy loam, of too light a nature to admit of a profitable cultivation; and is entirely destitute of timber.

It is generally covered with bunch grass, and will therefore make reasonably good pasturage; but in this respect, it will not be greatly advantaged by the generous beds of Cactus scattered over its surface.

3 N. of R. 28 E.

29  
29

## List of Names

A list of the names of the individuals employed to assist in running, measuring, or marking the lines and corners described in the foregoing field notes of Township No 3 North of the base line of Range No 28 East of the Willamette Meridian, showing the capacity in which each acted

Allen Thompson,	(Chainman)
Bester Potter,	(Chainman)
Benjamin Athey,	(Axman)
J. A. Purnell,	(Compassman)

~~W. S. H. of R. 20 E.~~

35

chains

North between Sections 14 and 21.

Variation  $20^{\circ}30' E.$

40.00

Set post for  $\frac{1}{4}$  Section Corner in a mound of earth established as per Instructions.

80.00

Set post for corner to sections 18 and 19, 13 & 24, and drove charred stake, and built mound in road with pits, trenches, &c. Course of Road, E. & W.

Land gently rolling Soil 2nd rate.

---

We hereby certify that we assisted in surveying the exterior boundaries of Townships Number Three North of the base line of Ranges number Twenty eight, Twenty-nine, and Thirty East of the Willamette Meridian, and that said townships have been in all respects, to the best of our knowledge and belief, well and faithfully surveyed, and the boundary monuments planted according to the instructions furnished by the Surveyor General.

- Allen Thompson (Chairman)
- Lester Patter (Chainman)
- Benjamin They (Ampman)
- J. A. Fournall (Compassman)

Subscribed and sworn to before me, this Eighteenth day of October A. D. 1859.

W. C. Moody  
 County Clerk  
 Wasco County Oregon

I, N. W. Gates, deputy Surveyor, do solemnly swear that, in pursuance of a contract with W. W. Chapman, Surveyor of the public lands of the United States in the State of Oregon, bearing date the twenty ~~second~~ day of July A. D. 1859, and in strict conformity to the laws of the United States and the instructions furnished by the said Surveyor General, I have faithfully surveyed the exterior boundaries of Townships 3 North, <sup>of the base line</sup> of Ranges number 28, 29, and 30, East of the Willamette meridian, in the State aforesaid, and do further solemnly swear that the foregoing are the true and original field notes of such Survey. N. W. Gates

Deputy Surveyor.

Subscribed & Sworn to before me  
this 28<sup>th</sup> day Oct 1859.

F. S. Hallard, Clerk  
of Circuit Court for Clackamas  
Co. Oregon

by A. Hallard, depy

Surveyor General's Office  
Eugene City January 3 1866

The foregoing field notes of the  
Survey of the Exterior lines of  
Township T<sup>3</sup> N. of Ranges  
T<sup>28</sup> S. 29. & 30 East of the  
Willamette Meridian, Oregon  
executed by N. H. Gates, Deputy  
Surveyor, under his Contract of  
the 2<sup>nd</sup> day of July 1859  
having been critically examined  
the necessary corrections and expla-  
-ations made, the said field notes  
and the Survey they describe are  
herby approved

W. W. Chapman  
Surveyor General of Oregon

Res Nov. 3<sup>d</sup>. Exch

47

Subdivisions

Examina & Correcting

Field notes of the Subdivision lines  
in Township No 3 North of Range 29  
East of the Willamette Meridian  
in the State of Oregon by W. H.  
Gates deputy Surveyor under his  
Contract No 84 bearing date the  
22<sup>nd</sup> day of July 1859

commenced September 15<sup>th</sup> 1859  
completed September 22<sup>nd</sup> 1859

Washington transcript made  
by P. J.

Manuscript compared  
with Notes. T. C.