

Field Notes of the survey of the
 Subdivisional lines of Town-
 ship No. 3, North of Range No
 3 East of the Willamette Merid-
 ian, in the State of Oregon, by
 Wm. B. Campbell, deputy surveyor,
 under his contract No 95,
 bearing date the 19th day of
 September 1860.

Commenced Oct 18th 1860
 Finished October 26th do

Index Diagram

6	5	4	3	2	1
63	62	45	34	23	12
7	8	9	10	11	12
60	59	43	32	21	10
18	17	16	15	14	13
57	56	41	31	20	9
19	20	21	22	23	24
54	53	39	28	17	6
31	29	28	27	26	25
51	49	37	26	15	4
31	32	33	34	35	36

Township 3, R. 30 E, Willamette Meridian
chains

West On a random line between
sections 30 & 31.

~~Variation 210° E~~

- 40.00 Set a temporary quarter section post
- ~~41.50 Commence to descend~~
- ~~53.25 To foot of descent~~ 100
- ~~61.00 Commence ascending~~
- ~~65.50 To top of ascent & commence descent~~ 25
- ~~78.50 To foot of descent & Nail SW. NE.~~ 30
- ~~81.00 Commence ascent~~
- 87.37 Intersect West boundary of Township
1600's North of post, come to
sec. 30 & 31.

Township 3. N Range 30 E. Tiltamott Meridian
Chain

Mesh On a random line between,
sections. 19 & 30.

Variation $24^{\circ} 15' E$

40.00 Set a temporary quarter section post
89.00 Intersect West boundary of
Township 49 Ns North of post
corner to sec. 19 & 30.

$N 89^{\circ} 39' E$. On a true line between
sec. 19 & 30.

Variation $24^{\circ} 15' E$

49.00 Set a post for quarter section corner,
drove a char & stake & raised
mound of earth, with trench & hills
as per instructions.

89.00 The post corner to sec. 19, 20,
29 & 30.

Land genly saline prairie.
Soil good $2\frac{1}{2}$ rates

53
95

Township 3, Range 30, Tilla north Meridian,
Maine

North Between Sec 19 & 20.

Variation $20^{\circ} E$

27.00 On Hay road N Rail road NW & SE.

40.00 Set a post for quarter sec.

40.00

corner. drove a char'd
stake & raised a mound
of earth, with trench & fills,
as per instructions.

80.00 Set a post for corner to sec. 19.

80.00

17, 18, 19, & 20. Drove a char'd
stake, & raised a mound of
earth, with trench & fills,
as per instructions.

Land gently rolling prairie,
Soil good & 2nd rate.

October 27th 1860

Township 3 N. Range 30 E. Tullamath Meridian
chains

East, On a random line between
sec. 17 & 20.

Variation $20^{\circ} 45' E$

40.00 Set a temporary quarter section
post.

N 45° Sim

80.06 Intersect corner to sec. 16, 17,
21 & 21, 20 N. North of post,
corner to sec. 16, 17, 20 & 21.

89.51 N. On a true line between
sec. 17 & 20.

40.03 Set a post for quarter sec.,
corner, drove a charred stake
& raised a mound of earth,
with trench & hills, as per instructions

80.04 The post corner to sec. 17
18, 19, & 20.

Sand land prairie soil
good 2nd rating

Township 3. N. Range 3. E. Tarrant Meridian,
Texas

West. On a random line between
sec 18 & 19.

Variation 20° 45' E

~~8.00 Commenced descent.~~

~~25.50 To foot of do~~

40.00

~~1000~~

40.00 Set a temporary quarter section post

89.61 Intersect West boundary of Town-

ship. at post. corner to sec

18 & 19. Sand rolling prairie

East. On a true line between Sec-18 & 19

49.61

Variation 20° 45' E

49.61 Set a post for quarter section level

corner; drove a char'd stake

raised a mound fourth with

64.11 trench & pits. as per instructions.

64.11 Common ascending ridge

81.61 To top of ascent

+100

89.61 The post corner to sec. 17 18 19 & 20,

89.61

Sand rolling prairie. Soil good
good rate.

Township 23rd N. R. 3rd E. Hillman Mer.
chains.

Set on a random line
between sections 6 & 7

Variation 2115th E

40.00 Set temporary quarter section
post. -50

89.78 Intersect West boundary of -25
Township 23rd N. R. 3rd E. South of post

Set on a true line between
sect. 6 & 7.

49.78 Set a post for quarter section +25
corner. drove a char'd stake
raised mound of earth with
trench & pits, as per instructions.

89.78 The corner to sect. 6 & 7 +50
Sand & Soil the same as
last miles.

List of Names.

List of the names of the individuals employed to assist in running, measuring, or marking the lines and corners described in the foregoing field notes, of Township No 3 North of the base line of Range No 30 East of the Willamette Meridian, showing the capacities in which they acted is

Samuel Campbell Chairman
 Josephus Tompkins do
 Robert Handfield do

We hereby certify that we assisted
 Saml Campbell deputy surveyor,
 in surveying the subdivisinal
 lines of Township No 3 North
 of the base line of Range number
 Thirty East of the

Pillmate Meridian, and that
said Township has been in all
respects, to the best of our know-
-edge and belief, well and
faithfully surveyed, and the
boundary monuments planted
according to the instructions
furnished by the Surveyor General,

Samuel L. Campbell Chairman.
Josephus Tompkins Chairman
Robert F. Canfield Assnary

Subscribed and sworn to
before me at Oregon City this
3rd day of Decr AD 1860

Jas Winston
Clerk of the Circuit
Court for the County
of Clatsop as State
of Oregon

69
189

Wm. Campbell deputy surveyor,
do solemnly swear that, in
pursuance of a contract with
W. W. Chapman Surveyor of the
public lands of the United States,
in the State of Oregon, bearing
date the 19th day of September,
1860, and in strict conformity
to the laws of the United States,
and the instructions furnished by
the Surveyor General, I have
faithfully surveyed the subdivi-
sional lines of Township No. 11
Three North of the base line of Range
number thirty East of the Willamette
Meridian, in the State aforesaid,
and do further solemnly swear
that the foregoing are the true
and original field notes of
such survey of Wm. Campbell
deputy Surveyor

Subscribed and sworn

119

To Before me at Oregon
City this 3rd day of Dec
A.D. 1860

John Wessington
Clerk of the Circuit
Court for the County
of Lincoln in the State
of Oregon

110A

Sur General's Office
Eugene City, Jan'y 29th 1861.

The foregoing field notes of the
survey of the subdivisions of Town-
ships No. 3 North, Range No. 30
East of the Willamette Meridian
executed by Wm. B. Campbell, dep-
uty Surveyor, under his contract
of the 19th day of September 1860:
having been critically exam-
ined, the necessary corrections
and explanations made the
said field notes and the sur-
veys they describe are hereby
approved.

W. W. Chapman

Sur: General of Oregon