

Field Notes of the Survey of the  
Exterior boundaries of Township 2 North  
of Range 29 East of the Willamette  
Meridian in the <sup>State</sup> Territory of Oregon  
by David P. Thompson Deputy Sur-  
veyor under his contract "No. 83"  
bearing date the 22<sup>nd</sup> day of July  
1859

29  
489  
S. 2. N. T. 29. E.

chains North between Secs 7 & 12

Variation  $20^{\circ}30'$  East

3.30 Prairie area Trail bears S.W. & N.E.

4000 Set post for  $\frac{1}{4}$  Sec corner in corner of Earth  
 $8^{\circ}$  as per instructions

8000 Set post for corner to Secs 6, 7, 18, 12  
in corner of Earth  $8^{\circ}$  as per instructions  
Land gently rolling  
Soil good & rate

---

North between Secs 1 & 6

Variation  $19^{\circ}15'$  East

7.40 Indian Trail bears N.E. & S.W.

4000 Set post for  $\frac{1}{4}$  Sec corner in corner of Earth  
 $8^{\circ}$  as per instructions

8000 Set post for corner to Township 2 & 3 North  
of Range 28 & 29 East in corner  
of Earth  $8^{\circ}$  as per instructions

Variation  $20^{\circ}14'$  East

Land gently rolling.

Soil good & rate

August 24<sup>th</sup> 1859

From the corner to Townships 28<sup>3</sup> North  
of Ranges 288 29 East I run a  
random line between said Townships  
Setting, <sup>temporary</sup> half mile and mile post  
at 4000 and 8000 chains

I find the Township line to be 6 miles  
8 chains and 70 links and the  
falling to be 400 links South of corner  
The correction will therefore be 8.70 links  
West and  $66\frac{2}{3}$  links North per mile

491 T. 2 N. R. 29 E.

From the Established corner to Township's  
 283 North of Range 29830 East Prec  
 S 89° 32' W on true line between Secs 18 36  
 chains Variation 19° 30' East  
 2800 Leave Bottom bears N. W. & S. E.  
 4000 Set post for <sup>1/4</sup> Sec corner in mound of Earth  
 8° as per instructions  
 8000 Set post for corner to Secs 1, 2, 35 & 36  
 in mound of Earth 8° as per instructions  
 Land gently rolling  
 Soil good & fertile

S 89° 32' W on true line between Secs 2835  
 Variation 20° East  
 4000 Set post for 1/4 Sec corner in mound of  
 Earth 8° as per instructions  
 8000 Set post for corner to Secs 2 3 34 & 35  
 in mound of Earth 8° as per instructions  
 Land gently rolling  
 Soil good & fertile

North between Secs

389°32' W on true line between Secs 38 & 34  
 chains Variation 20° E

3.75 Indian Trail bears N & S

40.00 Set post for 1/4 Sec ~~Post~~ in mound  
 of Earth &c as per instructions

42.00 Indian Trail ~~bears~~ & Ravine bears  
 North & South

80.00 Set post for corner to Secs 34, 33, & 34  
 in mound of Earth &c as per instructions  
 Sand gently rolling

Soil good & granite

389°32' W on true line between Secs 48 & 33  
 Variation 19°50' East

40.00 Set post for 1/4 Sec corner in mound of Earth  
 &c as per instructions

80.00 Set post for corner to Secs 45, 37, & 33  
 in mound of Earth &c as per instructions  
 Sand good & granite

So

- chains 8933' ~~W on~~ true line between Secs 3832  
 Variation  $20\frac{1}{4}^{\circ}$  East
- 470 Indian Trail bears N & S Spring bears  
 South 15.00 chains <sup>dist</sup>
- 4000 Set post for  $\frac{1}{4}$  Sec corner in mound of  
 Earth &c as per instructions
- 8000 Set post for corner to Secs. 5. 6. 31832  
 Land Soil &c  
 Soil good @ one rate

- 8933' W on Line between Secs 6831  
 Variation  $19\frac{3}{4}^{\circ}$  East
- 16.00 Indian Trail bears N & S
- 40.00 Set post for  <sup>$\frac{1}{4}$  Sec</sup> corner in mound of  
 Earth &c as per instructions
- 80.00 Indian Trail bears N E & S W
- 8870 Intersect corner to Township 283  
 North of Ranges 288 29 East  
 Land gently rolling  
 Soil good @ one rate  
 August 25<sup>th</sup> 1859

General Description <sup>34</sup>

494

The quality of land in this Township is good <sup>2<sup>nd</sup></sup> rate rolling Prairie covered with a thick growth of Bunch Grass. There are numerous Springs in this Township.

This Township will admit of considerable settlement and therefore should be subdivided.

---

Field Notes of the Survey of the Exterior boundaries of Township 1 North of Range 28 East of Willamette Meridian, in the State of Oregon by David P. Thompson deputy Surveyor under his contract No 83, bearing date the 23<sup>rd</sup> day of July 1859

## List of Names

A list of of the names of the individuals employed to assist in measuring and marking the lines and corners described in the foregoing field notes of the Exterior boundaries of Townships 18<sup>2</sup> North of Range Nos 28, 29, & 30 East of the Willamette Meridian Showing the respective capacities in which they acted

J. H. Townall (Chairman)  
 Allen Thompson "  
 Benj. Athey Axeman



We hereby certify that we assisted  
 David P Thompson deputy surveyor  
 in surveying the Exterior boundaries  
 of Townships Nos 1 & 2 North of the  
 Base Line of Ranges Nos 28, 29, &  
 30 East of the Willamette Meridian  
 and that said Townships have been  
 in all respects to the best of our  
 knowledge and belief well and faithfully  
 surveyed and the boundary monuments  
 planted according to the instructions  
 furnished by the Surveyor General

D. J. Fournell

Allen Thompson

Benjamin They

Sworn and Subscribed to before  
 me this 18<sup>th</sup> day of October 1859

W. C. Mowbray  
 County Clerk  
 Wasco County Oregon

I David P. Thompson deputy Surveyor do  
 Solemnly Swear that in pursuance of  
 a contract with W. W. Chapman Surveyor  
 of the public Lands of the United States  
 in the State of Oregon bearing date  
 the 22<sup>nd</sup> day of July 1859 and in strict  
 conformity to the laws of the United States  
 and the instructions furnished by the said  
 Surveyor General I have faithfully surveyed  
 the exterior boundaries of Townships Nos.  
 18 & 19 North of the Base Line of Ranges 28  
 29 & 30 East of the Willamette Meridian in the  
 State aforesaid and do further Solemnly  
 Swear that the foregoing are the true and original  
 field notes of such Survey

David P. Thompson Dep't Sur

Sworn and subscribed to before this 1<sup>st</sup> day  
 of November 1859 at Salem Oregon  
 L. C. White  
 Not Pub

Surveyor General's Office,

Eugene City January 31<sup>st</sup> 1860

The foregoing field notes of the surveys of the Exterior boundaries of Townships 1 & 2 North of Ranges 28, 29 & 30 East of the Willamette Meridian, Oregon, executed by David P. Thompson, deputy Surveyor under his Contract of the 22<sup>d</sup> day of July 1859, having been critically examined, the necessary corrections and explanations made, the said field notes and the surveys they describe are hereby approved.

W. W. Chapman  
Sur. Genl. of Oregon.