

Field Notes of the survey of the  
 Subdivisional lines of Town-  
 ship No. 3, North of Range No  
 3 East of the Willamette Merid-  
 ian, in the State of Oregon, by  
 Wm. B. Campbell, deputy surveyor,  
 under his contract No 95,  
 bearing date the 19<sup>th</sup> day of  
 September 1860.

Commenced Oct 18<sup>th</sup> 1860  
 Finished October 26<sup>th</sup> do

Index Diagram

6	5	4	3	2	1
63	62	45	34	23	12
7	8	9	10	11	12
60	59	43	32	21	10
18	17	16	15	14	13
57	56	41	31	20	9
19	20	21	22	23	24
54	53	39	28	17	6
31	29	28	27	26	25
51	49	37	26	15	4
31	32	33	34	35	36



Township 3 N Range 30 E Willamette Merid.  
chains

Cast On a random line between  
sections 24 & 25

Variation, 19245 E

140.08 Set temporary quarter sec post  
79.70 Intersect Guide Meridian.  
67 W South of post corner to Sec  
24 & 25.

8930 W On a true line between  
Sec 24 & 25.

39.85 Set a post for quarter section  
corner. draw a char'd  
Stake & raise mound of earth,  
as per instructions.

79.70 The corner to Secs., 23, 24,  
25 & 26.

Land, greatly rolling. Soil  
good 2<sup>nd</sup> rate.



Township 3 N Range 3 E Willamette Mer  
chains

North, Between Secs 23 & 24  
Variation 19° 15' E

40.00 Set a post for quarter section  
corner, drove a char'd stake &  
raised a mound of earth  
as per instructions.

80.00 Set a post, for corner to Secs  
13, 14, 23 & 24, drove a char'd  
stake & raised a mound of earth  
with trench & fills as per instructions,  
Land nearly level. Soil good  
2nd rate.



848

Township of N. 30. W. Willamette Merid.

East. On a random line between  
Sec 13 & 24

Variation  $19^{\circ}45'$  E.

40.00 Set temporary quarter section  
post.

80.18 Intersect Guide Meridian at  
post corner to Sec 13 & 24.

West. On a true line between Sec 13 & 24

40.09 Set a post for quarter section  
corner, drove a chain stake  
& raised a mound of earth,  
with trench and fills, as per  
instructions.

80.18 The corner to Sec 13, 14, 23, & 24.

Soil good 2<sup>nd</sup> grade  
Land level & rolling prairie



Township 3 N 3 E 6th Meridian  
Chains

North, Between Sec. 1 3 & 14

~~Variation 19 1/2 E~~

4000 Set a post for quarter section corner, drove a char'd stake & raised mound of earth, as per instructions.

8000 Set a post, for corner to sec. 11, 12, 13 & 14, drove a char'd stake & raised a mound of earth, with trench & pits as per instructions.

Land nearly level. Prairies  
Soil good & water



Township 3 N R 3 E Millmore Meridian  
chains

Cash. On a random line between  
sections 12 & 13.

Variation  $19^{\circ} 43' E$

40.00 Set a temporary quarter sec post  
49.56 Intersect Grid Meridian 24th  
South of post. corner sec 12 & 13.

\$89.50 On true line between  
Sec 12 & 13

39.78 Set a post for quarter section.  
corner drove a chard stake &  
raised a mound of earth,  
with trench, & fills as per instructions.

49.56 The corner to sections 11, 12, 13 & 14,  
Land & rolling prairie. Soil,  
good 2nd state



Township of Range 30 E. T11 S11 N11 W11

North. Between sec 11 & 12,

~~Meridian 19° 15' E~~

40.00 Set a post for quarter section corner drove a char'd stake & raised a mound of earth, with trench & pits as per instructions.

80.00 Set a post for corner to sec 1 2, 11 & 12. Drove a char'd stake & raised a mound with trench and pits, as per instructions. Land level. Prairie. Soil good & good water.



Township 3 N. Range 30 E. Willamette Meridian,  
chain

Cast On a random line between  
sections 1 & 12,

Variation 20° 15' E,

40.00 Set a temporary quarter sec. cor  
post.

79.55 Intersect Guide Meridian 30 E  
South of post, corner to sec.  
1 & 12.

89.47 On a true line between  
sec 1 & 12,

39.78 Set a post for quarter section  
corner, drove a char'd stake  
& raised a mound of earth  
with trench & pits as per instructions,

79.55 The corner to sections 1, 2, 11 & 12,  
Level level prairie. Soil  
good 2<sup>nd</sup> rate.



## List of Names.

List of the names of the individuals employed to assist in running, measuring, or marking the lines and corners described in the foregoing field notes, of Township No 3 North of the base line of Range No 30 East of the Willamette Meridian, showing the capacities in which they acted is

Samuel Campbell Chairman  
 Josephus Tompkins do  
 Robert Handfield do

We hereby certify that we assisted  
 Saml Campbell deputy surveyor,  
 in surveying the subdivisinal  
 lines of Township No 3 North  
 of the base line of Range number  
 Thirty East of the



Pillmate Meridian, and that  
said Township has been in all  
respects, to the best of our know-  
-edge and belief, well and  
faithfully surveyed, and the  
boundary monuments planted  
according to the instructions  
furnished by the Surveyor General,

Samuel L Campbell Chairman  
Josephus Tompkins Chairman  
Robert F. Canfield Assnary

Subscribed and sworn to  
before me at Oregon City this  
3<sup>rd</sup> day of Decr AD 1860

Jas Winston  
Clerk of the Circuit  
Court for the County  
of Clatsop as State  
of Oregon



69  
189

Wm. Campbell deputy surveyor,  
do solemnly swear that, in  
pursuance of a contract with  
W. W. Chapman Surveyor of the  
public lands of the United States,  
in the State of Oregon, bearing  
date the 19<sup>th</sup> day of September,  
1860, and in strict conformity  
to the laws of the United States,  
and the instructions furnished by  
the Surveyor General, I have  
faithfully surveyed the subdivi-  
sional lines of Township No. 11  
Three North of the base line of Range  
number thirty East of the Willamette  
Meridian, in the State aforesaid,  
and do further solemnly swear  
that the foregoing are the true  
and original field notes of  
such survey of Wm. Campbell  
deputy Surveyor

Subscribed and sworn



119

To Before me at Oregon  
City this 3<sup>rd</sup> day of Dec  
A.D. 1860

John W. Wessington  
Clerk of the Circuit  
Court for the County  
of Lincoln in the State  
of Oregon



110A

Sur General's Office  
Eugene City, Jan'y 29<sup>th</sup> 1861.

The foregoing field notes of the  
survey of the subdivisions of Town-  
ships No. 3 North, Range No. 30  
East of the Willamette Meridian  
executed by Wm. B. Campbell, dep-  
uty Surveyor, under his contract  
of the 19<sup>th</sup> day of September 1860:  
having been critically exam-  
ined, the necessary corrections  
and explanations made the  
said field notes and the sur-  
veys they describe are hereby  
approved.

W. W. Chapman

Sur: General of Oregon