

Field Notes of the survey of the  
 Subdivisional lines of Town-  
 ship No. 3, North of Range No  
 3 East of the Willamette Merid-  
 ian, in the State of Oregon, by  
 Wm. B. Campbell, deputy surveyor,  
 under his contract No 95,  
 bearing date the 19<sup>th</sup> day of  
 September 1860.

Commenced Oct 18<sup>th</sup> 1860  
 Finished October 26<sup>th</sup> do

Index Diagram

6	5	4	3	2	1
63	62	45	34	23	12
7	8	9	10	11	12
60	59	43	32	21	10
18	17	16	15	14	13
57	56	41	31	20	9
19	20	21	22	23	24
54	53	39	28	17	6
31	29	28	27	26	25
51	49	37	26	15	4
31	32	33	34	35	36

Township 3, Range 3, E. Willamette Meridian,

North, Between Sec 35 & 36  
~~West of Sec 35~~

Commence<sup>ascent</sup> of Bluff from post

24.50 To top of Bluff facing South. +200

40.00 Set a post, for quarter sec corner  
Drove char'd stake & raised mound  
of earth, with trench & pits as per instructions,

43.75 To a Stake Road runs E & W.

80.00 Set a post for corner to Secs  
25 & 26, 35 & 36. Drove a char'd  
stake & raised a mound of earth  
with trench & pits, as per instructions.

London Bluff broken Soil poor 3<sup>rd</sup>  
rate & stony. Balance land prairie  
Soil good 2<sup>nd</sup> rate, producing excellent  
grass.

444

Township 3. N. Range 36. William the Meridian

East Corner bet. ~~sec 25 & 36~~ Variation 20° 00' E

40.00 Set temporary quarter sec post.

79.97 Intersect ~~the~~ Meridian 68 lbs

South of corner sec 25, 836

8931 N. On Franklin between sec 25 & 36

~~Variation 20° 00' E~~

39.98 Set a post for quarter section corner, drove a hard stake & raised a mound, with trench spits, as per instructions.

79.96 Set a post for corner to sec "

24, 25, & 26, 35 & 36

Land gently rolling. Soil good  
2nd Rate

3  
45

Township 3 Range 3 E. Willamette Meridian  
chains

North, Between Secs. 25 & 26

~~Variation 20' 00"~~

40.00 Set a post for quarter section  
corner, drove a charred stake  
& raised a mound of earth as  
per instructions.

80.00 Set a post for corner to Secs.  
23, 24, 25 & 26, drove a charred  
stake & raised a mound with  
trench and pits as per  
instructions.

Land gently rolling prairie,  
nearly level, Soil good  
good water

Township 3 N Range 30 E Willamette Merid.  
chains

Cast On a random line between  
sections 24 & 25

Variation, 1925 E

140.00 Set temporary quarter sec post  
79.70 Intersect Guide Meridian.  
67 W South of post corner to Sec  
24 & 25.

8930 W On a true line between  
Sec 24 & 25.

39.85 Set a post for quarter section  
corner. Drive a char'd  
Stake & raise mound of earth,  
as per instructions.

79.70 The corner to Secs., 23, 24,  
25 & 26.

Land, greatly rolling. Soil  
good 2<sup>nd</sup> rate.

Township 3 N Range 3 E Willamette Mer.  
chains

North, Between Secs. 23 & 24  
Variation 19° 15' E

40.00 Set a post for quarter section  
corner, drove a char'd stake &  
raised a mound of earth  
as per instructions.

80.00 Set a post, for corner to Secs.  
13, 14, 23 & 24, drove a char'd  
stake & raised a mound of earth  
with trench & fills as per instructions,  
Land nearly level. Soil good  
2nd rate.

848

Township of N. 30. W. Willamette Merid.

East. On a random line between  
Sec 13 & 24

Variation  $19^{\circ}45'$  E.

40.00 Set temporary quarter section  
post.

80.18 Intersect Guide Meridian at  
post corner to Sec 13 & 24.

West. On a true line between Sec 13 & 24

40.09 Set a post for quarter section  
corner, drove a chain stake  
& raised a mound of earth,  
with trench and fills, as per  
instructions.

80.18 The corner to Sec 13, 14, 23, & 24.

Soil good 2<sup>nd</sup> rate  
Land level & rolling prairie

Township 3 N 3 E 6th Meridian  
Chains

North, Between Sec. 1 3 & 4

~~Variation 19 1/2 E~~

4000 Set a post for quarter section corner, drove a char'd stake & raised mound of earth, as per instructions.

8000 Set a post, for corner to sec. 11, 12, 13 & 14, drove a char'd stake & raised a mound of earth, with trench & pits as per instructions.

Land nearly level. Prairie  
Soil good & water



Township 3 N R 3 E Millomall Meridian  
chains

Cash. On a random line between  
sections 12 & 13.

Variation  $19^{\circ} 43' E$

40.00 Set a temporary quarter sec post

at 9.56 Intersect Grid Meridian 24th  
South of post. corner sec 12 & 13.

\$89.50 On true line between  
sec 12 & 13

39.78 Set a post for quarter section.

corner drove a chard stake &

raised a mound of earth,

with trench, & fills as per instructions.

49.56 The corner to sections 11, 12, 13 & 14,

Land & rolling prairie. Soil,

good 2<sup>nd</sup> state

Township of Range 30 E. T11 S11 N11 W11

North. Between sec 11 & 12,

~~Marsden 19 1/2 E~~

40.00 Set a post for quarter section corner drove a char'd stake & raised a mound of earth, with trench & pits as per instructions.

80.00 Set a post for corner sec 1 2, 11 & 12. Drove a char'd stake & raised a mound with trench and pits, as per instructions. Land level. Prairie. Soil good & good water

Township 3 N. Range 30 E. Willamette Meridian,  
chain

Cast On a random line between  
sections 1 & 12,

Variation  $20^{\circ}15' E$ ,

40.00 Set a temporary quarter sec. cor  
post.

79.55 Intersect Guide Meridian 30 E  
South of post, corner to sec.  
1 & 12.

89.47 On a true line between  
sec 1 & 12,

39.78 Set a post for quarter section  
corner, drove a char'd stake  
& raised a mound of earth  
with trench & pits as per instructions,

79.55 The corner to sections 1, 2, 11 & 12,  
Level level prairie. Soil  
good 2<sup>nd</sup> rate.

Township 3 Range 3 E. Tarrant Meridian  
chains

North, On a random line between sec  
1 & 2.

Variation 2035 E

40.00 Set a temporary post, for q. sec. corner.

~~70.11~~ Commence to ascend hill

83.11 Intersect North boundary of -50  
Township 3 & 4 East of post  
corner to sec. 1 & 2.

Sec 21 E. On a true line between  
sec. 1 & 2, commencing at

13.11 To top of ascent +50

43.11 Set a post for quarter section  
corner, drove a char'd stake  
& raised a mound of earth with  
trench & hills, as per instructions.

83.11 The corner to sec. 1, 2, 11 & 12.

Land gently rolling prairie,  
Soil good 2<sup>nd</sup> rate.

Oct. 18<sup>th</sup> 1860

Township 3 N Range 3 E, Willamette Mer.  
chains

North, Between Sec 3 & 4 1835

↳ Variation 22° 30' E,

Commenced to ascend Bluff

- 2,571 Sp. and Indian trail corner NWSE, 25
- 28.10 " Another " trail corner ESW,
- 31.00 To a Wagon Road " do
- 40.00 Set a quarter sec post, drove a char'd stake & raised mound of earth, with trench & pits as per instructions.
- 45.00 To another Wagon road branch of the above mentioned road corner NWSE leading to lower Wmatta,
- 80.00 Set a post for corner to Sec 2, 26, 27, 34 1835, drove a char'd stake & raised a mound of earth with trench & pits, as per instructions. Laid gently rolling prairie. Trail good 2<sup>nd</sup> rate

Township 3 N, R. 30 E, Willamette Meridian,  
Chains

East corner down line between

Sections 26, 27, 28 Variation, 21° 30' E,

~~30.00~~ ~~Trail runs N.W. & S.E.~~  
40.00 Set temporary quarter sec post

79.80 Intersect corner to sec<sup>s</sup> 25, 26, 27 & 28,  
at post.

Land gently rolling prairie,  
Soil good 2<sup>nd</sup> rate

West, On a true line between  
Sec<sup>s</sup> 26 & 27

39.90 Set a post for quarter section

39.90 corner, drove a char'd stake

raised mound of earth with

49.80 trench & pits, as per instructions,

49.80 ~~Trail runs N.W. & S.E.~~  
79.80 Chy corner to sec<sup>s</sup> 26, 27, 28 & 29,

79.80 Land gently rolling prairie.  
Soil good 2<sup>nd</sup> rate

Township 3, Range 30, T11N, R30E, S11N  
chain,

North, Between sec 26 & 27,

~~Variation 203° E,~~

40.00 Set post for quarter section  
corner. Drove a char'd stake  
raised mound, with trench  
spits, as per instructions,

80.00 Set a post for corner sec.  
22, 23, 26 & 27, drove a char'd  
stake & raised mound, with  
trench spits, as per instructions.

A short Oak in cascade range bears N 58° W,

& do " " " " " " N 75° W,

from this section post  
Soil good & rolling prairie  
Soil good & moderate

Township B. N. Range 3<sup>rd</sup> E. Tillewatt Precinct

Cash On a random line between Sec 23 & 26  
Variation 20° 45' E

37 To a Nail road corner NWSE

40.100 Set a temporary quarter sec post

80.70 Intersect <sup>N. & S. line</sup> ~~corner sec 23 & 24~~

~~25 & 26~~ at post corner to Sec

23, 24, 25 & 26

Test On a true line between  
sections 23 & 26

40.35 Set a post for quarter section  
corner, drove a char'd stake  
raised mound with trench  
& pits, as per instructions.

80.40 To a Nail before noted bears NWSE.

80.70 The corner to sec 22, 23, 26 & 27,  
Land gently rolling, nearly level  
prairie. Soil good 2<sup>nd</sup> rate



Township 3 N Range 3 E Willamette Meridian  
 Chms.

North Between Secs 22 & 23,

Variation  $24^{\circ} 13' E$ .

2.57 To Indian Trail before noted corner on sec.

40.00 Set a post for quarter section  
 corner. drove a char'd stake  
 raised mound with trench  
 spits as per instructions.

80.00 Set a post for corner to sec.

14, 15, 22 & 23 - Drove a  
 char'd stake & raised mound  
 with trench spits as per instructions.  
 Land gently rolling prairie, slightly  
 descending to the North Side  
 good 2nd rate.

Township 3 N Range 30 E Willamette Meridian  
Chains

Cash, On random line between  
Sec. 14 & 23

Variation 20° 30' E,

40.00 Set a temporary quarter sec post

80.18 Intersect <sup>line</sup> ~~corner to sec. 13, 14,~~

~~23 & 24, 1000s South of post~~

corner to Sec. 13, 14, 23 & 24

89.33 On a true line between

Sections 14 & 23

40.09 Set a post for quarter section

corner. drove a char'd stake

raised a mound of earth with

trench & hills, as per instructions,

80.18 The corner to sec. 14, 15, 22 & 23,

Land gently rolling prairie

Soil good 2nd rate

Township 3 N. Range 3 E. Hillman Co. Minn.  
Chambers

North. Between Secs., 14 & 15,

~~Variation 203 1/2~~

40.00 Set a post for quarter section  
corner. drove a char'd stake  
& raised mound of earth with  
trench & pits, as per instructions

80.00 Set a post for corner of Secs.,  
10, 11, 14 & 15. Drove a char'd  
stake & raised mound with  
trench & pits, as per instructions

Township 3, N. Range 30 E. Willamette Meridian

East. On a random line between Sec-  
11 & 14.

Variation 20° 30' E.

40.00 Set temporary quarter sec. post

49.94 Intersect corner to sec- 11, 12, 13,  
& 14, at post.

West. On a true line between Sec-  
11 & 14.

39.97 Set a post for quarter section corner

Drive a char'd stake & raised  
mound, with trench & pills as  
per instructions.

49.94 Set corner to sec- 10, 11, 14 & 15

Land gently rolling prairie,  
Soil good & 2<sup>nd</sup> rate

Survey of W. M. R. Willamette Merid.  
chain.

North Between Secs 10 & 11

Variation 20° 30' E

40.00 Set a post for quarter section  
corner from char'd stake  
& raised mound of earth,  
with trench & pills as per  
instructions.

80.00 Set a post for corner to Secs  
2, 3, 10, & 11. From a char'd  
stake & raised mound of  
earth with trench & pills as  
per instructions.

Large rolling prairie.  
Soil good 2<sup>nd</sup> quality

October 19th 1860

Township N. 3 Range 30 E Willamette Meridian  
chains

Cust. On a random line between  
Sections 2, 8, 11

Variation 20° 20' E

4000 Set temporary quarter section post  
79.76 Intersect corner to sec. 1, 2,  
11 & 12. at post.

Test. On a true line between  
Sections 2, 8, 11.

3988 Set a post for quarter section  
corner, drove a char'd stake  
raised mound of earth,  
with trench & pits as per  
instructions.

79.76 The post corner to sec. 2, 3,  
10 & 11.

Land nearly level prairie,  
Soil good 2nd rate

Township 3 N. Range 30 E. Willamette Mer.  
chains

Both, On a random line between  
Sections 2 & 3

Variation  $19^{\circ} 15' E$

41000 - Set a temporary quarter section  
post,

82.27' Intersect North boundary of  
Township 71 lks East of post

511030' On a true line between Sec.  
2 & 3,

4227' Set a post for quarter sec corner  
Drove a char'd Stake & raised  
mound with trench & pits  
as per instructions.

82.27' The post corner to sec 2, 3,  
10 & 11.

Land considerably rolling,  
Soil good Good rate

Township 3, Range 30 E, Willamette Mer. Chains.

North, Between Sections 33 & 34,  
~~Variation 19° 30' E.~~

35.16 To Hay road before noted corner NW Sec.

40.00 Set a post for quarter section

corner on gentle slope to the North - 50

Drive a char'd stake & raised

mound, with trench & pits, as

per instructions.

80.00 Set a post for corner to Sec. - 15

27, 28, 33, & 34.

Snow Pak 1<sup>st</sup> noted bears. N 37 W.

" " 2<sup>nd</sup> " " N 37 W.

Drive a char'd stake and

raised mound of earth with

trench & pits, as per instructions.

Land rolling prairie soil

good 2<sup>nd</sup> rate



Township 3 N Range 30 E Willamette Mer. chain

East, On a random line between sections 27 & 34

Variation 19° 45' E.

26.00 To a ~~Na~~ ~~road~~ ~~at~~ ~~before~~ ~~noted~~, to lower crossing on ~~the~~ ~~at~~ ~~till~~ ~~the~~ ~~line~~.

40.00 Set a temporary quarter sec post

79.50 <sup>N. line</sup> Intersect, ~~corner to sec 26, 27,~~

34 & 35. 9 lks North of post,

corner to sec., 26, 27, 34, & 35.

189.50 On a true line between

sections 27 & 34

39.75 Set a post for quarter section

corner, drove a char & stake raised mound of earth with trench & pits, as per instructions,

53.50 To Na you road corner N.W. & S.E.

79.50 The corner to sec., 27, 28, 33, & 34.

Land gently rolling with slight descent to the North Soil good 2nd rate

Township 3 N. Range 30 E. Tarrant Meridian  
Chains

North. Between Sec 27 & 28,

~~Variation 19° 45' E,~~

12.60 To Wagon road to Wmattariv Co. W.

40.00 Set a post for quarter sec  
corner, drove a chord stake &  
raised mound of earth, with trench  
spills - as per instructions.

80.00 Set a post for corner to sec<sup>s</sup>  
21, 22, 27, & 28. Drove a  
chord stake & raised mound  
of earth, with trench spills,  
as per instructions.

Snow Peak No 2 bears N 31° W  
from this post. Land rolling  
prairie, Soil good & moderate

Township 3 N Range 30 E Willamette Meridian  
Chambers

East. On random line between  
sec 22 & 27

Variation 21° E

- ~~16.04 Commence descending to hollow~~
- ~~25.14 Cross hollow & ascend -15 -15~~
- ~~30.04 To top of rocky point +25 +25~~
- 40.11 Set temporary quarter sec post
- 49.74 Intersect <sup>line</sup> corners to sec 22, 23,  
26 & 27, at post.

West. On a true line between <sup>27</sup> sec 22 & 27

- 39.87 Set a post for quarter sec  
corner, draw chain & stake etc  
as per instructions
- 49.74 Commence descent into hollow corner N.
- 54.74 Cross hollow & ascend -50
- 63.74 To top of bank +40 +40
- 79.74 The post corner to sec 21, 22,  
27 & 28
- Land & Soil same as last mile

Township 3 N Range 3 E Willamette Meridian,  
Maine

North, Between Secs 21 & 22,

~~Variation 2030' E,~~

4000 Set a post for quarter sec  
corner. Run a char'd stake  
& raised mound with trench  
spills, as per instructions.

8000 Set a post for corner to sec's  
15, 16, 21, & 22. Run a char'd  
stake & raised mound of earth,  
with trench spills, as per instructions.  
Land rolling prairie slight  
decent to the North, soil  
good 2nd rate.

Township 3 Range 30 Willamette Mer. chains

East, On a random line between sec. 15 & 22,

Variation. 19° 30' E

- ~~18.57~~ Commence descent to hollow corner,
- ~~24.17~~ Cross sandy hollow 3 ch wide & ascend 30
- ~~27.54~~ To top of rocky point +40
- 40.00 Set temporary quarter post,
- ~~42.20~~ To a trail corner, N W & S E
- ~~49.74~~ Intersect <sup>N & S line</sup> ~~corner to sec. 14 & 15~~

~~22 & 23~~ 78 lks North of post corner to sec. 14, 15, 22 & 23

89.27 N. On a true line between sec. 15 & 22

- 7.54 To a trail runs N W & S E,
- 39.87 Set post for quarter sec corner raised in <sup>4 ch or ch. slater,</sup> ~~normal~~ & as per instructions,
- 52.24 Commence descending rocky point
- 55.74 Cross hollow & com. ascending -40
- 61.24 To top of ascent +30
- 79.74 The corner to sec. 15, 76, 21 & 22, Land & Oil runs as last mile,

Township 3, Range 30, Willamette Meridian  
chs.

North, Between Sec 15 & 16.

Variation 19° 30' E

40.00 Set a post for quarter sec  
corner & draw a chur & state  
raised mound of earth,  
with trench & pits, as per instructions

80.00 Set a post for corner to sec 4  
9, 10, 15 & 16. Draw a chur &  
state raised mound of  
earth, with trench & pits as per  
instructions.

Land gently rolling prairie. Soil  
good & <sup>rich</sup> water

Township 3, Range 30 E, Willamette Mer  
Chains.

Cash. On a random line between  
sect. 10 & 15.

Variation  $21^{\circ}00' E$ .

40.00 Set a temporary quarter sec post,

~~53.00 To a trail course N. & S.~~

80.38 Intersect corner to sect. 11

11. 14 & 15 at post,

Test. On a true line between  
sect. 10 & 15.

25.38 To Indian trail course N. & S.

40.19 Set a post for quarter section

corner. Drove a char. stake

raised & mounded earth with

trench & pits as per instructions.

80.38 The post corner to sect. 9. 10

15 & 16.

Land gently rolling. Soil

good 2<sup>nd</sup> rate.

Township 3. N. Range 3. E. Willamette Mer.  
chs

North Between Sec<sup>s</sup> 9 & 10.

Variation N 1/2 E

110.00 Set a post for quarter section  
corner, drove a char'd stake  
& raised a mound of earth  
with trench & pits as per instructions.

80.00 Set a post for corner to sec. 3. 4  
9 & 10. Drove a char'd stake  
& raised mound of earth,  
with trench and pits as per  
instructions.

Land gently rolling prairie  
Soil good & moderate



Township 3, N. Range 30 E. Millard Co. Mo.,  
Chains.

East. On random line between Sec 3 & 10.  
Variation. 19° 35' E

- 38.00 To Indian Trail corner sec. 3 & 10.
- 40.00 Set a temporary quarter sec post.
- 80.46 Intersect corners sec. 2, 3, 10 & 11, at post.

West. On a true line between sec 3 & 10.

- 40.23 Set a post for quarter sec corner, drove a hard stake & raised mound of earth, with trench, and pits, as per instructions.
- 42.46 To Indian Trail corner sec 3 & 10.
- 80.46 The corners to sec. 3, 4, 9 & 10, sand & gravel rolling prairie. Soil good 2<sup>nd</sup> grade.

Township 3, N. R. 3, E. Willamette Meridian  
Main

North, On a random line between Sec 3 & 4

~~Variation 19° 35' E.~~

40.00 Set a temporary quarter section post

81.75 Intersect North boundary of

81.75 Township 31 N. East of post,  
corner to sec - 3, & 4,

S 00° 13' E. On a true line between Sec. 3 & 4

41.75 Set a post for quarter section

41.75 corner, drove a char'd stake  
raised mound of earth, with  
trench & pits, as per instructions;

81.75 The corner to sec. 3, 4, 9, 8, 10,

91.75 Land, rolling prairie, soil  
good 2<sup>nd</sup> Rate

October 20<sup>th</sup> 1860

W. H. May, Jr. D.M.M.

Township 3. N. R. 30. E. Willamette Meridian  
chains

North, Between Sec 32 & 33

Variation 20° 30' E.

Ascend rocky bluff from post

5.00 To top of bluff facing to the South. +200

38.00 To a Wagon road first noted from  
Dallas to Walla Walla, & N.W.

40.00 Set a post for quarter section corner,  
Drove a char'd stake raised mound heel  
of earth, with trench & pits as per insts

74.00 To Indian Trail corner N.W. & S.E.

80.00 Set a post for corner to Sec. 28.

28, 29, 32, & 33. Drove char'd  
stake raised mound of earth,  
with trench & pits as per  
instructions, Land on bluff  
rocky 3<sup>rd</sup> rate soil, balance  
gently rising prairie. Soil  
good 2<sup>nd</sup> rate

Township 3 Range 3 E. Tillamette Miss  
chains

East. On a random line between Sec 28 & 33.  
Variation 21° 00' E

40.00  
40.00 Set a temporary quarter section post  
80.40 Intersect corner to Sec 27 & 28.  
80.40 33 834, at post.

West. On a true line between Sec 28 & 33

40.20 Set a post for quarter section  
corner, drive a hard stake &  
raised mound with trench &  
pits, as per instructions.

80.40 The post corner to Sec 28  
80.40 29, 32 & 33.  
Sand rolling same as last  
miles.

Township 3, Range 306, Willamette Merit,  
chains

North, Between Sec. 28 & 29,  
~~Passation 21<sup>st</sup>~~

41.00 Set a post for quarter section  
52.00 Wagon road from N.W. + S.E.  
corner. Drove a char'd stake,  
raised mound of earth, with  
trench & pits, as per instructions,

80.00 Set a post for corner to sec-  
20, 21, 28, 29. Drove a  
char'd stake & raised mound  
with trench & pits as per in-  
-structions.  
Sand & Bail same as last  
miles

Township 3, R3, E Willamette Meridian,  
Chains.

Cast On a random line between Sec 21 & 28

Variation 20° 00' E

40.00  
40.11 Set a temporary quarter section

79.80 Intersect corner to sec. 21, 22,

79.80 27 & 28, at post.

Post On a true line between Sec  
21 & 28

39.90 Set a post for quarter section  
39.90 corner, drove a char'd stake  
raised mound, with trench  
spills, as per instructions,

79.80 The post corner to sec. 21, 21

79.80 28 & 29.

Land rolling prairie. Soil  
good & rate

Township 3 N. Range 30 E. Hillman to Meridian,  
Chains

North, Between Sec 20 & 21,

~~Paradise 20 & 21~~

40.00 Set a post for quarter section  
corner, drove a char'd stake  
raised mound of earth with  
trench & pits as per instructions,

80.00 Set a post for corner to sec-  
10, 17, 20 & 21. Drove a char'd  
stake, raised a mound of  
earth, with trench & pits as per  
instructions.

Land has a slight descent to the  
North, mostly rolling prairie. Soil  
good 2nd rate,

Township 3 N, Range 30 E, Willamette Meridian  
chains

Cast On a random line between  
Sections 16 & 21.

Variation 20° 00' E

40.00  
44.00 Set a temporary quarter sec post  
79.09 Intersect corners sections 15,  
79.09 16, 21 & 22, at post

West On a true line between Sec  
16 & 21

39 54 1/2 Set a post for quarter section  
39.54 1/2 corner, drove a bar & stake  
& raised mound of earth with  
trench & fills, as per instructions,  
79.09 The post corners to sections 16, 17,  
79.09 20 & 21.

Land rolling prairie, soil  
good 2nd rate,



Township 3<sup>d</sup> N. Range 3<sup>d</sup> E. Willamette Merid.  
chains

North, Between Sect 16 & 17

~~Meridian 2<sup>o</sup> 15' E~~

410.00 Set a post for quarter section  
corner, drove a char'd stake  
& raised mound of earth, with  
trench & pits, as per instructions,

42.57 Indian Trail corner NE & SE.

80.00 Set a post for corner to sec 10 &  
9. 16 & 17. Drove a char'd stake  
& raised mound of earth, with  
trench & pits, as per instructions,  
Land rolling prairie,  
Soil good 2<sup>nd</sup> rate,

Township 3 Range 3 E. Milamette Meridian  
chains

Cash, On a random line between sec  
9 & 16.

11.15

Variation 30° 00' E.

~~11.15 To a trail corner N. E. S. N.~~

40.00

40.00 Set a temporary quarter sec post

57.00

~~57.00 To hollow N. S. line~~

-25

79.65

79.65 Intersect, corners to sec 9, 10, level

~~15 & 16, 52 lbs. North of post~~

corners to sec 9, 10, 15, & 16.

1893 On a line between sec

22.65 9 & 16.

22.65 To hollow & ascend

-25

39.83 Set a post for quarter section

39.83

corner, drove a hard stake

raised mound of earth, with,

68.50

trench & pits, as per instructions,

68.50

To Indian trail corner N. E. S. N.

79.66

The post corner to sections 8, 9, 16 & 17,

79.66

land rolling prairie, soil good

2nd rate

Township 3 N R 30 E Willamette Meridian,  
Chain.

North, Between Secs. 8 & 9.

~~Variation 20' or 30'~~

40.00 Set a post for quarter section  
corner. Drove a char'd stake  
raised mound with trench  
spits, as per instructions.

80.00 Set a post for corner to sec. 11 betw  
4, 5, 8, 9. Drove a char'd  
stake raised mound of earth  
with trench spits, as per in-  
structions.

Sand rolling prairie soil  
good 2nd Rate

October 2<sup>nd</sup> 1860

Township 3, N Range 3, W 6th Meridian  
Chains

Cast, On a random line between  
Sec 4 & 9.

Variation 21° 00' E

Commenced ascending from post reading

25.04 To trail in 1/4 S. in hollow, 3 chs wide ascend - 150

27.40 To top of ascent + 154

40.00 Set temporary quarter sec post

49.64 Intersect <sup>N 20 S line</sup> corner to sections 3 & 4

4.9 3 4.4 2 1/2 chs South of post

corner to 3, 4, 9 & 10

59.48 On a true line between  
sections 4 & 9.

39.82 Set a post for quarter section  
corner, drove a char'd stake &  
raised mound of earth, with trench

52.24 pits, as per instructions,

52.24 Commenced

57.14 To trail hollow of descent Sec. - 150

49.64 The post corner to sec 4, 5, 8, 9

Land considerable rolling prairie  
Soil good 2<sup>nd</sup> rate

46 86

Township 3 N Range 30 E Willamette Meridian,  
Chasing

North. On a random line between Sect 4 & 5  
Variation 21° 00' E.

Common ascent

- 16.57 To top of ascent & descent +100
- 40.00 Set temporary quarter sec post 150
- ~~70.00~~ To foot of descent 150 50
- 80.00 Common ascent 50
- 82.62 Intersect North boundary +50  
of Township 3 N R 30 E East  
of post. corner to Sect 4 N 50  
Rock Mountain

41  
87

Township 3. N R 30 E Willamette Meridian  
Chains

- Sec 14 On a true line between Sec 4 & 5.
- 2.62 To foot of descent - 50
- 12.62 Commence ascending
- 42.62 Set apart for quarter section + 50  
corner, drive a char'd stake  
raised a mound of earth,  
with trench spills, as per instructions
- 66.12 To top of ascent & descend + 50
- 82.62 The post corner to section 4, 5,
- 82.62 89.

Land considerable rolling prairie.  
Soil good 2<sup>nd</sup> rate.

Township 3 Range 30 E. Hill, Mead,  
Chains

North, Between Sec 31 & 32.

Variation  $23^{\circ}$  E

Ascend from sec. post

25.35 To top of bluff facing South +200

" " Indian Trail corner S.W. N.E. +200

30.00 Another Trail " " "

40.00 Set a post for quarter sec corner and  
draw a char'd stake raised  
mound, with trench & pits.

as per instructions,

40.70 To a High Road corner S.W. N.E.

80.00 Set a post for corner to sec "

29, 30, 31, & 32. Draw a char'd  
stake & raised mound of earth,

with trench & pits as per instructions;

Found the 1<sup>st</sup> & 2<sup>nd</sup> Ch's 3<sup>rd</sup> Rate & price  
balance good 2<sup>nd</sup> rate slightly  
raining.

Township 8, N. 30, E. Willamette Merid.  
chs.

Set a random line between  
Sections 29 & 32.

Variation 21° 30' E.

40.00 Set a temporary quarter section  
post.

~~72.79 To an Indian Trail runs N 45° E.~~

81.08 Intersect <sup>N 45° E line</sup> corner to sec 28, 29,

~~32 & 33~~ 1" NW North east corner  
to sec 28, 29, 32 & 33

Set a random line between  
Sections 29 & 32.

72.29 To Indian Trail runs N 45° E.

40.04 Set a post for quarter section  
corner, drove a char'd stake  
raised mound of earth, with  
trunk & hills, as per instructions;

80.08 The corner to sec 29, 31, 34 & 32.

80.08 Land gently rolling prairie,  
Soil good & moderate



Township 3, R. 30 E, Willamette Meridian  
chains

West On a random line between  
sections 30 & 31.

~~Variation 210° E~~

- 40.00 Set a temporary quarter section post
- ~~41.50 Commence to descend~~
- ~~53.25 To foot of descent~~ 100
- ~~61.00 Commence ascending~~
- ~~65.50 To top of ascent & commence descent~~ 25
- ~~78.50 To foot of descent & Nail SW. 1/4~~ 30
- ~~81.00 Commence ascent~~
- 87.37 Intersect West boundary of Township  
1600's North of post, come to  
sec. 30 & 31.

Township 3 N. Range 3 E. Willamette Merid.  
chs

799<sup>30</sup> E. On a true line between  
sections 30 & 31, common descent,

799<sup>31</sup> To foot of descent -25

8. 8<sup>32</sup> To trail SWSE. Common ascent,

91. 8<sup>31</sup> To top of ascent & common ascent +30

96. 00 To foot of descent -25

32. 12 Commence ascent

45. 8<sup>31</sup> To top of ascent +100

47. 3<sup>31</sup> To post for quarter section

corner, drove a char'd stake  
raised mound of earth,  
with trench & pits, as per instructions

8<sup>31</sup> The post, corner sec. 29,

87. 37 30, 31, & 32.

Land considerably rolling prairie,  
Soil good 2<sup>nd</sup> - paten

October 23<sup>rd</sup> 1860

Township 3 N Range 3 E. Willamette Mer.  
chains

North, Between Secs 29 & 31,

~~Meridian 21<sup>st</sup> 1/2<sup>mi</sup>~~

40.00 Set a post for quarter section  
corner, drove a char'd stake  
& raised mound of earth,  
with trench & pits as per instructions.

80.00 Set a post for corner sec.  
19, 20, 29 & 30. Drove a char'd  
stake & raised mound of earth,  
with trench & pits, as per instructions.

Land rolling prairie. Soil  
good 2<sup>nd</sup> rate.

Township 3, N. R. 3, E. Willamette Meridian,  
chs

Cast, On a random line between  
sections. 20 & 29.

Variation 20° 00' E,

~~21.00 To a Trail corner N.W. & S.E.~~

~~32.50 To a Wagon road " " "~~

41.00 Set temporary quarter section post

49.11 Intersect, <sup>N.W. line</sup> ~~connects sec 20, 21~~

~~28 & 29, 26 lks. North of post, connect~~

~~Sec. 20, 21, 28 & 29,~~

89.41 On a true line between  
sections. 20, & 29.

39.58 Set a post for quarter section

39.53

corner, drove a char'd stake  
raised mound with trowel,  
spills, as per instructions.

46.54 To Wagon road corner N.W. & S.E.

58.07 To a Trail " do do

79.07 The corner sections 19, 20, 29 & 30

79.07 Land rolling prairie, soil  
good 3rd rate

Township 3. N Range 30 E. Tiltamott Meridian  
Chain

Mesh On a random line between,  
sections. 19 & 30.

Variation  $24^{\circ} 15' E$

40.00 Set a temporary quarter section post  
89.00 Intersect West boundary of  
Township 49 Ns North of post  
corner to sec. 19 & 30.

$N 89^{\circ} 39' E$ . On a true line between  
sec. 19 & 30.

Variation  $24^{\circ} 15' E$

49.00 Set a post for quarter section corner,  
drove a char & stake & raised  
mound of earth, with trench & hills  
as per instructions.

89.00 The post corner to sec. 19, 20,  
29 & 30.

Land genly saline prairie.  
Soil good  $2\frac{1}{2}$  rates

53  
95

Township 3, Range 30, T114 North Meridian,  
Maine

North Between Sec 19 & 20.

Variation  $20^{\circ} E$

27.00 On Hay road N Rail road NW & SE.

40.00 Set a post for quarter sec.

40.00

corner. drove a char'd  
stake & raised a mound  
of earth, with trench & fills,  
as per instructions.

80.00 Set a post for corner to sec. 19.

80.00

17, 18, 19, & 20. Drove a char'd  
stake, & raised a mound of  
earth, with trench & fills,  
as per instructions.

Land gently rolling prairie,  
Soil good & 2nd rate.

October 27<sup>th</sup> 1860

Township 3 N. Range 30 E. Tullamath Meridian  
chains

East, On a random line between  
sec. 17 & 20.

Variation  $20^{\circ} 45' E$

40.00 Set a temporary quarter section  
post.

80.06 Intersect <sup>at S. Sim</sup> corner to sec. 16, 17,  
21 & 21, 2000 ft. North of post,  
corner to sec. 16, 17, 20 & 21.

1895 N. On a true line between  
sec. 17 & 20.

40.03 Set a post for quarter section  
corner, drove a charred stake  
& raised a mound of earth,  
with trench & hills, as per instructions

80.04 The post corner to sec. 17  
18, 19, & 20.

Sand land prairie soil  
good 2<sup>nd</sup> rating

Township T. 1. Range 3. E. 11th Meridian,  
Maine.

West. On a random line between  
sec 18 & 19.

Variation 20° 45' E

~~8.00 Commenced descent.~~

~~25.50 To foot of do~~

40.00

~~1000~~

40.00 Set a temporary quarter section post

89.61 Intersect West boundary of Town-

ship. at post. corner to sec

18 & 19. Sand rolling prairie

East. On a true line between sec 18 & 19

49.61

Variation 20° 45' E

49.61 Set a post for quarter section level

corner, drove a char'd stake

raised a mound of earth with

64.11 trench & pits, as per instructions.

64.11 Common ascending ridge

81.61 To top of ascent

1100

89.61 The post corner to sec. 17 18 19 & 20,

89.61

Sand rolling prairie. Soil good  
good rate.



Township North R30E Willamette Merid  
chains

North, Between sec 1<sup>st</sup> & 8<sup>th</sup>

Variation ~~20~~ 45<sup>th</sup> E.

31.00 Commence descending, Trail N. E. & S. W.

40.00 Set a post for quarter section corner, drove a chard stake & raised a mound of earth, with trench & pits, as per instructions.

72.50 Foot of descent

40

80.00 Set a post for corner to Sec. 1<sup>st</sup> & 8<sup>th</sup>, N. E. 1<sup>st</sup> 8<sup>th</sup>. Drove a chard stake & raised a mound of earth, with trench and pits, as per instructions.

Sand & silty prairie soil,  
good ~~water~~

October 23<sup>rd</sup> 1860

Township 3 N. Range 3 E. Willamette Meridian,  
Chains.

Cast. On a random line between  
sections 8 & 17

Variation 20° 15' E.

40.00  
40.00 Set a temporary quarter section  
19.60 ~~Intersect <sup>at 8. line</sup> corner to sec. 8, 9,~~  
39.60 ~~10 & 17. 5 2 Mts. North of post~~  
corner to Sec. 8, 9, 16 & 17.

Set 3/4 N. On a true line between  
sections 8 & 17

39.80 Set a post for quarter section  
39.80 corner, drove a char'd stake  
& raised a mound of earth,  
with trench & pits as per instructions,  
19.60 The post corner to sec. 7, 8,  
9.60 17 & 18. Sand & silt & prairie  
Soil good 2nd rate

Township 3. N. Range 3. E. Hillamette Merid  
chains

West On a random line between  
sections 7 & 18.

~~Variation 30° 15' E~~

40.00 Set a temporary quarter sec post  
89.50 Intersect West boundary of  
Township, 16th North of  
corner to sec. 7 & 18.

89.53 E. On a true line between sec 7 & 18

~~Variation 20° 15' E~~

49.50 Set a post for quarter sec.  
corner. Drive a char'd stake  
driven. Formed with trench  
spits, as per instructions.

89.50 The post corner to sections  
7 & 17 & 18.

Land gently rolling prairie.  
Soil good 2<sup>nd</sup> rate.

Township 3, Range 3, Hillmanette Meridian  
Chs

North, Between Sections of 88.  
Variation 21° 15' E.

40.00 Set post for quarter sec. corner  
Drove a chard. stake & raised  
mound of earth, as with trench  
& pits, as per instructions.

80.00 Set a post for corner to sec.  
T. 3, R. 3. Drove a chard.  
stake raised mound of  
earth, with trench & pits, as  
per instructions.

Land gently rolling, soil  
good 2nd rate.

Township No 3 R30E T10Nth Merid.  
chain.

Cast, On a random line between  
Sections 5 & 8.

Variation 20° 5' E

40.00 Set temporary quarter section  
post. Drove a charred stake  
~~raised mound of earth,~~  
~~with trench pits, as per instructions~~

49.70 Intersect corner sec 4, 5,  
8 & 9. 300 ft. North of post.

corner sec 4 5 8 & 9.

49.75 On a true line between  
sections 5 & 8.

39.85 Set a post for quarter sec.  
corner. Drove a charred stake  
raised mound of earth  
with pits & trench as per instructions.

49.70 The post corner to sections  
5, 6, 7, 8.

Saved & Sail comes  
last mile

Township 23<sup>rd</sup> N. R. 3<sup>rd</sup> E. Hillman Mer.  
chains.

Set on a random line  
between sections 6 & 7

Variation 2115<sup>th</sup> E

40.00 Set temporary quarter section  
post. -50

89.78 Intersect West boundary of -25  
Township 23<sup>rd</sup> N. R. 3<sup>rd</sup> E. South of post

Set on a true line between  
sect. 6 & 7.

49.78 Set a post for quarter section +25  
corner. drove a char'd stake  
raised mound of earth with  
trench & pits, as per instructions.

89.78 The corner to sect. 6 & 7 +50  
Sand & Soil the same as  
last miles.

Township 3, N, Range 3, E, Tarrant Merid.  
chains

North, On a random line  
between Sec 5 & 6,

Variation 20° 15' E.

40.00 Set a temporary quarter sec. post

~~45.00 Commence descent~~

~~65.00 To foot of descent~~

-100

~~69.00 To a Nail E. W. corner~~

81.09 Intersect North boundary +100

of Township 5 links East of  
post. corner to Sec. 5 & 6.

S 22° E. On a line between Sec 5 & 6  
commence descent from post.

11.49 To foot of descent by Nail running E. W. -100

16.09 Commence ascending

36.09 To top of ascent +100

41.09 Set a post for quarter sec corner

drove a char'd Stake & raised

ground 4 in, with trench filled as per instr.

81.09 The corner to Sec 5 & 6 - 7 & 8.

Sand rolling prairie soil

2nd rate, Oct 26<sup>th</sup> 1860

General Description

65  
105

This Township of land is very desirable for grazing purposes. It is good Soil for Wheat & Oats. It is handsomely situated on the Halla Halla Road, many sections are nearly level, & producing the best quality of grass for all kinds of Stock, & an abundance of it.

The Wmattla river runs through Section 31. The hollow is about one quarter of a mile wide & heavily timbered with Palm of Silead Alder, Willow, Crabapple & Hawker. The quality of the land on the river bluff is poor, the balance is good 2<sup>nd</sup> rate. The Wmattla river is about 150 to 200 links wide, & runs generally in a N. W. course, overflowing its banks generally except the bluffs.



## List of Names.

List of the names of the individuals employed to assist in running, measuring, or marking the lines and corners described in the foregoing field notes, of Township No 3 North of the base line of Range No 30 East of the Willamette Meridian, showing the capacities in which they acted is

Samuel Campbell Chairman  
 Josephus Tompkins do  
 Robert Handfield do

We hereby certify that we assisted  
 Saml Campbell deputy surveyor,  
 in surveying the subdivisinal  
 lines of Township No 3 North  
 of the base line of Range number  
 Thirty East of the

Pillmate Meridian, and that  
said Township has been in all  
respects, to the best of our knowl-  
-edge and belief, well and  
faithfully surveyed, and the  
boundary monuments planted  
according to the instructions  
furnished by the Surveyor General,

Samuel L Campbell Chairman.  
Josephus Tompkins Chairman  
Robert F. Caufield Assnary

Subscribed and sworn to  
before me at Oregon City this  
3<sup>rd</sup> day of Decr AD 1860

Jas Winston  
Clerk of the Circuit  
Court for the County  
of Clatsop as State  
of Oregon

69  
189

Wm. Campbell deputy surveyor,  
do solemnly swear that, in  
pursuance of a contract with  
W. W. Chapman Surveyor of the  
public lands of the United States,  
in the State of Oregon, bearing  
date the 19<sup>th</sup> day of September,  
1860, and in strict conformity  
to the laws of the United States,  
and the instructions furnished by  
the Surveyor General, I have  
faithfully surveyed the subdivi-  
sional lines of Township No. 11  
Three North of the base line of Range  
number thirty East of the Willamette  
Meridian, in the State aforesaid,  
and do further solemnly swear  
that the foregoing are the true  
and original field notes of  
such survey of Wm. Campbell  
deputy Surveyor

Subscribed and sworn

119

To Before me at Oregon  
City this 3<sup>rd</sup> day of Dec  
A.D. 1860

John Wessington  
Clerk of the Circuit  
Court for the County  
of Lincoln in the State  
of Oregon

110A

Sur General's Office  
Eugene City, Jan'y 29<sup>th</sup> 1861.  
The foregoing field notes of the  
survey of the subdivisions of Town-  
ships No. 3 North, Range No. 30  
East of the Willamette Meridian  
executed by Wm. B. Campbell, dep-  
uty Surveyor, under his contract  
of the 19<sup>th</sup> day of September 1860:  
having been critically exam-  
ined, the necessary corrections  
and explanations made the  
said field notes and the sur-  
veys they describe are hereby  
approved.

W. W. Chapman

Sur: General of Oregon