

Field notes of the Survey of the Subdivisions
of Township 3 North of the base line of Range
32 East of the Willamette Meridian by David
Chaplin deputy Surveyor under his contract
No. 1071 bearing date the 31st day of September
1864

Commenced October 25th 1864

Completed October 30th 1864

Index

Referring the lines to the pages of the field notes
Town 3 N R. 32 East Will. Mer.

6	103	5	95	4	89	3	83	2	78	1
102		102		94		88		83		77
7	101	8	94	9	88	10	82	11	77	12
101		100		93		87		82		76
18	100	17	93	16	87	15	81	14	76	13
99		99		92		86		81		75
19	98	20	92	21	86	22	80	23	75	24
98		97		91		85		80		74
30	97	29	91	28	85	27	79	26	74	25
96		96		90		84		79		73
31	95	32	90	33	84	34	78	35	73	36

273

273C 73

Township 3 North Range

North between Secs 35 & 36

4000 Set stone 14x8x6 for 1/4 Sec cor. 36

8000 Set post for corner tases 25, 26, 35 & 36

in corner of Earth with Charred Stake
pits & as per instructions

Land gently rolling

Soil good & well water

Eastern boundary between Secs 25 & 36

4000 Set post for temporary 1/4 Sec. cor.

8000 Intersect East boundary 20 M South
of corner tases 25 & 36 from which I run

S 89° 51' W. on a true line between Secs 25 & 36

4000 Set Stone 15x14x6 for 1/4 Sec. cor.

8000 The corner tases 25, 26, 35 & 36

Land gently rolling

Soil good & well water

32 East Willamette Meridian
North between Secs 25 & 26

Chains Pa. 20° E.

- 4000 Set post for 1/4 Sec. cor. in corner of
East with charna stake pits & as per instructions
7725 Matilla & Walla Koa bears S 78° E
8000 Set post for corner to Secs 23, 24, 25 & 26
in corner of East with charna stake
pits & as per instructions
Level Level. Soil goes 2nd part
-

East on a ranam line between Secs 24 & 25

- 4000 Set post for temporary 1/4 sec corner
8020 Intersect East boundary 24th S of
corner to Secs 24 & 25 from which corner line
S 89° 30' W on a true line between Secs 24 & 25
4010 Set post for 1/4 Sec. cor. in corner of East
with charna stake pits & as per instructions
4800 Matilla & Walla Walla Koa bears N 8° 15' W
8020 The corner to Secs 23, 24, 25 & 26
Level Level. Soil 1st part

Township 3 North Range
North between Secs 23 & 24

chains pa 19 1/2 East

4000 Set post for 1/4 Sec. cor. in manner East
with Charms Stake pits & Casper instructions

8000 Set post for corner to Secs 13, 14, 23 & 24
in manner of East with Charms Stake
pits & Casper instructions

Level rolling. Soil good ³⁰⁰⁰ rate

East on a remnant line between Secs 13 & 24

4000 Set post for temporary 1/4 Sec. cor.

8039 Intersect East boundary S 4 1/2 W South
of corner to Secs 13 & 24 from which I run

S 89.37 W. on a true line between Secs 13 & 24

4020 Set post for 1/4 Sec. cor. in manner of East
with Charms Stake pits & Casper instructions

8039 The corner to Secs 13, 14, 23 & 24

Level Level

Soil 1 1/2 rate

32 East Willamette Meridian
North between Secs 13 & 14

chains per. 20° E.

4000 Set post for $\frac{1}{4}$ Sec. cor. in Monong Earth
with charred stake pits & copper instructions

8000 Set post for corner to secs 11, 12, 13 & 14 in
Monong Earth with charred stake pits
& copper instructions

Same gully rolling. Soil $\frac{1}{2}$ rate

Eastona Meridian line between Secs 12 & 13

4000 Set post for temporary $\frac{1}{4}$ Sec corner

7980 Intersect East boundary 30 Ms South
S of corner to secs 12 & 13 from which I run

S 89° 47' W. on a true line between Secs 12 & 13

3990 Set post for $\frac{1}{4}$ Sec. cor. in Monong Earth

3990 with charred stake pits & copper instructions

7980 The corner to secs 11, 12, 13 & 14

7980 Same gully rolling

Soil $\frac{1}{2}$ rate

heavy pine Graps

277

77

Township 3 North Range
North Section Secs 11 & 12

Chains Bea. 20° E.

2000 Ravine near West

4000 Set post for $\frac{1}{4}$ Sec. cor. in mound of earth
with charred stake pits & asper instructions

8000 Set post for corner to Secs 1, 2, 11 & 12 in
in mound of earth with charred
stake pits & asper instructions
Same Level Soil $\frac{1}{2}$ rate

East on a random line between Secs 11 & 12

4000 Set post for temporary $\frac{1}{4}$ Sec. cor.

8030 Intersect East boundary at corner to
Secs 11 & 12 from which I run

West on a true line between Secs 11 & 12

4015 Set post for $\frac{1}{4}$ Sec. cor. in mound of earth
with charred stake pits & asper instructions

8030 The corner to Secs 1, 2, 11 & 12
Same Level. Soil $\frac{1}{2}$ rate

279

99

Township 3 North Range

Eastern corner line between Secs 26 & 35
4000 Set post for temporary 1/4 Sec. cor.

79.80 Intersect N & S Line 35-Ms North
of corner to Secs 25, 26, 35 & 36 from which I run

N 89° 45' W on a true line between Secs 26 & 35-

39.90 Set post for 1/4 Sec. cor. in corner of East
with charred stake pits & as per instructions

69.00 Walla Walla & Matilla Road about N 88° W

79.80 The corner to Secs 26, 27, 34 & 35.

Level Level

Soil 1st rate

North between Secs 26 & 27

N. 20 1/4 E.

4000 Set post for 1/4 Sec. cor. in corner of East
with charred stake pits & as per instructions

8000 Set post for corner to Secs 22, 23, 26 & 27
in corner of East with charred stake pits
& as per instructions

Level Level. Great Plain

Soil 1st rate

32 East Willamette Meridian

Easton a random line between Secs 23 & 26

Chairs

4000 Set post for temporary $\frac{1}{4}$ sec. cor.

7980 Intersect N & S line at corner to sec

23, 24, 25 & 26 from which corner I run

West on a true line between Secs 23 & 26

3990 Set post for $\frac{1}{4}$ sec corner in corner of

Earth with chains stake pits & as per instructions

7980 The corner to sec 22, 23, 26 & 27

Land gently rolling

Soil $\frac{1}{2}$ ^{or} better

North between Secs 22 & 23

Pa. 20 $\frac{1}{2}$ E.

4000 Set post for $\frac{1}{4}$ sec corner in corner of Earth

with chains stake pits & as per instructions

8000 Set post for corner to sec 14, 15, 22 & 23 in corner

of Earth with chains stake pits & as per

instructions

Land level grass plain

Soil $\frac{1}{2}$ better

Township 3 North Range

Eastena corner on line between Secs 14 & 23
 @hains

4000 Set temporary $\frac{1}{4}$ Sec. cor.

79.75. Intersect N & S line at corner Secs

13, 14, 23 & 24 from which I run

Westena true line between Secs 14 & 23

39.88 Set post for $\frac{1}{4}$ Sec corner in mound of earth
 with charred stake pits & as per instructions

79.75. The corner to Secs 14, 15, 22 & 23

Ground gently rolling. Soil 1st rate

North between Secs 14 & 15

ba. 20° E.

4000 Set post for $\frac{1}{4}$ Sec. cor. in mound of earth
 with charred stake pits & as per instructions

64.50 Ravine bears West

8000 Set post for corner to Secs 10, 14 & 15

in mound of earth with charred stake
 pits & as per instructions

Ground Level. Soil 1st rate

- 32 East Willamette Meridian
 Easton a ranam line between Secs 11 & 14
 chains
 4000 Set temporary 1/4 Sec corner
 7985 Intersect N & S line at corner to Secs
 11, 12, 13 & 14 from which corner from
 Weston a true line between Secs 11 & 14
 2200 Ravine bears S W
 3992 Set post for 1/4 Sec cor. in Monna of Earth
 with charred stake pits & copper instructions
 7985 The corner to Secs 10, 11, 14 & 15
 General Level. Soil good 2 ^{out}/₄ rate

North between Secs 10 & 11
 (ba. 204° E.

- 4000 Set post for 1/4 Sec cor. in Monna of Earth
 with charred stake pits & copper instructions
 8000 Set post for corner to Secs 2, 3, 10 & 11
 in Monna of Earth with charred stake pits
 & copper instructions
 General Level
 Soil good 2 ^{out}/₄ rate

Township 3 North Range
 Eastern boundary line between Secs 2811
 4000 Set post temporary $\frac{1}{4}$ Sec. cor.

7950 Intersect N & S Line at corner trees
 1, 2, 11 & 12 from which corner Iron
 West on a true line between Secs 2811

3975 Set post for $\frac{1}{4}$ Sec. cor. in Manna grass
 with charred stake pits & Casper instructions

7950 The corner trees 2, 3, 10 & 11
 Level Soil good 2nd rate

Northern boundary line between Secs 283
 pa. 20° E.

4000 Set post for temporary $\frac{1}{4}$ Sec corner

8060 Intersect North boundary 30 Ms West
 of corner trees 283 from which Iron
 No 13' N on a true line between Secs 283

4060 Set post for $\frac{1}{4}$ Sec corner in Manna grass
 with charred stake pits & Casper instructions

8060 The corner trees 2, 3, 10 & 11

Level gently rolling

Soil good 2nd rate

October 26th 1864

32 East Willamette Meridian
North between Secs 33 & 34

4000 Set Stone 18x12x4 for 1/4 Sec. cor.

8000 Set post post for corner to secs 33 & 34. 27 & 28
in Monna of Earth with Charred Stake pits
& as per instructions

Level Level Graph Plain

Soil good good rate

Eastern a ranam line between Secs 27 & 34

4000 Set post for temporary 1/4 Sec. cor.

80.75 Intersect at N + S Line 27 Ws north of corner
to secs 26, 27, 34 & 35 from which I run

N 89° 48' W. on a true line between Secs 27 & 34

4037 Set post for 1/4 Sec. cor. in Monna of
Earth with Charred Stake pits & as per instructions

80.75 The corner to secs 27, 28, 33 & 34

80.75 Level Level Graph Plain

Soil good good rate

Township 3 North Range
North between Secs 27 & 28
chains $\text{bear } 20^{\circ} \text{ E.}$

40.00 Set post for $\frac{1}{4}$ sec. cor. in Monong Earth
with charred stake pits & Casper instructions
80.50 Set post for corner to Secs 21, 22, 27 & 28
in Monong Earth with charred stake
pits & Casper instructions
Lower Level. Soil Potate

Eastern boundary line between Secs 22 & 27
40.00 Set post for temporary $\frac{1}{4}$ sec corner
80.50 Intersect $\frac{1}{4}$ & $\frac{1}{2}$ Line 25 $\frac{1}{2}$ Ms North of
corner to Secs 22, 23, 26 & 27 from which run
 $N 89^{\circ} 49' W.$ one true line between Secs 22 & 27
40.25; Set post for $\frac{1}{4}$ sec corner in Monong Earth
with charred stake pits & Casper instructions
80.50 The corner to Secs 21, 22, 27 & 28
Lower Level. Soil good 2000 $\frac{1}{2}$ acre

32 East Willamette Meridian
North between Secs 21 & 22
chains pa. 19° E.

4000 Set post for $\frac{1}{4}$ Sec. cor. in corner of East
with Charney Stake pits & Casper instructions

8000 Set post for corner to Secs 15, 16, 21 & 22 in
corner of East with Charney Stake
pits & Casper instructions

Ground gently rolling

Soil good 2nd rate

East on a random line between Secs 15 & 22

4000 Set post for temporary $\frac{1}{4}$ Sec. cor.

8016 Set post N & S line at corner to Secs

14, 15, 22 & 23 from which corner runs

West on a true line between Secs 15 & 22

4008 Set post for $\frac{1}{4}$ Sec corner in corner of
East with Charney Stake pits & Casper
instructions

8016 The corner to Secs 15, 16, 21 & 22

Level. Soil 1st rate

287

87

Township 3 North Range
North between Secs 15 & 16

chains

ba. 20° E.

25.00 Range bears West

40.00 Set post for $\frac{1}{4}$ Sec corner in corner of East
with charred stake pits & gaspin instructions

80.00 Set Stone 16x12x4 for corner trees

9, 10, 15 & 16

Land gently rolling. Soil 2nd rate

Eastern range line between Secs 10 & 15

40.00 Set post for temporary $\frac{1}{4}$ Sec corner

80.10 Put in set A & S Line at corner trees

10, 11, 14 & 15 from which corner I run

West range line between Secs 10 & 15

40.05 Set post for $\frac{1}{4}$ Sec corner in corner of

East with charred stake pits & gaspin
instructions

80.10 The corner trees 9, 10, 15 & 16

Land gently rolling

Soil 2nd rate

32 East Willamette Meridian
North between Secs 9 & 10

Chains Run 20° E.

4000 Set post for 1/4 Sec. cor. in corner of East
with chain stake pits & as per instructions

8000 Set post for corner to Secs 3, 4, 9 & 10 in
corner of East with chain stake pits &
as per instructions

Land gently rolling Soil good 2000 ft

East on a range line between Secs 3 & 10

4000 Set post for temporary 1/4 Sec. cor.

8000 Interest at N & S Line 28 N & S of
corner to Secs 2, 3, 10 & 11 from which I run

89° 48' N. on a true line between Secs 3 & 10

4000 Set post for 1/4 Sec corner in corner of East
with chain stake pits & as per instructions

8000 1/4 Sec corner to Secs 3, 4, 9 & 10

Land gently rolling
Soil good 2000 ft
very heavy growth of Grass

289

89

Township 3 North Range
Northwestern line between Secs 3 & 4
chains bearing 20° E.

4000 Set post for temporary 1/4 Sec cor.

8060 Intersect North boundary 37 West of
corner to Secs 3 & 4 from which I run
S 0° 16' N on a true line between Secs 3 & 4

4060 Set post for 1/4 Sec cor. in corner
of East with charred stake pits & other
instructions

8060 The corner to Secs 3, 4, 9 & 10

Land gently rolling
Soil good 2nd rate
October 27th 1864

32 East Willamette Meridian

Path between Secs 32 & 33

Chains

4000 Set stone 12x8x6 for 1/4 Sec. cor.

8000 Set post for corner to Secs 28, 29, 32 & 33

in corner of Earth with chains & stake pits

& as per instructions

150

Land rolling. Soil 2nd rate

East on a narrow line between Secs 28 & 33

4000 Set temporary 1/4 Sec. cor.

8014 Intersect N & S Line at corner to Secs

80.14

27, 28, 33 & 34 from which corner I run

Western true line between Secs 28 & 33

4007 Set post for 1/4 Sec corner in corner of

Earth with chains & stake pits & as per instructions

80.14 The corner to Secs 28, 29, 32 & 33

Land gently rolling

Soil good 2nd rate

291

91

Township 3 North Range
North between Secs 28 & 29

Chains

Sec. 20 E

4000 Set post for $\frac{1}{4}$ Sec. cor. in Monna grass
with charred stake pits & casper instructions

8000 Set post for corner to Secs 20, 21, 28 & 29
in Monna of Earth with charred
stake pits & casper instructions

Land gently rolling
Soil good 2000 feet

Eastern ranon line between Secs 21 & 28

4000 Set post for temporary $\frac{1}{4}$ Sec. cor.

80.10 Intersect N & S line at corner to Secs

21, 22, 27 & 28 from which I run

Western true line between Secs 21 & 28

40.05 Set post for $\frac{1}{4}$ Sec corner in Monna of
Earth with charred stake pits & casper
instructions

80.10 The corner to Secs 20, 21, 28 & 29

Lower Quad. Soil 1 $\frac{1}{2}$ feet

32 East Willamette Meridian
North between Secs 20 & 21

chains va. 1934° E.

40.00 Set post for $\frac{1}{4}$ sec corner in Monna of Earth
with charna stake pits & Casper instructions

80.00^{80.00} Set post for corner to Secs 16, 17, 20 & 21 in
Monna of Earth with charna stake pits & Cas
per instructions

Genoa gently rolling
Soil $\frac{1}{2}$ agate

Easton a ranam line between Secs 16 & 21

40.00 Set post for temporary $\frac{1}{4}$ sec cor.

80.20 Intersect N & S Line at corner to Secs
15, 16, 21 & 22 from which corner Penn

Weston a true line between Secs 16 & 21.

40.10 Set post for $\frac{1}{4}$ sec corner in Monna of Earth
with charna stake pits & Casper instructions

80.20 The corner to Secs 16, 17, 20 & 21

80.20^{80.20} Genoa gently rolling

Soil $\frac{1}{2}$ agate

Thin Grazing

193

93

Township 3 North Range
North between Secs 16 & 17

Chains $\mu a. 20^{\circ} E.$

- 40.00 Set post for $\frac{1}{4}$ Sec. com. in ^{Earth} ~~normal~~ with Charred Stake pits & Casper instructions
- 45.50 Ravine bears West
- 80.00 Set post for corner to Secs 8, 9, 16 & 17
in ^{normal} ~~normal~~ of Earth with Charred Stake pits
& Casper instructions
Lower gently rolling Soil 2 ^{or} 3 rate

East on a narrow line between Secs 16 & 9

- 40.00 Set temporary $\frac{1}{4}$ Sec corner
- 80.20 Intersect NW $\frac{1}{4}$ Line at corner to Secs
9, 10, 15 & 16 from which comes ^{Prun}
Mustard tree line between Secs 9 & 16
- 40.10 Set post for $\frac{1}{4}$ Sec corner in ^{normal} ~~normal~~
of Earth with Charred Stake pits
& Casper instructions
- 80.20 The corner to Secs 8, 9, 16 & 17
Lower gently rolling
Soil 2 ^{or} 3 rate

32 East Willamette Meridian
North between Secs 8 & 9

chains $\text{Bearing } 20^{\circ} \text{ E.}$

4000 Set Stone $18 \times 10 \times 6$ for $\frac{1}{4}$ Sec. cor.

8000 Set post for corner to Secs 4, 5, 8 & 9 in *Monument*
of Earth with Charred Stake pits & Casper
instructions

Ground gently rolling

Soil 2nd rate

East on a random line between Secs 4 & 9

4000 Set post for temporary $\frac{1}{4}$ Sec. cor.

79.80 Intersect N & S Line at corner to Secs

79.80 3, 4, 9 & 10 from which corner *Prin*

Mustena true line between Secs 4 & 9

39.90 Set post for $\frac{1}{4}$ Sec. cor. in *Monument* of Earth
with Charred Stake pits & Casper instructions

79.80
79.80 The corner to Secs 4, 5, 8 & 9

Ground gently rolling

Soil good 2nd rate

295

95-

Township 3 North Range

North on a bearing line between Secs 485-
chains Pa. $19\frac{1}{2}^{\circ}$ E.

4000 Set post for temporary $\frac{1}{4}$ sec. cor.

80.68 Intersect north boundary at corner
to sec 485 from which corner from

South on a true line between Secs 485-

40.68 Set post for $\frac{1}{4}$ sec corner in mound of earth
with charred stake pits & as per instructions

80.68 The corner to sec 485; 889

Land gently rolling

Soil good $2\frac{1}{4}$ rate

North between Secs 31832

.10 Old Emigrant Road bears N 78° SE

4000 Set post for $\frac{1}{4}$ sec corner in mound
of earth with charred stake pits & as per
instructions

8000 Set post for corner to sec 2930. 31832

in mound of earth with charred stake
pits & as per instructions

Land Level

Soil $2\frac{1}{4}$ rate

October 28th 1864

32 East Willamette Meridian

Eastern a permanent line between Secs 29 & 32
Cherins

4000 Set temporary $\frac{1}{4}$ Sec corner

8000 Intersect N & S Line 35th N. S. of corner

to Secs 28, 29, 32 & 33 from which I run

S 89^o 45' W. on a true line between Secs 29 & 32

4000 Set post for $\frac{1}{4}$ Sec corner in corner

of earth with charred stake pits & as per instructions

8000 The corner to Secs 29, 30, 31 & 32

General Level. Soil ~~2~~ rate

Western a permanent line between Secs 30 & 31

4000 Set post for temporary $\frac{1}{4}$ Sec cor.

8600 Intersect West boundary at corner to Secs

30 & 31 from which corner I run

East on a true line between Secs 30 & 31

4600 Set post for $\frac{1}{4}$ Sec. cor. in corner of earth

with charred stake pits & as per instructions

8600 The corner to Secs 29, 30, 31 & 32

General Level

Soil ~~2~~ rate

297

99

Township 3 North Range
North between Secs 29 & 30

chains per 20th E.

4000 Set post for $\frac{1}{4}$ sec corner in ³⁰monument
with chain stake pits & as per instructions

8000 Set post for corner to sec 19, 20, 29 & 30
in ³⁰monument of Earth with chain stake
pits & as per instructions

Level & polling. Soil sample rate

East on a range line between Secs 20 & 29

4000 Set post for temporary $\frac{1}{4}$ sec cor.

8040 Cut a set of 2 1/2" line 30 M. S. at the corner
to sec 20, 21, 28 & 29 from which run

S 89° 47' W. on a true line between Secs 20 & 29

4020 Set stone 15x12x10 for $\frac{1}{4}$ sec. cor.

8040 The corner to sec 19, 20, 29 & 30

Level

Soil sample rate

32 East Willamette Meridian -

West on a remnant line between Secs 19830

4000 Set post for temporary $\frac{1}{4}$ Sec. cor.

85:30 Intersect West boundary 35th N. South of corner to Secs 19830 from which I run

S 89° 45' E on a true line between Secs 19830

45:30 Set post for $\frac{1}{4}$ Sec corner in Monong East with charred stake pits & copper instructions

85:30 The corner to Secs 1920, 29830
 Same Level. Soil 2nd rate.

North between Secs 19820

Cor. 20° E.

4000 Set post for $\frac{1}{4}$ Sec corner in Monong East with charred stake pits & copper instructions

8000 Set post for corner to Secs 1918, 19820 in Monong East with charred stake pits & copper instructions
 Same Level. Soil 2nd rate

Township 3 North Range
 East on a range line between Secs 17 & 20
 corners
 4000 Set post for temporary $\frac{1}{4}$ Sec corner
 8066 Intersect N & S Line 13 Ms South of
 corner to Secs 16, 17, 20 & 21 from which I run
 S 89° 34' W. on a true line between Secs 17 & 20
 4033 Set post for $\frac{1}{4}$ Sec corner in Monong East
 with charred stake pits & copper instructions
 8066 The corner to Secs 17, 18, 19 & 20
 Level Level. Soil Long note

West on a range line between Secs 18 & 19
 4000 Set temporary $\frac{1}{4}$ Sec cor.
 8456 Intersect West homerang 60 Ms South
 of corner to Secs 18 & 19 from which I run
 S 89° 34' E. on a true line between Secs 18 & 19
 4456 Set post for $\frac{1}{4}$ Sec corner in Monong East
 with charred stake pits & copper
 instructions
 8456 The corner to Secs 17, 18, 19 & 20
 Level Level. Soil Long note

32 East Willamette Meridian
North between Secs 17 & 18

chains N. 20° E.

4000 Set post for 1/4 sec corner in corner of East
with Charra Stake pits & as per instructions

6080 Nearing bears West

8000 Set post for corner to Secs 7, 8, 17 & 18 in
corner of East with Charra Stake pits
& as per instructions

Ground gently rolling
Soil 2 ^{1/2} ~~1/2~~ rate

East on a random line between Secs 8 & 17

4000 Set post for temporary 1/4 sec. cor.

8030 Intersect at N & S Line at Corner to Secs
8, 9, 16 & 17 from which corner I run
rest on true line between Secs 8 & 17

4016 Set post for 1/4 Sec corner in corner
of East with Charra Stake pits
& as per instructions

8030 The corner to Secs 7, 8, 17 & 18

Ground rolling

Soil 2 ^{1/2} ~~1/2~~ rate

October 29th 1864

Township 3 North Range

West on a permanent line between Secs 7 & 8
chains

- 40.00 Set post for temporary $\frac{1}{4}$ sec. cor.
 84.00 Intersect West boundary 67 Ms
 South of corner to sec 7 & 8 from which I run
 S 89° 31' E. on a true line between Secs 7 & 8
 14.00 Range bears N W
 44.00 Set stone 15 x 12 x 5 for $\frac{1}{4}$ sec cor.
 84.00 The corner to sec 7, 8, 17 & 18
 Same rolling. Soil 2 on $\frac{1}{4}$ sec

✓ North between Secs 7 & 8
 bearing 20° E.

- 40.00 Set post for $\frac{1}{4}$ sec cor. in corner of East
 with corner stake pit & as per instructions
 80.00 Set post for corner to sec 5, 6, 7 & 8 in
 corner of East with corner stake
 pit & as per instructions
 Same rolling
 Soil 2 on $\frac{1}{4}$ sec

32 East Willamette Meridian

East on a run or line between Secs 5 & 8
 4000 Set post for temporary $\frac{1}{4}$ Sec corner

8020 Intersect $\frac{1}{4}$ Sec Line at corner Secs
 4, 5, 8 & 9 from which corner Run

West on a true line between Secs 5 & 8

4010 Set post for $\frac{1}{4}$ Sec corner in normal
 Earth with Charrier Stake pits & as per
 instructions

8020 The corner trees 5, 6, 7 & 8

Same rolling. Soil 2nd rate

West on a run or line between Secs 6 & 7

4000 Set post for temporary $\frac{1}{4}$ Sec corner

8370 Intersect West boundary 6000 South
 of corner trees 6 & 7 from which corner Run

889.34' E. on a true line between Secs 6 & 7

4370 Set post for $\frac{1}{4}$ Sec. cor. in normal Earth
 with Charrier Stake pits & as per instructions

8370 The corner trees 5, 6, 7 & 8

Same rolling

Soil 2nd rate

303

103

Township 3 North Range
North on a meridian line between Secs 5 & 6
ba. 20° E.

4000 Set post for temporary $\frac{1}{4}$ Sec corner
8070 Intersect North boundary at corner
to Secs 5 & 6 from which corner Run
South on a true line between Secs 5 & 6

4075 Set post for $\frac{1}{4}$ Sec corner in Monong
Earth with charred stake pits & as per
instructions

8075 The corner to Secs 5, 6, 7 & 8
Corner rolling Soil $\frac{1}{4}$ or $\frac{2}{11}$ water

32 East Willamette Meridian

General Description

The Land in this Township is generally either Level or gently rolling and covered with a heavy growth of Grass. There is but a very Spring and no streams of water, and not a tree in the Township.

This is the best Township for Grass in this section of country.

Stok

List of Names

A List of the names of the men and
 employed to assist in running measuring
 and marking the lines and corners
 described in the foregoing field notes of
 the Survey of Township No 3 North of the
 base line of Range No 32 East of the
 Willamette Meridian Showing the respective
 capacities in which they acted

David P Thompson Comptroller

J. S. Dotson Chainman

Rev. W. Newman "

A. McLean Assessor

We hereby certify that we assisted 306

Daniel Chaplin, deputy Surveyor in
Subdividing Township N.° 3 north of the
base line of Range N.° 32 East of the
Willamette Meridian and that said
Township has been in all respects
well and faithfully surveyed and the
boundary monuments planted
according to the instructions furnished
by the Surveyor General

Daniel P. Thompson Comptroller

J. S. Gutzon Chairman

W. Newman

"

A. McLean Assessor

Sworn and subscribed before me
this 8th day of November 1864

J. P. Phillilanes

Justice of the Peace

I Daniel Chaplin Deputy
Surveyor do solemnly Swear
that in pursuance of a
Contract with B. J. Pengra
Surveyor of the Public Lands
of the United States in Oregon
bearing date the 21st day of
September 1864 I have well
faithfully and truly and in
my own proper person and
in strict conformity with
the instructions furnished
by the said Surveyor General
the Surveying Manual and
the Laws of the United States
Surveyed all those parts or
portions of Township No. 3
North Range No. 2 East of the
Willamett Meridian as are
represented in the following

field notes as having
309 been surveyed under my
directions and I do farther
voluntarily swear that all of
the corners of said surveys
have been established and
perpetuated in strict accord
-ance with the surveying
-manuel and printed instruc-
-tions and that the forego-
-ing are the true and origin-
-al field notes of such sur-
-vey-

Daniel Chaplin Deputy Surveyor

Sworn and subscribed to before
me this 1st day of December 1861

H. I. Reinhardt
Justice of the Peace
in Union Co. Oregon

Surveyor General's Office
Eugene City. Jan. 11th 1865

The foregoing field notes of the surveys of subdivision
lines in T. 3 N. R. 32 E. Will. Mer. Ore,
executed by Daniel Chaplin, Deputy Sur-
veyor, under his contract No. 107 dated
Sept. 21st 1864, having been critically
examined, the necessary corrections and
explanations made, the said field note
and the surveys they describe are hereby
approved.

J. J. Pengra
Sur. Gen. of Ore.