

of the Willamette

Meridian.

Field Notes of West. Boundary of
Twp. 3 North Range 35, East

North on West side of Sec. 31.

40.00 Set post and made mound
of Earth for $\frac{1}{4}$ Sec. cor.

80.00 Set post and made mound
of Earth for cor. to Secs. 30, 31,
25 + 36.

Land rolling. Soil good 2d rate.

North on West boundary of
Sec. 30.

N. 21° E.

40.00 Set post and made mound of
Earth for $\frac{1}{4}$ Sec. cor.

80.00 Set post and made Earth mound
for cor. to Secs. 19, 30, 24, 25.

Land nearly level. Soil good.
Good quality of Grass.

8

Township 3 North Range 35 East

chs. North on West boundary of
Sec. 19.

N. 20° 30' E.

40.00 Setpost and made mound
of Earth for '4 Sec. corner.

78.00 Old wagon road very fine.

50.00 Setpost and made mound
of Earth for cor. to Secs.

18, 19, 13 + 24

Land rolling; Soil 1st rate, Good grass

North on West bdy. of Sec. 18.

N. 21° E.

20.00 Branch, 3 chs. flows N.W.

40.00 Setpost and made mound of Earth
for '4 Sec. cor.

46.000 Road, N.E. + S.W.

80.00 Setpost and Earth mound
for cor. to Secs. 12, 13, 7 + 18.
Land level Soil 1st rate

of the Willamette

Meridian.

11

9

Ch North on West boundary of Sec. 7
N. 20° 30' E.

4000 Set post and made mound of Earth
for $\frac{1}{4}$ Sec. corner.

61.54 Spring Branch, 4 lbs flows. N. W.

8000 Set post and made mound of Earth
for cor. to sections 6, 7, 11 & 12.
Land level prairie. Soil 1st rate,
Good grass.

North on West boundary of Sec. 6

Var. 21° E.

4000 Set Post and made mound of Earth for
 $\frac{1}{4}$ Sec. corner.

78.00 Wagon Road. N E + S W.

8000 Set post and made mound
of Earth for cor. to Tps. 3 & 4
North, Ranges 34 & 35 East.
Land level Soil 1st rate,
Good grass.

24
Township

Range

U. S. Surveyor General's Office
Oregon City June 21st 1872

The foregoing field notes of the survey of Ex-
terin lines of T 3 N. R 35 E ~~#~~ and
T 21 N. Ranges 34th and 35 East Will
Mer and the subdivisinal lines
of T 4 N Rqs 34th and 35 E Will
Mer Oregon executed by J. B.
Moody deputy Surveyor under con-
tract No 164 bearing date Oct
24th 1871 having been critically
examined the necessary cor-
rections and explanations
made the said field notes and
the surveys they describe are
herby approved

W. H. Bell
Sur Gen

" I, Genas F. Moody, having been appointed a deputy Surveyor of the lands of the United States in Oregon, do solemnly swear that I will well and faithfully, and to the best of my skill and ability execute the duties confided to me pursuant to a contract with W. H. Odell, Surveyor General of public lands in Oregon, bearing date the 4th day of October 1871, according to the laws of the United States and the instructions received from the said Surveyor General.

G. F. Moody

Sworn and Subscribed before me
this 14th day of October 1871
W. Davenport
U.S. Comm^r Dist of Oregon

J. J. Kent, do solemnly swear that I will faithfully execute the duties of chain carrier; that I will level the chain upon uneven ground, and plumb the tally pins, whether by striking or dropping the same; that I will report the true distances to all notable objects, and the true length of all lines that I assist in measuring, to the best of my skill and ability.

J. J. Kent

Sworn and Subscribed before me
 This 14th day of October 1871
 W. Davenport
 U.S. Commr. Dist. of Oregon.

J. O. Hathaway do solemnly
swear that I will well and truly
perform the duties of Axeman
according to the instructions given
me, and to the best of my skill and
ability

O Hathaway

Sworn and Subscribed before me
This 14th day of October 1871
M. Davenport
U.S. Commr. Dist. of Oregon.

I, Geo. W. Renne, do
 solemnly swear that I will faithfully
 execute the duties of chain carrier; that
 I will level the chain upon uneven
 ground, and plumb the tally pins,
 whether by striking or dropping the
 same; that I will report the true
 distances to all notable objects, and
 the true length of lines that I assist
 in measuring, to the best of my skill
 and ability.

G. W. Renne

Sworn and Subscribed before me
 this 14th day of October 1871
 W. Davenport
 U.S. Comm. Dist. of Oregon

I Edward Gariopy, do solemnly swear that I will well and truly perform the duties of Axeman, according to the instructions given me, and to the best of my skill and ability.

Edward Gariopy

Sworn & Subscribed before me
 This 14th day of October 1871
 W. Davenport
 U.S. Commr. Dist. of Oregon.