

Between R.s. 33 & 34. E. T 2 N.

90

chs.

North on East Boundary of Sec. 12.  
Variation 21° East.

8.00

8.00

23.50

28.50

40.00

40.00

80.00

8.00

Wagon road, course E & W.

Umatilla river, course W.

Set Stone 16 + 14 + 8 for 14 S. cor.

Set post and made mound of Earth  
for Connection Secs 1, 12, 6 & 7.

Land level, Soil 1<sup>st</sup> rate

North on East Boundary of Sec. 1.

Variation 21°

40.00

40.00

80.00

8.00

Set post and made stone mound  
for 1/4 Sec. corner

Set post and made mound of  
Earth for corner Tps 2 & 3 North  
Ranges 33 & 34. East.

Land rolling. Soil 1<sup>st</sup> rate

Good grass

May, 19, 1871

cho North on East boundary of Sec. 12.  
Var. 20° East.

4000 Set Stone 14 + 14 + 8 for  $\frac{1}{4}$  Sec. corner

43.75 Wagon road, course N.E. + S.W.

8000 Set Stone 18 + 16 + 8 for corner to  
Sections, 1, 12, 6 + 7.

Land Kelly. Soil good 2<sup>d</sup> rate  
Good grass.

North on East boundary of Sec 1,  
Var. 21° East.

20.50 Foot of Bluff 200

27.50 Womahilla River, 150 thro flows  
West.

4000 Set post and made stone mound  
for  $\frac{1}{4}$  Sec. cor.

63.25 Leave river bottom

8000 Set post and made stone mound  
for cor. to Tps. 2 + 3. N. R. 34 + 35 East.

Timber in river bottom. Soil  
1<sup>st</sup> rate. good grass.

North boundary T2 N. R 34 E. Hill <sup>mer</sup>

hs. <sup>120</sup>  
Met on a random line on the  
North boundaries of sections 1, 2, 3, 4, 5 & 6

omit <sup>is given</sup> Var.  $19^{\circ}30'$  East. ~~this variation~~

I set temporary half mile and mile  
posts at every 40 and 80 chains  
and 6 miles 40 links to a point  
2 chains and 54 links N. of the  
corner to Townships 2 + 3 North  
Ranges 33 + 34. East.

North  $89^{\circ}42'$  East on true line  
on north boundary of Sec. 6.

Var.  $18^{\circ}30'$  E.

40.40  
4 1/2  
Set post and made earth mound  
for '4 Sec. cor.

80.40  
8 1/2  
Set post and made earth mound  
for corner to Secs 5, 6, 31, 32.

Land rolling. Soil 1<sup>st</sup> rate  
Excellent quality of grass.

May 31<sup>st</sup> 1871.

121 North boundary of Twp. 2 N. R. 34. East

chs North  $89^{\circ}42'$  East on true line  
on north boundary of Sec. 5,  
Var.  $18^{\circ}30'$  East.

4000 Set post and made Earth mound  
for  $\frac{1}{4}$  Sec. corner.

8000 Set post and made mound of  
Earth for corner to Secs 4, 5, 32, 33.  
Land rolling. Soil 1<sup>st</sup> rate.  
Good grass.

North  $89^{\circ}42'$  East on true line  
on North boundary of Sec. 4.  
Var  $19^{\circ}$  East.

35,000 Old Major Road  
Course: N. E.  $4^{\circ}$  S. W.

4000 Set post and raised Earth mound  
for  $\frac{1}{4}$  Sec. corner

8000 Set post and made Earth mound  
for corner to Secs 3, 4, 33 & 34.

Land rolling. Soil 1<sup>st</sup>  
rate. Good grass.

North Boundary, T2 N. R 34 East.

122

N 89° 42' East on true line on the  
north boundary of Sec. 3.

Var. 18° 30' E.

35.00

35.50

Walla Walla and Cayuse  
Stage Road, Course N.E. & S.W.

40.00

Set post and made earth mound for 1/4

Section corner

80.00

Set post and Earth mound for corners to Secs

2, 3, 34 + 35,

Land rolling. Soil 1<sup>st</sup> rate. Good grass.

North 89° 42' East on true line on  
north boundary of Sec. 2.

Var. 19° East.

40.00

40.00

Set post and made Earth mound for 1/4 Sec. corner

80.00

80.00

Set post and made Earth mound for corners to Secs

1, 2, 35 + 36

Land rolling. Soil 1<sup>st</sup> rate. Good grass

122  
els North Boundary T2 N.R. 34 E. Will. Mer.  
N 89° 42' East on true line on the  
North Boundary of Sec. 1.  
Var. 1915' East.

4,000 Set post and made Earth mound  
for 1/4 Section corner

8,000 Tolona for Tps. 2+3, NRs 34+35  
East, Willamette meridian to  
\* Sand rolling, Soil 1<sup>st</sup> rate  
Good grass.

June 1<sup>st</sup> 1871.

1244

Surveyor General's Office  
Eugene City Nov 11<sup>th</sup> 1871

The foregoing field notes of the Survey  
of the Exterior lines of T 1 N R 30  
33, 34 & 35 East, and T 2 N R 30 & 34  
E Will Mer Oregon executed by  
G. F. Moody deputy under his  
contract bearing date the 23<sup>rd</sup> day  
of April 1871 having been critic-  
ally examined the necessary  
explanations and corrections  
the said field notes and the Sur-  
veys the describe are hereby  
approved

W. H. Bell  
Sur Gen<sup>l</sup>

I Genas F. Moody, having  
 been appointed Deputy Surveyor, of the  
 lands of the United States in Oregon,  
 do solemnly swear that I will well  
 and faithfully, and to the best of my  
 skill and ability, execute the duties  
 confided to me, pursuant to a con-  
 tract with W. H. Odell, Surveyor  
 General, of the public lands in Oregon,  
 bearing date 23 day of April 1871,  
 according to the laws of the United  
 States and the instructions received  
 from the said Surveyor General.

J. G. Moody

Sworn and Subscribed before me  
 This 29th day of April 1871  
 W. Davenport  
 Coroner of the U.S. Circuit Court  
 for the District of Oregon



I, M. A. Moody, do solemnly swear that I will faithfully execute the duties of chain carrier; that I will level the pins upon uneven ground, and plumb the lally pins, whether by sticking or dropping the same; that I will report the true distance to all notable objects, and the true length of all lines that I assist in measuring, to the best of my skill and ability.

M. A. Moody

Sworn and Subscribed before me }  
 this 29th day of April 1871 }  
 W. Davenport }  
 Commissioner of the U.S. Circuit Court }  
 for the District of Oregon }

A. E. G. Condon, do solemnly swear  
that I will well and truly perform the  
duties of a seaman, according to  
instructions given me, and to the  
best of my skill and ability.

E. G. Condon

Sworn and Subscribed before me  
This 29<sup>th</sup> day of April 1871  
M. Davenport  
Clerk of the U.S. Circuit Court  
for the District of Oregon

J. E. Henderson do solemnly <sup>298</sup>  
swear that I will faithfully execute  
the duties of chain carrier; that I  
will level the chain upon uneven  
ground, and plumb the lally  
pins, whether by striking or dropping  
the same; that I will report the  
true distance to all notable  
objects, and the true length of all  
lines that I assist in measuring,  
to the best of my skill and  
ability.

C. H. Henderson

Sworn and Subscribed before me  
this 29th day of April 1871  
M. Davenport  
Clerk of the U.S. Circuit Court  
for the District of Oregon