

150

Township 3 North

Range 34 East

Township 3 N R. 34 E

6	5	4	19	3	13	2	7	1		
7	8	23	9	18	10	12	11	6	12	
18	30	17	22	16	17	15	11	11	5	13
19	29	20	21	21	16	22	10	23	4	24
30	27	29	20	28	15	27	9	26	3	25
31	26	32	19	33	14	34	8	35	2	36

Chas Field notes of the Survey of the
Subdivisional Lines of Township
No 3 North of Range No 34
East of the Will. Mer. by T. F.
Moody, under Contract No.
164, bearing date Oct. 4th
1871.

North bet. Secs. 35 & 36.

4000 Set post and made Earth mound
for 1/4 S. cor.

8000 Set post and made mound of
Earth for cor. to Secs. 35, 36

25. + 26

Land. generally rolling.

Soil good. First rate

Grass.

Township 3 North

Range 34 East

chs East on random bet. Secs. 25 & 26.
V. 20° E.

4000 Set temporary 1/4 Sec. corner.

8014 Intersected N. & S. line 22 lks S of cor.

S. 89° 51' W. on true line

4007 Set stone 14 + 12 + 7 for 1/4 S. cor

8014 To corner

Land generally rolling. Soil good
Good Grass.

North bet. Secs. 25 & 26

4000 Set post and made Earth mound
for 1/4 Sec. corner.

8000 Set post and made Earth
mound for cor. to Secs.

25, 26, 23 & 24

Land rolling. Soil good.
Good Grass.

of the Millamette

Meridian.

chs. East on random bet. Secs. 24 + 25
S. 21° E.

40.00
40.00
79.90
Set temporary 1/4 Sec. cor.
Intersected N+S. line at cor.

39.95
39.95
79.90
N. on true line
Set Stone 14 + 12 + 5 for 1/4 S cor.
To corner.

Land rolling, Soil good.
Good Grass.

North bet. Secs. 23 + 24

13.00
13.00
40.00
40.00
80.00
Cayuse + Macea Road N E
Post and Earth mound for
1/4 S. cor.

80.00
Set post and made Earth
mound for cor. to Secs.

23. 24. 13 + 14

Land level. Soil 1st rate,
Good Grass

Township 3 North Range 34 East

chs East on random bet. Secs. 13 & 24
 V. $20^{\circ}30'$ E.

4000 Set temporary $\frac{1}{4}$ Sec. cor.

8000 Intersected N+O. line 14th
 S. of cor.

S. $59^{\circ}54'$ N. on true line

4000 Set post and made Earth
 mound for $\frac{1}{4}$ Sec. cor.

8000 To corner.

Land level. Soil good

North bet. Secs. 13 & 14

4000 Set post and made Earth
 mound for $\frac{1}{4}$ Sec. cor.

8000 Set post and made mound
 of Earth for. cor. to Secs.
 13. 14. 11 & 12

Land level. Soil good
 Good grass

of the Willamette Meridian. 335
b.

Chs East on random bet. Secs. 12 & 13
N. 21° E.

40.00 ^{40.00} Set temporary 1/4 Sec. corner.

79.86 ^{79.86} Intersected N & S line 14 hrs. S of
S. 89° 34' N. on true line

39.93 ^{39.93} Set post and made Earth mound
for 1/4 Sec. corner.

79.86 ^{79.86} To corner

Land rolling. Soil good. Good Grass.

North bet. Secs. 11 & 12.

40.00 ^{40.00} Set post and made Earth mound
for 1/4 Sec. cor.

43.50 ^{43.50} Dry Branch runs N.

80.00 ^{80.00} Set post and made Earth
mound for cor. to Secs. 11, 12
1 & 2

Land rolling. Soil Good
Good Grass.

2
380
Township 3 North

Range 34 East

chs East on random bet. Secs. 1 & 12.

N. $20^{\circ}30'$ E.

4000 Set temporary $\frac{1}{4}$ Sec. corner.

8018 Intersected N.W.S. line 21 lks N of cor.

N $89^{\circ}37'$ W. on true line

4009 Set post and made mound of
Earth for $\frac{1}{4}$ S. cor.

8018 To Cor.

Land rolling. Soil good.

North on random bet Secs. 1 & 2

4000 Set temporary $\frac{1}{4}$ Sec. cor.

8030 Intersected North boundary
17 lks E of cor.

S $00^{\circ}4'$ E. on true line

4030 Set post and made Earth
mound for $\frac{1}{4}$ Sec cor.

8030 To cor.

Land rolling. Soil good
Oct. 26, 1871.

of the Willamette Meridian. 337

Chs. North bet. Secs. 34 & 35
4000 ^{40.00} Set post and made Earth mound for $\frac{1}{4}$ Sec. corner.
8000 ^{80.00} Set post and made mound of Earth for cor. to Secs. 34, 35-26, 27.
Land rolling Soil Good.
Good Grass.

East on random bet Secs. 26 & 35
N. $20^{\circ}30'$ E

4000 ^{40.00} Set Temporary $\frac{1}{4}$ Sec. cor.
8014 ^{80.14} Intersected N+S line 12ths S of cor.
S. $89^{\circ}33'$ W. on true line
4007 ^{40.07} Set post and made Earth mound for $\frac{1}{4}$ Sec. cor.
8014 ^{80.14} To Corner.
Land rolling Soil Good
Good Grass.

9

Township 3 North

Range 34 East

4000 North bet. Secs. 26 + 27

Set post and made mound of earth for 1/4 sec. cor.

4700 Wagon Road NE + SW

8000 Set post and made mound of earth for cor. to Secs. 26, 27, 22, 23

Land rolling, Soil good
Good grass

East on road bet. Secs. 23 + 24
N. 20° East.

4000 Set temporary 1/4 Sec. cor.

8016 Intersected N + S. line 14th S of cor.
S. 89° 54' W. on true line

4048 Set post and made mound of earth for 1/4 sec cor.

4900 Road NE

8016 To corner

Land rolling, Soil good

of the Willamette Meridian.

4000 ^{40.00} North lat. Secs. 22 + 23.
 8000 ^{80.00} Set post and Earth Mound for $\frac{1}{4}$ Sec. cor.
 Set post and Made Mound of Earth for cor.
 to Secs. 22, 23, 14 + 15
 Land rolling Soil $\frac{1}{11}$ rate, Good Grass.

East on random lat. Secs. 14 + 23.
N. 21° E.

4000 ^{40.00} Set temporary $\frac{1}{4}$ Sec. corner.
 79.88 ^{79.88} Intersected N. + S. line 21 lbs N of corner
 N. 89° 37' N. on true line
 39.94 ^{39.94} Set Post and Made Earth mound for
 $\frac{1}{4}$ Sec. corner.
 79.88 ^{79.88} To corner
 Land rolling Soil $\frac{1}{11}$ rate
 Good Grass.

W 340
Township

3 North

Range 34 East

Chs North bet. Secs. 14 & 15

4000 Set post and made mound
of Earth for $\frac{1}{4}$ Sec. cor.

8000 Set post and made Earth
Mound for cor. to Secs
14, 15, 10 & 11.

Land rolling Soil 1st rate,
Good Grass.

East on random bet. Secs. 11 & 14

$V. 20^{\circ} 30' E.$

4000 Set temporary $\frac{1}{4}$ S. cor.

1984 Intersected N. & S. line 14th
S. of cor.

S. $89^{\circ} 54' N$ on true line

3992 Set Post and made Earth
Mound for $\frac{1}{4}$ Sec cor.

1984 Take corner.

Land rolling, Good Soil

of the Millamette Meridian.

4000 ^{40.00} lbs North wt. Secs, 10 & 11.
 Set post and made Mound of Earth
 for 1/4 Sec. corner.
 8000 ^{80.00} Set post and made Earth
 Mound for cork Secs. 10, 11.
 2 & 3.
 Land rolling Soil Good.

East on random bet. Sect. 2 & 11
 T. 20° E.

4000 ^{40.00} Set temporary 1/4 S. cor.
 8017 ^{80.17} Intersected N. & S. line 12 lbs N of cor.
 N 89° 55' W. on true line
 4008 ^{40.08} Set post and made Earth Mound
 for 1/4 Sec. cor.
 8017 ^{80.17} To corner.
 Land rolling Soil Good.
 Good Grass.

13. 342

Township 3 North Range 34 East

Ch North on random bet. Secs. 24 & 3
N 20° E

400 Set temporary 1/4 Sec. cor
8027 intersected North boundary 18th
E of cor.

S 00° E on true line

4027 Set Post and made mound
of earth for 1/4 Sec. cor.

4410 Spring Branch flows N.E.
8027 To corner

Land rolling Good grass
1st rate Soil.

Oct. 27, 1871

14
213

of the Willamette Meridian.

Chs North lat. Secs. 33 + 34
40.00
40.00 Set post and made mound of Earth
for $\frac{1}{4}$ Sec. cor.
80.00
80.00 Set post and made mound of
Earth for cor. to Secs. 33, 34
27, 28.
Land rolling, Soil 1st rate.

East on random lat. Secs. 27 + 34
V. 20° E

40.00
40.00 Set temporary $\frac{1}{4}$ S. cor.
80.12
80.12 Intersected N + S. line 14 lbs S of cor.
S. 89° 54' N. on true line
24.00
24.00 Road N E S W
40.06
40.06 Set post and made Earth
mound for $\frac{1}{4}$ S cor.
80.12
80.12 To corner
Land. Generally level
Soil 1st rate.
Good Grass

Township 3 North Range 34 East

Chd North bet. Secs. 27 + 28.
 4000 Set post and made mound
 of Earth for $\frac{1}{4}$ Sec. corner.
 8000 Set post and made Earth
 mound for cor. to Secs
 27, 28, 21, 22.
 Land rolling, Soil good
 Good Grass.

East on random bet. Secs (22 + 20)
 U, 20° E.

4000 Set temporary $\frac{1}{4}$ S. cor
 8010 Intersected N + S. line 24 lks
 N of cor.
 N $89^{\circ} 30'$ W. on true line
 4005 Set post and made mound
 of Earth for $\frac{1}{4}$ S. cor.
 8010 To corner.
 Land level. Good Soil.

Of the Willamette Meridian. 345 ¹⁶

Chs North bet. Secs. 21 + 22.
4000 ^{40.00} Set post and made Earth
Mound for 1/4 Sec. cor.
8000 ^{80.00} Set post and made Earth
Mound for cor. to Secs. 21, 22,
15 + 16.
Land level. Soil good.

East on random bet. Secs. 15 + 22
N. 21° E.

4000 ^{40.00} Set temporary 1/4 Sec cor.
8000 ^{80.00} Intersected N. + S. line 1/4 Sec cor
S 89° 54' N. on true line
4000 ^{40.00} Set post and made Earth
Mound for 1/4 Sec cor.
8000 ^{80.10} Pole corner
Land level. Soil Good.
Good Grass.

17
346
Township

3 North

Range 34 East

lehs North bet. Secs. 15 & 16

4000 Set Post and made Earth
Mound for 1/4 Sec cor.

8000 Set post and made Earth Mound
for Cor. to Secs. 15, 16, 9 & 10
Land level, Soil Good.

East on random bet. Secs. 10 & 15
T. 20° 30' E

4000 Set Temporary 1/4 Sec. cor.

7992 Intersected N & S. line above,
Now true line

3996 Set post and made Earth
mound for 1/4 Sec cor.

7992 Take over

Land level, Soil good

of the Willamette Meridian.

4000 ^{40.00} Work bet. Secs 9 & 10.
 Set post and made Earth
 mound for 1/4 Sec cor.
 8000 ^{80.00} Set post and made Earth
 mound for cor to Secs. 9, 10
 3 & 4.
 Land some rolling. Soil good.

East on random bet. Secs 3 & 10.
 V. 21° E

4000 ^{40.00} Set temporary 1/4 Sec cor
 7964 ^{79.64} Intersected N & S line 14 lbs
 W of cor.

3982 ^{39.82} N 89° 54' W on true line
 Set Post and made Earth
 mound for 1/4 Sec cor.
 7964 ^{79.64} To cor.
 Land rolling Good soil

19

Township 3 North Range 34 East

chs. North bet. Secs. 3 & 4
 39.24 To Wild Horse ck.
 The Boundary of the Reservation.

18.40 North bet. Secs. 4 & 9
 To Wild Horse ck. The
 Boundary of the Sub-
 Reservation.

4000 North bet. Secs. 32 & 33
 Set post and made Cont.
 Mound for 1/4 Sec. cor.
 8000 Set post and made Cont.
 Mound for cor. to Secs
 32, 33 28 & 29
 Land rolling. Soil good

of the Millamette Meridian. 319²⁰

Chs East on road about Secs. 28 + 33

V. 20° E

40.00^{40.00} Set temporary 1/4 Sec. cor.
80.40^{80.40} Intersected N+S line 14th N of cor.

40.20^{40.20} N 89° 54' N. on true line
Set post and made Earth mound for
1/4 Sec. cor.

80.40^{80.40} To Corner

Land rolling, Soil Good,

North bet. Secs. 28 + 29

40.00^{40.00} Set post and made Earth mound
for 1/4 Sec. cor.

80.00^{80.00} Set post and made mound of
Earth for cor. to Secs. 28. 29

20. 21

Land rolling, Soil Good
Good Grass

21

350

Township 3 North

Range 34 East

Chs Easton prairie bet. Secs. 21 & 28
N. 21° E.

4000 Set temporary 1/4 Sec. cor.

8000 Intersected N+S line 100 ft
N of cor.

N 89° 32' W. on true line

4000 Set post and made mound of
Earth for 1/4 Sec. cor.

8000 Pole on

Land rolling. Soil good

North bet. Secs 21 & 20

4000 Set post and made Earth
mound for 1/4 Sec. cor.

8000 Set post and made
mound of Earth for cor.
to Secs. 21, 20, 16 & 17

Land rolling. Soil good
Oct. 28, 1871

of the Willamette

Meridian.

22

Chs. East on railroad bet. Secs 16 + 21
N. $20^{\circ}30' E$.

40.00 Set temporary $\frac{1}{4}$ Sec. cor.

80.20 Intersected N+S. line 16 lks S of cor.
 $S^{\circ}89^{\circ}53' N$. on true line

40.10 Set post and made mound of
Earth for $\frac{1}{4}$ Sec. cor.

80.20 To Corner.

Land rolling. Soil Good
Good Grass.

North bet. Secs 16 + 17

40.00 Set post and made Earth
mound for $\frac{1}{4}$ S. cor.

44.50 Old Wagon Road. sim.

80.00 Set post and made Earth
mound for cor to Secs

16, 17, 8 + 9

Land rolling. Good Grass

23

Township 3 North Range 34 East

600 East on prairie bet. Secs. 9 & 16
N. 21° 30' E

400 Set temporary 1/4 Sec. corner.

800 Intersected N. & S. line 1200
N of corner

N 59° 35' W. on true line

400 Set post and made mound
of earth for 1/4 Sec. cor.

800 To corner

Land rolling. Soil Good

North bet. Secs. 8 & 9

19.75 To Wild Horse cr. the
Boundary of the Reservation

West bet. Secs 8 & 17

N. 21° 45' E.

25.20 To Wild Horse cr. the
Reservation Boundary.

ch
Field notes of the West boundary
of T. 3 N. R. 34 E.

North on East Boundary

of Sec. 31

4000 ^{40.00}
Set post and made Earth
Mound for 1/4 Sec.

8000 ^{80.00}
Set post and made mound
of Earth for cor. to Secs.
30, 31, 25 + 31.

Land level. Soil Good.

North on West boundary of Sec. 30
T. 2 N. R. 30 E.

4000 ^{40.00}
Set post and made Earth mound
for 1/4 Sec. cor.

8000 ^{80.00}
Set post and made mound
of Earth for cor to Secs.

19, 30, 24 + 25

Land rolling Soil
Good.

25

351

Township 3 North Range 34 East

Obs. North on West by Sec. 19
N. 21° E.

4000 Set post and made mound
of Earth for 1/4 S. cor.

8000 Set post and made mound
of Earth for cor. to Secs.
18, 19, 13 + 24

Land rolling, Soil Good

North on West by Sec. 18
N. 21° E.

1340 To Wild Horse ck the
Boundary of the Reser-
vation.

Land rolling. Good
Soil

of the Willamette Meridian 355

Chs North bet. Secs. 31 + 32
 40.00
 40.00 Set post and made Earth
 Mound for 1/4 Sec. cor.
 80.00
 80.00 Set post and made Earth mound
 for. cor. to Secs. 31, 32, 29 + 30
 Land rolling, Soil Good

East on random bet. Secs. 29 + 32
 N. 20° 30' E.

40.00
 40.00 Set temporary 1/4 S. Cor.
 80.14
 80.14 Intersected N + S. line at cor
 N on true line
 40.08
 40.08 Set Post and made Mound
 of Earth for 1/4 Sec. cor.
 80.14
 80.14 To corner
 Land rolling, Soil Good

27
358

Township 3 North Range 34 East

Chs. West on random bet. Secs. 30+31
4000 Set temporary $\frac{1}{4}$ S. cor.
7962 Intersected N+S line $\frac{1}{4}$
lks S of cor.
S. 8954' E. on true line
3962 Set post and made Earth
mound for $\frac{1}{4}$ Sec. cor.
7962 To corner
Land rolling. Soil Good

North bet. Secs. 29+30
4000 Set post and made Earth
mound for $\frac{1}{4}$ Sec. cor.
8000 Set post and made mound
of Earth for cor. to
Secs. 29.30. 19+20
Land rolling. Soil
Good Good Grass.

Chs East on random bet. Secs 20 & 29
N. 20° 30' E

4000 ^{40.00} Set temporary 1/4 Sec. cor.
8037 ^{80.34} Intersected N+S line 1 1/2 blocks
S of cor.

4018 ^{40.18} Set post and made Earth
8037 ^{80.31} Mound for 1/4 Sec. cor.

Pole corner
Land level. Good Soil

West bet. Secs. 19 & 20

4000 ^{40.00} Set temporary 1/4 S. cor.
7984 ^{79.84} Intersected N+S line at cor.
E. on true line

3984 ^{39.84} Set post and made mound
7984 ^{79.84} of Earth for 1/4 Sec. cor.
Pole cor.

Land level. Soil Good

29

Township 3 North Range 34 East

Chb Work bet. Secs. 19 & 20.

40.00 Set post and made mound of earth for 1/4 S. cor.

80.00 Set post and made Earth mound for cor. to Secs. 19, 20, 17, 18.



East on random bet. Secs. 17 & 20
Var. 21° E

40.00 Set temporary 1/4 S. cor.

80.00 Intersected N. & S. line 16 lks S. of cor.

S 79° 53' N. on true line

40.00 Set Post and made Earth mound for 1/4 S. cor.

Done To corner

Land rolls of Soil
Good. Good grass

of the Willamette

P. 6,

Meridian.
359

Chs. West on prairie bet. Secs. 18 & 19

40.00 Set temporary 1/4 Sec. cor.

49.75 Intersected N + S line at cor.
E. on true line

39.75 Set post and made Earth
Mound for 1/4 Sec. cor.

49.75 Tolomer.

Land rolling, Soil fork

Work bet. Secs. 17 & 18

40.00 Set post and made Earth Mound
for 1/4 Sec. cor.

57.10 To Wild Horse crk. the Dry
of the Reservation

Oct. 30. 1871.

Contract No 165

Surveyor General's Office
Eugene City 1872

The foregoing field notes of the survey
of the subdivisional lines of Tract
T3 North Range 34 East Will
Mer Oregon executed by J. H. Moody
deputy Surveyor under con-
tract No 164 bearing date
October 4 1871 having been
critically examined the
necessary explanation
made the same field notes
and the surveys they de-
scribe are hereby ap-
proved X

" I, Genas F. Moody, having been appointed a deputy Surveyor of the lands of the United States in Oregon, do solemnly swear that I will well and faithfully, and to the best of my skill and ability execute the duties confided to me pursuant to a contract with W. H. Odell, Surveyor General of public lands in Oregon, bearing date the 4th day of October 1871, according to the laws of the United States and the instructions received from the said Surveyor General.

G. F. Moody

Sworn and Subscribed before me
this 14th day of October 1871
W. Davenport
U.S. Comm^r Dist of Oregon

J. J. Kent, do solemnly swear that I will faithfully execute the duties of chain carrier; that I will level the chain upon uneven ground, and plumb the tally pins, whether by striking or dropping the same; that I will report the true distances to all notable objects, and the true length of all lines that I assist in measuring, to the best of my skill and ability.

J. J. Kent

Sworn and Subscribed before me
 This 14th day of October 1871
 W. Davenport
 U.S. Commr. Dist. of Oregon.

I. O. Hathaway do solemnly
swear that I will well and truly
perform the duties of Axeman
according to the instructions given
me, and to the best of my skill and
ability

O Hathaway

Sworn and Subscribed before me
This 14th day of October 1871

M. Davenport
U.S. Commr. Dist. of Oregon.

I, Geo. W. Renne, do
 solemnly swear that I will faithfully
 execute the duties of chain carrier; that
 I will level the chain upon uneven
 ground, and plumb the tally pins,
 whether by striking or dropping the
 same; that I will report the true
 distances to all notable objects, and
 the true length of lines that I assist
 in measuring, to the best of my skill
 and ability.

Geo. W. Renne

Sworn and Subscribed before me
 this 14th day of October 1871
 W. Davenport
 U.S. Comm. Dist. of Oregon

I Edward Gariopy, do solemnly swear that I will well and truly perform the duties of Axeman, according to the instructions given me, and to the best of my skill and ability.

Edward Gariopy

Sworn & Subscribed before me
 this 14th day of October 1871
 W. Davenport
 U.S. Commr. Dist. of Oregon.