

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FIELD NOTES
OF THE
DEPENDENT RESURVEY OF A PORTION OF THE SOUTH BOUNDARY,
TOWNSHIP 3 NORTH, RANGE 35 EAST,
AND
THE DEPENDENT RESURVEY OF A PORTION OF THE WEST BOUNDARY,
SUBDIVISIONAL LINES, AND SUBDIVISION-OF-SECTION LINES
OF SECTION 6, AND SUBDIVISION OF SECTION 6,
TOWNSHIP 2 NORTH, RANGE 35 EAST,
OF THE WILLAMETTE MERIDIAN,
IN THE STATE OF OREGON.

EXECUTED BY

Daniel E. Weller, Cadastral Surveyor
Richard L. Johnson, Cadastral Surveyor
Robert J. Mayorga, Cadastral Surveyor

Under Special Instructions dated October 13, 1988, approved October 20, 1988,
which provided for the surveys included under Group No. 1471,
and Assignment Instructions dated October 17, 1988, and June 13, 1990.

Survey commenced November 8, 1988

Survey completed July 26, 1990

INDEX DIAGRAM

TOWNSHIP 2 NORTH

RANGE 35 EAST

	3	2				
6	6	8 5	4	3	2	1
7	8	9	10	11	12	
18	17	16	15	14	13	
19	20	21	22	23	24	
30	29	28	27	26	25	
31	32	33	34	35	36	

Subdivision of Section 6Pages 10-17

T. 2 N., R. 35 E., Willamette Meridian, Oregon

CHAINS

The following field notes are those of the dependent resurvey of a portion of the south boundary, township 3 north, range 35 east, and of a portion of the west boundary and subdivisional lines, and subdivision-of-section lines of section 6, and subdivision of section 6, township 2 north, range 35 east, Willamette Meridian, Oregon.

The history of surveys pertaining to this resurvey is as follows:

In 1866, William H. Odell, U.S. Deputy Surveyor, surveyed the south boundary of township 3 north, range 35 east.

In 1871, Zenas F. Moody, U.S. Deputy Surveyor, surveyed the west boundary of township 2 north, range 35 east, and the south boundary of township 3 north, range 35 east.

In 1887, James P. Currin and James E. Noland, U.S. Deputy Surveyors, resurveyed the north and west boundaries of township 2 north, range 35 east, and subdivided the township and certain sections. Currin and Noland do not mention Odell's or Moody's surveys and their survey supersedes the 1866 survey by Odell and the 1871 survey by Moody.

In 1889, James P. Currin, U.S. Deputy Surveyor, resurveyed a portion of the west boundary and subdivisional lines of township 2 north, range 35 east, and subdivided certain sections.

In 1917-19, C. E. Redfield, Surveyor for the U. S. Indian Service, retraced certain section lines, remonumented corners, subdivided sections by the three mile method, and established corners. The field notes of the Redfield surveys are on file at the Umatilla Indian Reservation Agency Office in Mission, Oregon.

The survey was executed in accordance with the specifications as set forth in the Manual of Surveying Instructions, 1973, and Special Instructions dated October 13, 1988, for Group No. 1471, Oregon.

Preliminary to the resurvey, the lines of the prior surveys were retraced and a search was made for all corners and other calls of record. Identified corners were remonumented in their original positions; lost corners were reestablished and monumented at proportionate positions based on the record. The retracement data were thoroughly verified and only the true line field notes are given herein.

The directions of the lines are based on the true meridian as determined by direct solar observations and were carried forth by means of sustained angulation.

Detectable Electronically Energized Particles (DEEP-1 TM) were buried as memorials and used to reference certain corner monuments. The DEEP-1 is composed of strontium encased in a color coded plastic container. The units are 1 inch in diameter, 2½ inches long, weigh 2½ ounces, and are magnetically detectable to an average depth of 8 feet.

T. 2 N., R. 35 E., Willamette Meridian, Oregon

CHAINS

The geographic position (NAD 1927) of the corner of sections 32 and 33 only, on the south boundary of township 3 north, range 35 east, as determined by a tie to triangulation station "EAGLE," established by the National Geodetic Survey in 1963, is as follows:

Latitude 45° 41' 15.90" N. Longitude 118° 27' 16.47" W.

The mean magnetic declination is 20° East.

**Dependent Resurvey of a Portion of the South Boundary,
T. 3 N., R. 35 E., Willamette Meridian, Oregon**

(Restoring the survey by James P. Currin and
James E. Noland in 1887)

Beginning at the cor. of secs. 32 and 33, perpetuated by C. E. Redfield, Indian Service Surveyor, in 1917-19, from original evidence no longer in existence, recovered, recorded, and used in a private survey by David H. Krumbien, Registered Land Surveyor No. 933, in 1970; monumented with an iron post, 2 ins. diam., firmly set, projecting 12 ins. above ground, in a mound of stone, 3 ft. base, 8 ins. high, with brass cap mkd.

T3N	
S32	S33
T2N R35E	

From this point, the National Geodetic Survey triangulation station "EAGLE," 1963, bears N. 35° 26' 00" E., 300.510 chs. dist., monumented with a concrete post, 12 ins. square, firmly set flush with the ground surface, with a brass tablet, 3 ins. diam., seated in the top, mkd. EAGLE 1963 and a triangle.

S. 89° 51' 00" W., on the S. bdy. of sec. 32.

Descend over broken S. slope, through light timber and medium undergrowth.

40.055

Point for the $\frac{1}{4}$ sec. cor. of sec. 32 only, at proportionate distance; there is no remaining evidence of the original corner.

Set a stainless steel post, 28 ins. long, 2 $\frac{1}{2}$ ins. diam., 21 ins. in the ground, with brass cap mkd.

T3N	R35E
$\frac{1}{4}$	S 32
1990	

from which

A cottonwood, 23 ins. diam., bears S. 52 $\frac{1}{2}$ ° W., 135 $\frac{1}{2}$ lks. dist., mkd. X BT.

A cottonwood, 12 ins. diam., in a clump of cottonwood, bears N. 60 $\frac{1}{4}$ ° W., 15 $\frac{1}{2}$ lks. dist., mkd. X BT.

Dependent Resurvey of a Portion of the South Boundary,
T. 3 N., R. 35 E., Willamette Meridian, Oregon

CHAINS							
	Deposit white "DEEP-1" magnetic marker at base of stainless steel post.						
	Continue over river bottom, through light timber and moderate undergrowth.						
41.50	Enter Umatilla River, edge bears N. 80° W. and S. 80° E., course N. 65° W.						
78.680	Point for the closing cor. of secs. 5 and 6, T. 2 N., R. 35 E., at proportionate distance; there is no remaining evidence of the original corner. The corner is located in the Umatilla River where it is impracticable to establish a permanent monument.						
78.75	Leave river, edge bears N. 50° W.; thence over nearly level land.						
80.110	Point for the cor. of secs. 31 and 32 only, at proportionate distance; there is no remaining evidence of the original corner. Set a stainless steel post, 28 ins. long, 2½ ins. diam., 21 ins. in the ground, with brass cap mkd.						
	<table style="margin-left: auto; margin-right: auto;"> <tr> <td style="padding: 0 10px;">T3N</td> <td style="padding: 0 10px;">R35E</td> </tr> <tr> <td style="padding: 0 10px;">S 31</td> <td style="padding: 0 10px;">S 32</td> </tr> <tr> <td colspan="2" style="text-align: center; padding: 0 10px;">1990</td> </tr> </table>	T3N	R35E	S 31	S 32	1990	
T3N	R35E						
S 31	S 32						
1990							
	from which						
	<p style="margin-left: 40px;">A cottonwood, 16 ins. diam., bears N. 87¼° W., 118½ lks. dist., mkd. X BT.</p>						
	Deposit white "DEEP-1" magnetic marker at base of stainless steel post.						
	<hr/> <p>S. 89° 51' 00" W., on the S. bdy. of sec. 31.</p>						
	Over nearly level land, through light timber and medium undergrowth.						
5.10	Enter Umatilla River, edge bears N. 70° E. and S. 70° W., course S. 70° W.						
18.590	Point for the E 1/16 sec. cor. of sec. 6 only, T. 2 N., R. 35 E., is located in the Umatilla River where it is impracticable to establish a permanent monument.						
19.05	Right bank, Umatilla River, edge bears N. 60° E. and S. 60° W.; thence across river bottom land.						
20.035	The E 1/16 sec. cor. of sec. 31 only, established by C. E. Redfield, Indian Service Surveyor, in 1917-19, and is accepted as the corner; monumented with an iron post, 2 ins. diam., firmly set, projecting 8 ins. above ground, in a mound of stone, 3 ft. base, to top, with brass cap mkd.						

Dependent Resurvey of a Portion of the South Boundary,
T. 3 N., R. 35 E., Willamette Meridian, Oregon

CHAINS	
	<p style="text-align: center;">INDIAN ALLOTMENT T3N 1/16 <u>3 S31</u></p> <p>from which a new reference monument</p> <p style="padding-left: 40px;">A stainless steel post, 28 ins. long, 2½ ins. diam., set 16 ins. in the ground, in a mound of stone, 2½ ft. base, to top, for a reference monument, bears S. 30° E., 20 lks. dist., with brass cap mkd. RM E1/16 S31 13.2 FT TO COR 1990 and an arrow pointing to the corner.</p> <hr style="width: 20%; margin: 10px auto;"/> <p>S. 89° 31' 30" W., beginning new measurement.</p> <p>Ascend broken S. slope.</p>
18.580	<p>The ¼ sec. cor. of sec. 6 only, T. 2 N., R. 35 E., established by C. E. Redfield, Indian Service Surveyor, in 1917-19, recovered, recorded, and used in private surveys in 1971 by David H. Krumbein, Registered Land Surveyor No. 933, and in 1982 by William R. Wells, Registered Land Surveyor No. 1106, and is accepted as the corner; monumented with an iron post, 2 ins. diam., firmly set, projecting 18 ins. above ground, in a mound of stone, 3 ft. base, to top, with brass cap mkd.</p> <p style="text-align: center;">S31 <u>T3N R35E</u> 1/4 S6 T2N R35E</p> <p>from which</p> <p style="padding-left: 40px;">A pink "DEEP-1" magnetic marker, buried 12 ins. in the ground, bears S. 45° E., 30 lks. dist.</p> <p style="padding-left: 40px;">A blue "DEEP-1" magnetic marker, buried 16 ins. in the ground, bears S. 45° W., 15 lks. dist.</p> <hr style="width: 20%; margin: 10px auto;"/> <p>S. 89° 02' 30" W., beginning new measurement.</p> <p>Continue over broken S. slope.</p>
1.440	<p>The ¼ sec. cor. of sec. 31 only, reestablished at proportionate position by C. E. Redfield, Indian Service Surveyor, in 1917-19, recovered, recorded, and used in a private survey in 1970 by David H. Krumbein, Registered Land Surveyor No. 933. There is no remaining evidence of the original corner, therefore this position is accepted as the corner; monumented with an iron post, 2 ins. diam., firmly set, projecting 24 ins. above the ground, in a mound of stone, 4 ft. base, to top, with brass cap mkd.</p> <p style="text-align: center;">1/4 S31 <u>T3N R35E</u> S6 T2N R35E</p> <hr style="width: 20%; margin: 10px auto;"/>

Dependent Resurvey of a Portion of the South Boundary,
T. 3 N., R. 35 E., Willamette Meridian, Oregon

CHAINS										
	<p>S. 89° 24' 00" W., beginning new measurement.</p> <p>Continue along broken S. slope.</p>									
0.50	<p>Draw, 30 lks. wide, drains S.</p>									
18.590	<p>The W 1/16 sec. cor. of sec. 6 only, T. 2 N., R. 35 E., established by C. E. Redfield, Indian Service Surveyor, in 1917-19, and is accepted as the corner; monumented with an iron post, 2 ins. diam., firmly set, projecting 30 ins. above ground, in a mound of stone, 3 ft. base, to top, with brass cap mkd.</p>									
	<table style="margin-left: auto; margin-right: auto;"> <tr><td colspan="2" style="text-align: center;">S31</td></tr> <tr><td style="text-align: center;">T3N</td><td style="text-align: center;">R35E</td></tr> <tr><td style="text-align: center;">1/16 9</td><td style="text-align: center;">S6</td></tr> <tr><td style="text-align: center;">T2N</td><td style="text-align: center;">R35E</td></tr> </table>	S31		T3N	R35E	1/16 9	S6	T2N	R35E	
S31										
T3N	R35E									
1/16 9	S6									
T2N	R35E									
	<p>from which</p> <p style="padding-left: 40px;">A pink "DEEP-1" magnetic marker, buried 8 ins. in the ground, bears S. 45° E., 20 lks. dist.</p> <p style="padding-left: 40px;">A blue "DEEP-1" magnetic marker, buried 10 ins. in the ground, bears S. 45° W., 20 lks. dist.</p>									
	<p>The corner is located at the corner of old barbed wire fences, extending S. and W.</p> <hr style="width: 20%; margin: 10px auto;"/>									
	<p>S. 89° 18' 00" W., beginning new measurement.</p> <p>Continue over broken S. slope, along barbed wire fence.</p>									
1.435	<p>The W 1/16 sec. cor. of sec. 31 only, established by C. E. Redfield, Indian Service Surveyor, in 1917-19, and is accepted as the corner; monumented with an iron post, 2 ins. diam., firmly set, projecting 24 ins. above ground, in a mound of stone, 4 ft. base, to top, with brass cap mkd.</p>									
	<table style="margin-left: auto; margin-right: auto;"> <tr><td colspan="2" style="text-align: center;">T3N</td><td style="text-align: center;">R35E</td></tr> <tr><td style="text-align: center;">1/16 14</td><td style="text-align: center;">S6</td><td style="text-align: center;">S31</td></tr> <tr><td colspan="2" style="text-align: center;">T2N</td><td style="text-align: center;">R35E</td></tr> </table>	T3N		R35E	1/16 14	S6	S31	T2N		R35E
T3N		R35E								
1/16 14	S6	S31								
T2N		R35E								
	<p>from which</p> <p style="padding-left: 40px;">A silver "DEEP-1" magnetic marker, buried 12 ins. in the ground, bears N. 45° E., 10 lks. dist.</p>									
	<p>The corner is located 5 lks. N. of barbed wire fence, extending E. and W.</p> <hr style="width: 20%; margin: 10px auto;"/>									
	<p>S. 89° 18' 30" W., beginning new measurement.</p> <p>Continue along broken S. slope, generally along a barbed wire fence.</p>									
13.690	<p>Point for the closing cor. of Tps. 2 N., Rs. 34 and 35 E., hereinafter described.</p>									

**Dependent Resurvey of a Portion of the South Boundary,
T. 3 N., R. 35 E., Willamette Meridian, Oregon**

CHAINS	
20.000	<p>The cor. of Tps. 3 N., Rs. 34 and 35 E., perpetuated by C. E. Redfield, Indian Service Surveyor, in 1917-19, from original evidence no longer in existence, monumented with an iron post, 2 ins. diam., firmly set, projecting 15 ins. above ground, in a mound of stone, 3 ft. base, to top, with brass cap mkd.</p> <p align="center"> T3N S36 S31 <u>R34E R35E</u> S1 T2N R34E </p> <p>from which</p> <p align="center">A silver "DEEP-1" magnetic marker, buried 12 ins. in the ground, bears N. 45° E., 20 lks. dist.</p> <hr/> <p align="center">Dependent Resurvey of a Portion of the West Boundary, T. 2 N., R. 35 E., Willamette Meridian, Oregon</p> <hr/> <p align="center">(Restoring the resurvey by James P. Currin and James E. Noland in 1887)</p> <hr/> <p>From the ¼ sec. cor. of secs. 1 and 6 on the W. bdy. of the Tp., perpetuated by C. E. Redfield, Indian Service Surveyor, in 1917-19, from original evidence no longer in existence, recovered, and recorded in a private survey by William R. Wells, Registered Land Surveyor No. 1106, in 1989; monumented with an iron post, 2 ins. diam., firmly set, projecting 18 ins. above ground, in a mound of stone, 3 ft. base, to top, with brass cap mkd.</p> <p align="center"> S1 R34E T2N ¼ ¼ T2N R35E S6 </p> <p>from which a new reference monument</p> <p align="center">A stainless steel post, 28 ins. long, 2½ ins. diam., set 24 ins. in the ground, for a reference monument, bears N. 60° W., 34.8 lks. dist., with brass cap mkd. RM ¼ S1 23.0 FT TO COR T2N R34E 1988 and an arrow pointing to the corner. Deposit white "DEEP-1" magnetic marker at base of stainless steel post.</p> <p>N. 1° 07' 00" W., bet. secs. 1 and 6.</p> <p>Along W. edge of graveled road, 30 lks. wide, bears N.</p>
13.80	Umatilla River, 200 lks. wide, course S. 50° W.; asc. over broken S. slope.
19.50	Union Pacific Railroad, bears NE. and SW.

Dependent Resurvey of a Portion of the West Boundary,
T. 2 N., R. 35 E., Willamette Meridian, Oregon

CHAINS															
20.245	<p>The N 1/16 sec. cor. of secs. 1 and 6, established by C. E. Redfield, Indian Service Surveyor, in 1917-19, recovered, and recorded in a private survey by William R. Wells, Registered Land Surveyor No. 1106, in 1989, and is accepted as the corner; monumented with an iron post, 2 ins. diam., firmly set, projecting 18 ins. above ground, with brass cap mkd.</p> <table border="0" style="margin-left: auto; margin-right: auto;"> <tr> <td>T2N</td> <td>S1</td> <td>S6</td> <td>R35E</td> </tr> <tr> <td>R34E</td> <td>11</td> <td>16</td> <td>T2N</td> </tr> <tr> <td colspan="4" style="text-align: center;">1/16</td> </tr> </table> <p>from which a new reference monument</p> <p>A stainless steel post, 28 ins. long, 2½ ins. diam., set 22 ins. in the ground, for a reference monument, bears N. 45° W., 75.8 lks. dist., with brass cap mkd. RM T2N R34E N 1/16 S1 50.0 FT TO COR 1988, and an arrow pointing to the corner.</p> <hr style="width: 20%; margin: 10px auto;"/> <p>N. 1° 30' 30" W., beginning new measurement.</p> <p>Ascend over broken SW. slope.</p>	T2N	S1	S6	R35E	R34E	11	16	T2N	1/16					
T2N	S1	S6	R35E												
R34E	11	16	T2N												
1/16															
12.135	<p>The original closing cor. of Tps. 2 N., Rs. 34 and 35 E., perpetuated by C. E. Redfield, Indian Service Surveyor, in 1917-19, from original evidence no longer in existence, monumented with an iron post, 2 ins. diam., projecting 24 ins. above ground, supported in a mound of stone, 4 ft. base, to top, with brass cap mkd. S31 T3N R35E CC S1 S6 R34E R35E T2N. Add the marks AM and bury the iron post in place, 6 ins. below surface.</p>														
12.335	<p>Intersect the S. bdy. of sec. 31, T. 3 N., R. 35 E.</p> <p>Point for the closing cor. of Tps. 2 N., Rs. 34 and 35 E.</p> <p>Set a stainless steel post, 28 ins. long, 2½ ins. diam., 14 ins. in the ground, in a mound of stone, 3 ft. base, to top, with brass cap mkd.</p> <table border="0" style="margin-left: auto; margin-right: auto;"> <tr> <td>T3N</td> <td>R35E</td> </tr> <tr> <td colspan="2" style="text-align: center;">S31</td> </tr> <tr> <td>S1</td> <td>S6</td> </tr> <tr> <td>R34E</td> <td>R35E</td> </tr> <tr> <td colspan="2" style="text-align: center;">T2N</td> </tr> <tr> <td colspan="2" style="text-align: center;">CC</td> </tr> <tr> <td colspan="2" style="text-align: center;">1988</td> </tr> </table> <p>from which</p> <p>A pink "DEEP-1" magnetic marker, buried 12 ins. in the ground, bears S. 45° E., 10 lks. dist.</p> <p>A blue "DEEP-1" magnetic marker, buried 12 ins. in the ground, bears S. 45° W., 10 lks. dist.</p>	T3N	R35E	S31		S1	S6	R34E	R35E	T2N		CC		1988	
T3N	R35E														
S31															
S1	S6														
R34E	R35E														
T2N															
CC															
1988															

**Dependent Resurvey of a Portion of the West Boundary,
T. 2 N., R. 35 E., Willamette Meridian, Oregon**

CHAINS

From this point, the cor. of Tps. 3 N., Rs. 34 and 35 E., bears S. 89° 18' 30" W., 6.310 chs. dist., hereinbefore described.

**Dependent Resurvey of a Portion of the Subdivisional Lines,
T. 2 N., R. 35 E., Willamette Meridian, Oregon**

(Restoring the survey by James P. Currin and James E. Noland,
in 1887, and the resurvey by James P. Currin, in 1889)

From the cor. of secs. 5, 6, 7, and 8, reestablished by C. E. Redfield, Indian Service Surveyor, in 1917-19. There is no remaining evidence of the original corner, therefore, this position is accepted as the corner; monumented with an iron post, 2 ins. diam., firmly set, projecting 8 ins. above ground, with brass cap mkd.

S6	S5
S7	S8
T2N	R35E

The corner is located in an old barbed wire fence, bears N. and S. N. 0° 47' 30" E., bet. secs. 5 and 6.

Descend over broken NW. slope.

20.035

The S 1/16 sec. cor. of secs. 5 and 6, perpetuated by C. E. Redfield, Indian Service Surveyor, in 1917-19, from original evidence no longer in existence, monumented with an iron post, 2 ins. diam., firmly set, projecting 8 ins. above ground, with brass cap mkd.

1/16	
S6	S5
12	15
T2N	R35E

The corner is located at the intersection of barbed wire fences, extending S. and W.

N. 0° 16' 30" W., beginning new measurement.

Descend over rolling wheatfield.

20.535

Point for the 1/4 sec. cor. of secs. 5 and 6, at proportionate distance; there is no remaining evidence of the original corner.

Set a stainless steel post, 28 ins. long, 2 1/2 ins. diam., 46 ins. in the ground, with top 18 ins. below surface, with brass cap mkd.

T2N	R35E
S 6	S 5
1/4	
1990	1990

from which

Dependent Resurvey of a Portion of the Subdivisional Lines,
T. 2 N., R. 35 E., Willamette Meridian, Oregon

CHAINS	
	<p>A pink "DEEP-1" magnetic marker, buried 22 ins. in the ground, bears S. 45° E., 10 lks. dist.</p> <p>An orange "DEEP-1" magnetic marker, buried 22 ins. in the ground, bears N. 45° W., 10 lks. dist.</p> <p>Deposit white "DEEP-1" magnetic marker at base of stainless steel post.</p> <p>Continue descent over rolling wheatfield.</p>
35.20	Utility line, bears E. and W.
36.30	Bluff, edge bears N. 60° W. and S. 60° E.; enter heavy undergrowth.
41.070	<p>Point for the N 1/16 sec. cor. of secs. 5 and 6.</p> <p>Set a stainless steel post, 28 ins. long, 2½ ins. diam., 24 ins. in the ground, with brass cap mkd.</p> <div style="text-align: center;"> <p>N 1/16 S 6 S 5 1990</p> </div> <p>from which</p> <p>A cherry, 11 ins. diam., bears S. 31¼° E., 19½ lks. dist., mkd. N 1/16 S5 BT.</p> <p>Deposit white "DEEP-1" magnetic marker at base of stainless steel post.</p> <p>Continue over nearly level land.</p>
41.25	Wire fence, bears N. 85° E. and S. 85° W.
41.90	Union Pacific Railroad, bears N. 50° E. and S. 50° W.
42.40	Utility line, 16 wire, bears N. 50° E. and S. 50° W.
43.05	County Road No. 900, asphalt surface, 30 lks. wide, bears N. 80° E. and S. 80° W.
54.665	<p>Point selected for the witness cor. to the closing cor. of secs. 5 and 6.</p> <p>Set a stainless steel post, 28 ins. long, 2½ ins. diam., 24 ins. in the ground, in a collar of stone, with brass cap mkd.</p> <div style="text-align: center;"> <p>WC T 3 N ↑ R 35 E S 6 S 5 T 2 N R 35 E CC 1990</p> </div> <p>from which</p>

**Dependent Resurvey of a Portion of the Subdivisional Lines,
T. 2 N., R. 35 E., Willamette Meridian, Oregon**

CHAINS							
	<p>A cottonwood, 14 ins. diam., bears S. 38° E., 35½ lks. dist., mkd. X BT.</p> <p>A cottonwood, 13 ins. diam., bears S. 38° W., 29 lks. dist., mkd. X BT.</p> <p>Deposit a white "DEEP-1" magnetic marker at the base of the stainless steel post.</p> <p>Continue over nearly level land.</p>						
54.80	Left bank of the Umatilla River, bears N. 65° W. and S. 65° E., course N. 65° W.; thence in the river.						
54.970	Intersect the S. bdy. of sec. 32, T. 3 N., R. 35 E., at the true point for the closing cor. of secs. 5 and 6, hereinbefore described.						
	From this point, the cor. of secs. 31 and 32 only, T. 3 N., R. 35 E., bears S. 89° 51' 00" W., 1.430 chs. dist., hereinbefore described.						
<hr/> <p>Dependent Resurvey of a Portion of the Subdivision of Section Lines of Section 6, T. 2 N., R. 35 E., Willamette Meridian, Oregon</p> <hr/>							
<p>(Restoring the survey by James P. Currin, in 1889)</p> <hr/>							
<p>From the center E 1/16 sec. cor. of sec. 6, perpetuated by C. E. Redfield, Indian Service Surveyor, in 1917-19, from original evidence no longer in existence, recovered, recorded, and used in a private survey by William R. Wells, Registered Land Surveyor No. 1106, in 1989; monumented with an iron post, 2 ins. diam., firmly set, with top 2 ins. below surface, with brass cap mkd.</p>							
<table border="1"> <tr> <td>1/16</td> <td></td> </tr> <tr> <td>E</td> <td>S6</td> </tr> <tr> <td>T2N</td> <td>R35E</td> </tr> </table>		1/16		E	S6	T2N	R35E
1/16							
E	S6						
T2N	R35E						
from which							
<p>A silver "DEEP-1" magnetic marker, buried 14 ins. in the ground, bears N. 45° E., 25 lks. dist.</p> <p>A pink "DEEP-1" magnetic marker, buried 14 ins. in the ground, bears S. 45° E., 10 lks. dist.</p> <p>Set a steel fence post, 5 ft. long, alongside iron post.</p> <p>N. 0° 31' 30" W., on the N. and S. center line of the NE¼ of sec. 6.</p> <p>Descend over rolling wheatfield.</p>							
9.940	Point for the center S-NE 1/64 sec. cor. of sec. 6.						

Subdivision of Section 6,
T. 2 N., R. 35 E., Willamette Meridian, Oregon

CHAINS	
	N. 88° 01' 00" W., on the N. bdy. of the S $\frac{1}{2}$ of the S $\frac{1}{2}$ of the N $\frac{1}{2}$ of the SW $\frac{1}{4}$ of the NE $\frac{1}{4}$ of sec. 6.
1.85	County Road NO. 900, asphalt surface, 30 lks. wide, bears N. 35° E. and S. 35° W.
2.40	Union Pacific Railroad, bears N. 80° E. and S. 80° W.
14.890	The 1/1024 sec. cor. on the N. and S. center line of sec. 6.
GENERAL DESCRIPTION	
<p>Township 2 North, Range 35 East is located approximately 16 miles east of Pendleton, Oregon. The small community of Thorn Hollow, Oregon, is located in section 5.</p>	
<p>The Umatilla River meanders through the northerly portion of section 6 with several seasonal creeks draining the section. Elevations range from about 1500 feet above sea level along the river bottom, to about 2100 feet above sea level at the corner of sections 5, 6, 7, and 8. The majority of the township is covered with rolling ground, cultivated with various grains. The soil is very rocky along the river, but is almost rock free in the sandy wheatfields.</p>	
<p>Access is by way of County Road No. 900 which generally parallels the Umatilla River, and the Union Pacific Railroad.</p>	
<p>The vegetation along the Umatilla River and creek bottoms consists of very dense undergrowth of willow, sumac, blackberry, and wild rose, with scattered pine, cottonwood, and fir timber.</p>	
<p>There were no mineral deposits noted along the lines surveyed.</p>	
<p>The mean magnetic declination is 20° East, as shown on the United States Geological Survey quadrangle "THORN HOLLOW, OREG.," 7$\frac{1}{2}$ minute series, dated 1964.</p>	

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FIELD ASSISTANTS

Richard S. Shatto	Surveying Technician
Gregory G. Carter	Surveying Technician
James A. Read	Surveying Technician

CERTIFICATE OF SURVEY

We, Daniel E. Weller, Richard L. Johnson, and Robert J. Mayorga, Cadastral Surveyors, HEREBY CERTIFY upon honor that, in pursuance of special instructions bearing date of the 13th day of October 1988, we have dependently resurveyed a portion of the south boundary of township 3 north, range 35 east, and a portion of the west boundary, subdivisional lines, and subdivision of section lines of section 6, and subdivided section 6, township 2 north, range 35 east, of the Willamette Meridian, in the State of Oregon, which are represented in the foregoing field notes as having been executed by us and under our direction; and that said survey has been made in strict conformity with said special instructions, the Manual of Instructions for the Survey of the Public Lands of the United States, and in specific manner described in the foregoing field notes.

2/10/92
Date

Daniel E. Weller
Cadastral Surveyor

2/10/92
Date

Richard L. Johnson
Cadastral Surveyor

2/10/92
Date

Robert J. Mayorga
Cadastral Surveyor

CERTIFICATE OF APPROVAL

Bureau of Land Management
Portland, Oregon

The foregoing field notes of the dependent resurvey of a portion of the south boundary, township 3 north, range 35 east, and the dependent resurvey of a portion of the west boundary, subdivisional lines and the subdivision of section lines of section 6, and the subdivision of section 6, township 2 north, range 35 east, Willamette Meridian, Oregon, executed by Daniel E. Weller, Richard L. Johnson, and Robert J. Mayorga, Cadastral Surveyors, having been critically examined and found correct, are hereby approved.

March 13, 1992
Date

Wayne M. Gardner
Chief Cadastral Surveyor of Oregon

~~CERTIFICATE OF TRANSCRIPT~~

I CERTIFY That the foregoing transcript of the field notes of the above-described surveys in T. 2 N., R. 35 E., Willamette Meridian, Oregon, is a true copy of the original field notes.

Date

Chief Cadastral Surveyor of Oregon