

RECEIVED AND FILED,

this 31<sup>st</sup> day of June 1900

330

*Platted*

*B.*

ROBERT A. HABERSHAM,  
U. S. Surveyor General for Oregon.

FIELD NOTES

Of the Subdivisional Lines of  
fractional  
T. 3 North R. 37 East

Willamette Meridian, Oregon,

BY

William O. Campbell  
Deputy Surveyor,

UNDER

Joint Contract No. 708 dated May 1., 1900

Survey commenced July 23<sup>d</sup>, 1900

Survey completed August 29<sup>d</sup>, 1900

Platted

Copied for Washington 4-3-1900-19.

# FIELD NOTES

Of the survey of the *subdivision* .....

Lines of *fractional Township No. 3 North* .....

*Range No. 37 East* ..... Willamette Meridian, Oregon,

as surveyed by *William E. Campbell* .....

U. S. Deputy Surveyor, under his <sup>joint</sup> contract No. *918* .....

dated *May first* ....., 1900..

Survey commenced *July 23<sup>rd</sup>* ....., 1900..

Survey completed *August 29<sup>th</sup>* ....., 1900..

## NAMES AND DUTIES OF ASSISTANTS.

*Charles E. Campbell* ....., Chainman.

*Roy J. Campbell* ....., Chainman.

....., Chainman.

....., Chainman.

*Charles E. Campbell* ....., Axman.

*Roy J. Campbell* ..... ~~Axman.~~  
Moundman.

....., Flagman.

336B

PRELIMINARY OATHS OF ASSISTANTS.

WE, Charles L. and

Roy J. Campbell

do solemnly swear that we will faithfully execute the duties of chainmen; that we will level the chain over even and uneven ground, and plumb the tally pins, either by sticking or dropping the same; that we will report the true distance to all notable objects, and the true length of all lines that we assist in measuring, to the best of our skill and ability, and in accordance with the instructions given us, in the survey of the subdivision

lines of fractional Township No. 3 North, range No. 37 East, Willamette Meridian, Oregon.

Charles L. Campbell, Chainman.

Roy J. Campbell, Chainman.

, Chainman.

, Chainman.

Subscribed and sworn to before me this Twentieth

day of July, 1900

William E. Campbell

U. S. Deputy Surveyor

[SEAL.]

WE, Charles L. and

Roy J. Campbell

do solemnly swear that we will well and truly perform the duties of axmen and mound men, and flagman in the establishment of corners and other duties, according to instructions given us, and to the best of our

skill and ability, in the survey of the subdivision lines of fractional Township No. 3 North, range No. 37 East, Willamette Meridian, Oregon.

Charles L. Campbell, Axman.

Roy J. Campbell, Moundman.

, Axman.

, Flagman.

Subscribed and sworn to before me this Twentieth

day of July, 1900

William E. Campbell

U. S. Deputy Surveyor

[SEAL.]

# INDEX

337

Referring the Lines to the Pages of the Field Notes.

*South half of*  
*Township No 3 North, Range No 37 East, Will. Mer.*

6		5		4		3		2		1
7		8		9		10		11		12
18		17		16		15		14		13
19	56	20	42	21	32	22	21	23	11	24
54		53		41		30		20		9
30	51	29	39	28	27	27	18	26	7	25
48		46		36		26		16		5
31	44	32	35	33	24	34	14	35	3	36

Meanders of \_\_\_\_\_ Pages \_\_\_\_\_ to \_\_\_\_\_

Meanders of \_\_\_\_\_ Pages \_\_\_\_\_ to \_\_\_\_\_

## Subdivision of T. 3 N., R. 57 E. - Continued.

Chains: on the 'dest. cor.; and determine a true meridian by the solar at the cor. of secs. 29, 30, 31<sup>2d</sup> & 32, which agrees with the observation made at this point August 23. Thence I run

N.  $89^{\circ} 44' W.$ , on a random line bet. secs. 30<sup>2d</sup> & 31.

40.00 Set temp.  $\frac{1}{4}$  sec. cor.

81.79 Intersect W. bdy. of Tp. 2 ch. 10 lbs. S.  $1^{\circ} 42' E.$  of the cor. of secs. 25<sup>2d</sup> & 36, which point I determine by the one remaining witness-tree, a fir, 8 ins. diam., bearing N.  $20^{\circ} W.$ , 56 lbs. dist., from old mound of stone<sup>2d</sup> marked as described by the surveyor-general; the cor. stone is missing.

I re-establish this sec. cor. by setting an ironstone  $15 \times 10 \times 6$  ins. 10 ins. in the ground, for cor. of secs. 25<sup>2d</sup> & 36, marked with 5 notches on N. and 1 notch on S. edges, and raise a mound of stone 2 ft. base,  $1\frac{1}{2}$  ft. high, W. of cor. Pit impracticable.

Note: By retracement of W. bdy. of sec. 31 I determine my random line to be closed 25 lbs. N.  $1^{\circ} 42' W.$  of the cor. of secs. 30<sup>2d</sup> & 31, which is a basalt stone  $12 \times 5 \times 4$  ins. above ground, marked and witnessed as described in the field notes of recovery returned to the surveyor-general.

Thence I run

S.  $89^{\circ} 55' E.$ , on a true line bet. secs. 30<sup>2d</sup> & 31.

Over stony level of ridge - N.  $20^{\circ} W.$ ,<sup>2d</sup> & S  $20^{\circ} E.$

.50 Descend through timber and dense undergrowth;

## Subdivision of D. 3 N., R. 37 E. - Continued.

81.60 Intersect W. bdy. of Sp. 1 ch. 40 ths. S. of the cor. of secs. 24<sup>rd</sup> & 25, as determined by remains of stone mound, decayed post<sup>rd</sup> & marked stone described by the surveyor-general and 5 ths. S. of the closing cor. of secs. 19<sup>th</sup> & 30, as determined by retriangulation, a basalt stone 6 x 6 x 5 ins. above ground, marked & witnessed as described in the field notes of re-survey returned to the surveyor-general.

Thence I run

S.  $89^{\circ} 58' E.$ , on a true line bet. secs. 19<sup>th</sup> & 30.

Ascending steep, grassy hill through widely scattering timber & dense undergrowth; bears N. & S.

2.25 Stock trail; bears N. & S.

5.75 Leave dense undergrowth.

10.50 Top of bare, stony ridge; N. & S.; descend into the "Bobbed" cañon; bears N.W. & S.E.

11.00 Enter heavy timber & undergrowth; bears N. & S.

21.75 Ravine, course N.  $30^{\circ} W.$ ; dense undergrowth.

37.00 Hill slopes N.  $20^{\circ} E.$

41.60 At point 200 feet below the closing sec. cor. and set a basalt stone 15 x 12 x 10 ins. 10 ins. in the ground, for  $\frac{1}{4}$  sec. cor., marked  $\frac{1}{4}$  on N. face, from which

A fir, 18 ins. diam., bears S.  $19^{\circ} W.$ , 37 ths. dist., marked  $\frac{1}{4}$  S. 30, B. I.;

A pine, 14 ins. diam., bears N.  $3\frac{1}{2}^{\circ} W.$ , 39 ths. dist., marked  $\frac{1}{4}$  S. 19, B. I.

Thence through scattering timber & undergrowth.

46.50 Foot of hill; over gravel bar.

The Dalles, Ore., Jan. 8, 1901.

Robert A. Hobusham - U. S. Surveyor - General for Oregon,

Portland:

Sir:

I send herewith guide maps for Tps. 2<sup>nd</sup> & 3<sup>rd</sup> N., R. 37<sup>th</sup> & 48<sup>th</sup> E. I discover the following omissions in notes of T. 3 N., R. 37 E.: On west boundary of sec. 19, at 54.80 chs., trail up creek, bears with stream; N. 0° 2' W., bet. sec. 21<sup>st</sup> & 22<sup>nd</sup>, at 2.00 chs., trail from Greaves' Butte, bears N.W. & S.E. - then N.E.; N. 0° 3' W., bet. sec. 28<sup>th</sup> & 29<sup>th</sup>, at 45.50 chs. trail, bears N.E. & S.W. And in T. 2 N., R. 48 E., on line S. 89° 54' W., bet. sec. 11<sup>th</sup> & 14<sup>th</sup>, I find trail down hollow - at 18.50 chs. is omitted. All these trails were rattled, faded & dim at the points mentioned which accounts for the failure of the chain bears to notice them; they are now recalled by me & set down correctly on the accompanying maps.

Very Respectfully

William E. Campbell

U. S. Deputy Surveyor

P. S.: I believe I forgot to mention it in my general descriptions, but these townships are more than generously supplied with rattlersakes of the most business-like qualifications.

Yours Truly,

FINAL OATHS FOR SURVEYS.

399  
A list of the names of the individuals employed by William E. Campbell, U. S. Deputy Surveyor, to assist in running, measuring, and marking the lines and corners described in the foregoing field notes of the survey of the subdivision lines of fractional township No. 3 north, range No. 37 east, Willamette Meridian, Oregon, showing the respective capacities in which they acted:

\_\_\_\_\_, Compassman.  
Charles E. Campbell, Chainman.  
Roy I. Campbell, Chainman.  
\_\_\_\_\_, Chainman.  
\_\_\_\_\_, Chainman.  
Charles E. Campbell, Axeman.  
Roy I. Campbell, ~~Axeman.~~ <sup>Moundman.</sup>  
\_\_\_\_\_, Flagman.

FINAL OATHS OF ASSISTANTS.

We hereby certify that we assisted William E. Campbell, U. S. Deputy Surveyor, in surveying all those parts or portions of the subdivision lines of fractional township No. 3 north, range No. 37 east, Willamette Meridian, Oregon, as are represented in the foregoing field notes as having been surveyed by him and under his direction; and that said survey has been in all respects, to the best of our knowledge and belief, well and faithfully surveyed, and the corner monuments established according to the instructions furnished by the U. S. Surveyor General of Oregon:

\_\_\_\_\_, Compassman.  
Charles E. Campbell, Chainman.  
Roy I. Campbell, Chainman.  
\_\_\_\_\_, Chainman.  
\_\_\_\_\_, Chainman.  
Charles E. Campbell, Axeman.  
Roy I. Campbell, ~~Axeman.~~ <sup>Moundman.</sup>  
\_\_\_\_\_, Flagman.

Subscribed and sworn to before me, this thirtieth day of August, 1900.

[SEAL.]

William E. Campbell  
U. S. Deputy Surveyor

## FINAL OATH OF DEPUTY SURVEYOR.

I, William E. Campbell, United States

Deputy Surveyor, do solemnly swear that in pursuance of instructions received from Robert A. Habersham, U. S.

Surveyor-General for Oregon, bearing date of the eleventh

day of May, 1900, I have well, faithfully, and truly, in my own proper person, and in strict conformity with the instructions furnished by the U. S. Surveyor-General for Oregon, the Manual of Surveying Instructions, and the laws of the United States, surveyed

all those parts or portions of The subdivision lines of fractional township No. 3 North, range No. 57 East,

Willamette Meridian, in the State of Oregon, which are represented in the foregoing field notes as having been surveyed by me and under my directions; and I do further solemnly swear that all the corners of said survey have been established and perpetuated in strict accordance with the Manual of Surveying Instructions and the special written instructions of the U. S. Surveyor-General for Oregon, and in the specific manner described in the field notes, and that the foregoing are the true field notes of such survey; and should any fraud be detected, I will suffer the penalty of perjury, under the provisions of an act of Congress approved August 8, 1846.

William E. Campbell

U. S. Deputy Surveyor.

Subscribed by said William E. Campbell, U. S.

Deputy Surveyor, and sworn to before me this twenty eight

day of December, 1900

Alvin E. Lake

County Clerk ex officio

Clerk of the Circuit Court.

399B

Office of U. S. Surveyor-General,

PORTLAND, OREG., *March 28*, 190*1*

The foregoing field notes of the survey of the .....

*Subdivisional of fractional  
Township 3 North Range  
37 East Will. Men Oregon*

executed by *William O. Campbell*  
*U. S. Deputy Surveyor*

under his contract No. *718*, dated .....

*May 1*, 190*0*, having been critically examined,

and the necessary corrections and explanations made, the said field notes and the surveys they describe, are hereby approved.

*Robert A. Habershaw*

U. S. Surveyor-General.