

250 250 B

# Index

Referring to the pages of the field notes.

Town 3 N. Range 36 E. Will. Mer-

14	15	16	17	18	19
6	5	4	3	2	1

12 17

*all of this*

13 10

24 9

25 9

31	32	33	34	35	36
2	2	33	4	5	6

7

Field notes of the survey of  
the exterior lines of Township  
number 3 North of the Base  
Line of Range 36 East of Willamette  
Meridian in the State of Oregon  
by William H. Odell, deputy  
Surveyor under his contract  
No 114 bearing date July  
2<sup>nd</sup> 1866.

Commenced September 3<sup>rd</sup>  
1866 and completed  
September 25<sup>th</sup> 1866.

---

Township 3 North Range 36 East

40.00 Set post corner for 1/4 section <sup>+</sup>350 <sup>+</sup>350  
 from which

A Fir 12 in - dia - bears S 70° East 14 ft  
 no other tree marks  
 dug pit and raised mound  
 as per instructions,

6.00 Summit of ridge course S, W, <sup>+</sup>500 <sup>+</sup>500  
 Bar 21° East =

8.00 Set Bassalt Stone 7x9x24. on <sup>50</sup> 50  
 steep side hill facing the south,  
 This line passes over very  
 broken mountain ridge  
 quite rocky -

East on South boundary  
 of section 36

Bar 20° East

40.00 Set post corner for 1/4 section <sup>+</sup>700  
 on mountain side facing  
 the west, drove charred stake  
 dug pit and raised mound  
 as per instructions

257<sup>9</sup>

Township 3 North Range 36 East

8000 Set post corner for townships 243

+  
100

North Ranges 36 & 37 East section

1. 6. 31. 436, ~~xxxx~~ which on  
a Fir 24 in dia - ~~xxxx~~ was made  
for corner, from which

a Fir 20 in dia - bears S 20° W 21 Mo  
do - do - 18 do - do - do - N 30° W 65 do -  
do - do - 16 do - do - do - N 65° E 40 do -  
no tree near in section 6,

This line passes up the  
mountain the corner is near  
the summit of the Blue Mountain

The last 20, 111 ch through  
timber Fir Larch & Pine  
Undergrowth the same  
with Willow,

September 3<sup>rd</sup> 1866,

North on East boundary  
of section 36,

Bar 21° East,

4000

Set post corner for  $\frac{1}{4}$  section

Township 3 North Range 36 East

on side hill on brink  
of mountain from which

A Fir 20 in dia - bears S 40° E, 21 lbs

do - do - 10 do - do - do - N 10° W, 50 do -

8000 Set post corner for sections 250 250

25, 36, 30 & 31, on east side of ridge

near summit, from which

A Fir 6 in dia - bears N 10° E, 35 lbs

do - do - 8 do - do - do - N 20° W, 56 do -

no tree near in sections 31 & 36

Made Mound of stone as per  
instructions,

This line on the south half  
passes over level land, through  
timber consisting of Fir & Larch  
The north half passes across  
head of canyon on to ridge  
sides of canyon on the  
south timbered,

Township 3 North Range 3 East - <sup>259</sup>

North on East boundary  
of section 25

Bar  $20^{\circ}$  E -

40.00 Set post corner for  $\frac{1}{4}$  section 200  
on steep mountain side on east  
side of ridge from which  
A Pine 36 in dia - bears  $S 2^{\circ}$  E - 100 lbs  
do - do - 8 do - do - do -  $N 6^{\circ}$  E - 50 do -

80.00 Set post corner for sections 300  
24. 25. 19 & 30. in ravine corner  
west, deposited marked  
stone and raised stone mound  
as per instructions.

Land broken & rocky  
timber in the canyons on  
south side, consisting of  
Fir Larch & Pine,

North on East boundary of  
section 24.

Bar  $20^{\circ}$  East

40.00 Set post corner for  $\frac{1}{4}$  section 175

Township 3 North Range 36 East -  
on hill side facing the East  
from which

A Fir 6 in - dia bears South  $65^{\circ}$  0 lbs  
no tree near on west side

59.50 Small creek 3 lbs wide course N W  $\checkmark$  7000  
80.00 Set post corner for sections 13.24,  
18.419 on summit of ridge course  $+500$   $+500$

North West, deposited stone &  
marked stone marked as per  
instructions from which  
A Pine 8 in - dia - bears N  $26^{\circ}$  W, 200 lbs  
do - do - 10 do - do - do - N,  $27^{\circ}$  E, 210 lbs

This line passes across deep  
Canyon on the south side  
through thick timber, North  
side open some grass, soil  
stony,

North on east boundary  
of section 13

Bar  $20^{\circ}$  E -

32.50 Boise City Stage Road course 550

269 71

Township 3 North Range 36 East -

South of West

39,850 Omatilla River course S.W. 6

4,000 Middle of river, Made corner  
for 4-section 60 links south  
of true corner on Fir 8 in-dia-  
on left bank of the river  
from which

A Fir 7 in-dia - bears S 20° W 12 links

do - do - 10 dia do - do N 85° E 21 do -

September 4<sup>th</sup> 1866 -

8000 Set Bassalt Stone 6x8x16 800.

corner for sections 12, 13,

7 & 18, on steep mountain side  
facing the south,

This line passes  
over very broken lands

Timber along the Omatilla  
River Fir Pine & Balsm

The mountain sides on the  
south are bald on the  
north timbered, all  
more or less rocky.

Township 30 North Range 36 East,  
The open lands have fair  
yield of grass.

North on East boundary  
of section 12.

Bar 15° East

4000

Set post corner for  $\frac{1}{4}$  section <sup>400</sup> 400  
on summit of Ridge Course  
S.W. deposited Marked  
Stone and Made Stone  
Mound as per instructions,

8000

Set post corner for sections <sup>100</sup> 100  
1, 12, 6 & 7, on hill side  
facing the East, Made  
Stone Mound as per  
instructions, after deposit-  
ing Marked Stone,

This line crosses up  
mountain side from Amatta  
River some grass on the  
ridges, Soil Stony.

Township 3 North Range 36 East

North on East boundary  
of section 1,

Bar 16° East,

40.00 Set post corner for 1/4 section <sup>50</sup>

from which,

A Larch 10 in. dia bears N 15° W, 32 lbs

do. do. 12 do. do. do. S 35° E 26 do

Bar 20° East -

80.00 Set post corner for Townships

344. North Range 36437

East Sections 1, 6, 31, 36,

from which

A Fir 10 in dia bears N 10° W, 24 lbs

do. do. 8 do. do. do. N 55° E, 20 do,

do. do. 6 do. do. do. S 45° E, 30 do.

do. do. 12 do. do. do. S 3° W, 18 do,

This line passes through  
thick timber, considerable  
of it fallen. Timber Fir and  
Larch. Under growth the  
same with Willow

September 5<sup>th</sup> / 1866,

A list of the names of  
 the persons employed to assist  
 in running measuring or marking  
 the lines and corners described in  
 the foregoing field notes of the  
 Exterior boundaries of Township No  
 3 North of the Base Line of Range 36 East  
 of Willamette Meridian, showing the  
 respective capacities in which  
 they acted.

J. J. Henderson, }  
 John A. Riggs } Chairman  
 P. M. Denney Axeman.

Carroll J. Applegate

William H. Odell, <sup>275</sup>

Deputy surveyor, do solemnly swear that in pursuance of a Contract entered into with E. L. Applegate surveyor of the public lands of the United States in the State of Oregon, bearing date July 2<sup>d</sup> 1866, and in strict conformity to the laws of the United States and the instructions furnished by said Surveyor General, I have faithfully surveyed the Exterior boundaries of Township number 3 North of the Base line of Range 36 East of Willamette Meridian, in the State aforesaid, and do further solemnly swear the foregoing are the true and original field Notes of such survey.

William H. Odell

State of Oregon

County of Lane

} ss. Subscribed, and

Sworn to before me, this 23<sup>d</sup> day of December 1866.

Joel Ware

Notary Public

We hereby certify that we assisted  
 William H. Odell Deputy surveyor, in  
 surveying the exterior boundaries of  
 Townships No 3 North of Ranges No  
 35 & 36 East of Willamette Meridian, also  
 No. 4 North of Ranges 34 & 35 East of  
 Willamette Meridian, and that said  
 exterior boundaries have been in all  
 respects, to the best of our knowledge and  
 belief well and faithfully surveyed and the  
 boundary monuments planted according  
 to the instructions furnished by the Surveyor  
 General.

J J Henderson Chairman  
 J A Trigg Chairman  
 P A. Demney Assessor

State of Oregon }  
 County of Wasatch } 33 Subscribed and  
 Sworn to before me this day  
 of September A. D. 1866.

William Luellen Justice of the Peace

com

278

Surveyor General's Office  
Eugene City January 17 1867

The foregoing field notes of the survey  
of the Exterior boundaries of Township  
No 3 North Range 36 East Will. Mer  
Oregon executed by William H  
Odell. Deputy Surveyor under his  
contract. No 114. bearing date  
July 2nd. 1866 having been critic-  
ally examined, the necessary correc-  
tions and explanations made  
the field notes and the surveys  
they describe are hereby approved

E. L. Applegate

Surveyor General of Oregon

Recd  
to this