

Field notes of the survey of
the exterior lines of Township
number 3 North of the Base
Line of Range 36 East of Willamette
Meridian in the State of Oregon
by William H. Odell, deputy
Surveyor under his contract
No 114 bearing date July
2nd 1866.

Commenced September 3rd
1866 and completed
September 25th 1866.

Township 3 North Range 36 East.

Begin at the South West corner
Thence East on south boundary
of section 31.

17.00 Summit of ridge course N. E. + 200 + 200

40.00 Set Basalt Stone 7x8x15. on steep - 200 - 200.

hillside for 1/4 section corner

53.00 Macham Creek 30ths wide course N. E. 175 175

63.50 do - do - do - do - do - do - S. E.

76.00 do - do - do - do - do - do - N. E.

80.00 Set post corner for sections 31. 32 + 20.

5-46, from which

A Pine 24 in dia - bears S. 50° W. 19 ths

do - do - 16 do - do - do - N. 60° W. 31 do,

do, do - 18 do - do - do - N. 15° E. 30 do -

No tree near in section

5, This line pass over very
broken lands quite rocky,
some pine timber along
Creek Bottom.

East on south boundary
of section 32.

253³
Township 3 North Range 36 East

Bar 21°30' East-

4000 Set post corner for 1/4 Section ⁺ 150
on steep hill side facing the
South west. made stone
mound as per instructions

Bar 20° East-

8000 Set post corner for sections ⁺ 50
32.33.4.45, drove charred
stake and made stone
mound as per instructions

Land broken and
rocky, a very good
grove of timber on
north west 1/4 quarter of
of section 5 T. 2 N. R. 36 E.
Timber small growth
Gir Larch and Pine.

East on south boundary
of section 33.

Bar 20°45' East-

2000 Summit of ridge course N. W. ⁺ 300

Township 3 North Range 36 East

40.00 Set post corner for 14 section 100

in Ravine course N-W
drove charred stake, dug
pits and raised mound as
per instructions

48.00 Summit of ridge course North 725

80.00 Set post corner for sections 33. 250

34. 344 on steep hill side facing
the north, from which

A Fir 10 in-dia bears $N. 38^{\circ} E, 27$ lbs

do - do - 7 do - do - do - $N. 62^{\circ} W, 41$ do

do - do - 10 do - do - do - $S. 43^{\circ} W, 38$ do

do - do - 12 do - do - do - $S. 51^{\circ} E, 25$ do

This line passes over very
rough broken mountain ridges

The last 10.00 chs passed through
thick timber small growth

Fir - Larch & Pine,

East on south boundary
of section 34.

Bar $20^{\circ} 30'$ East

Township 3 North Range 36 East.

2,500	Creek 10 lks wide course North	300
4,000	Set post corner for $\frac{1}{4}$ section on steep hillside facing the West. Above charred stake, dug pit, and raised mound as per instructions	300
4,750	Summit of ridge course North	150
8,000	Set post corner for sections 34, 35, 2 & 3. on steep point of rocks deposited marked stone and raised stone mound as per instructions.	80

This line passes over
broken mountain ridges
timber on most of the
northern slopes.

East on south boundary
of section 35.

Bar 19° East.

5,750	Small creek 6 lks wide course N.W.	75
-------	------------------------------------	----

Township 3 North Range 36 East

40,000 Set post corner for 1/4 section ⁺350 ⁺350
 from which

A Fir 12 in - dia - bears S 70° East 14 ft
 no other tree marks
 dug pit and raised mound
 as per instructions,

6,000 Summit of ridge course S, W, ⁺500 ⁺500
 Bar 21° East =

8,000 Set Bassalt Stone 7x9x24. on ⁺50 ⁺50
 steep side hill facing the south,
 This line passes over very
 broken mountain ridge
 quite rocky -

East on South boundary
 of section 36

Bar 20° East

40,000 Set post corner for 1/4 section ⁺700
 on mountain side facing
 the west, drove charred stake
 dug pit and raised mound
 as per instructions

257⁹

Township 3 North Range 36 East

8000 Set post corner for townships 243

+
100

North Ranges 36 & 37 East section

1. 6. 31. 436, ~~xxxx~~ which on
a Fir 24 in dia - ~~xxxx~~ was made
for corner, from which

a Fir 20 in dia - bears S 20° W 21 Mo
do - do - 18 do - do - do - N 30° W 65 do -
do - do - 16 do - do - do - N 65° E 40 do -
no tree near in section 6,

This line passes up the
mountain the corner is near
the summit of the Blue Mountain

The last 20, 111 chs through
timber Fir Larch & Pine
Undergrowth the same
with Willow,

September 3rd 1866,

North on East boundary
of section 36,

Bar 21° East,

4000

Set post corner for $\frac{1}{4}$ section

A list of the names of the persons employed to assist in running measuring or marking the lines and corners described in the foregoing field notes of the Exterior boundaries of Township No 3 North of the Base Line of Range 36 East of Willamette Meridian, showing the respective capacities in which they acted.

J. J. Henderson, }
 John A. Riggs } Chairman
 P. M. Denney Axeman.

Carroll J. Applegate

William H. Odell, ²⁷⁵

Deputy surveyor, do solemnly swear that in pursuance of a Contract entered into with E. L. Applegate surveyor of the public lands of the United States in the State of Oregon, bearing date July 2^d 1866, and in strict conformity to the laws of the United States and the instructions furnished by said Surveyor General, I have faithfully surveyed the Exterior boundaries of Township number 3 North of the Base line of Range 36 East of Willamette Meridian, in the State aforesaid, and do further solemnly swear the foregoing are the true and original field Notes of such survey.

William H. Odell

State of Oregon

County of Lane

} ss. Subscribed, and

Sworn to before me, this 23^d day of December 1866.

Joel Ware

Notary Public

We hereby certify that we assisted
 William H. Odell Deputy surveyor, in
 surveying the exterior boundaries of
 Townships No 3 North of Ranges No
 35 & 36 East of Willamette Meridian, also
 No. 4 North of Ranges 34 & 35 East of
 Willamette Meridian, and that said
 exterior boundaries have been in all
 respects, to the best of our knowledge and
 belief well and faithfully surveyed and the
 boundary monuments planted according
 to the instructions furnished by the Surveyor
 General.

J J Henderson Chairman
 J A Trigg Chairman
 P A. Demney Assessor

State of Oregon }
 County of Wasatch } 33 Subscribed and
 Sworn to before me this day
 of September A. D. 1866.

William Luellen Justice of the Peace

com

278

Surveyor General's Office
Eugene City January 17 1867

The foregoing field notes of the survey
of the Exterior boundaries of Township
N^o 3 North Range 36 East Will. Mer
Oregon executed by William H
Odell. Deputy Surveyor under his
contract. N^o 114. bearing date
July 2nd. 1866 having been critic-
ally examined, the necessary correc-
tions and explanations made
the field notes and the surveys
they describe are hereby approved

E. I. Applegate

Surveyor General of Oregon

Recd
to his