

FIELD NOTES

Of the survey of the Exterior L

Lines of Tl. 2 N. R. 32 & 33 Q. Tl. 4 N. Rgs. 34 & 35

E & Ts. 3 N. Rs. 33. 34. 35 & 36 Willamette Meridian, Oregon,

as surveyed by Jas. P. Currier & Jas. E. Noland

U. S. Deputy Surveyors under ^{their} his Contract No. Special

dated May 24th, 1887.

Survey commenced, July 27th, 1887.

Survey completed, Sept 10th, 1887.

NAMES AND DUTIES OF ASSISTANTS.

L. J. Wooley, Compassman.

Frank Belsaw, Chainman.

Guy Davis, Chainman.

J. H. Medley, Chainman.

J. S. Medley, Chainman.

Barney Crowder, Axman.

J. R. Hadley, Axman.

, Flagman.

504 PRELIMINARY OATHS OF ASSISTANTS.

We, J. S. Medley, F. H. Medley, Frank Belshaw & Guy Davis

do solemnly swear that we will faithfully execute the duties of Chain Carriers; that we will level the chain over even and uneven ground, and plumb the tally pins, either by sticking or dropping the same; that we will report the true distance to all notable objects, and the true length of all lines that we will assist in measuring, to the best of our skill and ability, and in accordance with the instructions given us in the survey

of the ~~Exterior Lines of T. 2 N. R. 32 & 33 E.~~
~~T 4 N. R. 34 & 35 E.~~ ~~lines of T. 3 N. R. 33.~~
34. 36 & 36 East. Willamette Meridian, Oregon.

J. S. Medley, Chainman.

F. H. Medley, Chainman.

Frank Belshaw, Chainman.

Guy Davis, Chainman.

Subscribed and sworn to before me this 14th

day of June, 1887



James P. Currier,

U. S. Deputy Surveyor.

We, B. B. Crammer and

H. Beatch

, do solemnly
swear that we will well and truly perform the duties of Axmen in the
establishment of corners and other duties, according to instructions
given us, and to the best of our skill and ability, in the survey of the


~~Exterior lines of T. 2 N. R. 32 & 33 E. T. 4 N. R. 34 & 35 E.~~
T. 3 N. R. 33. 34. 35 & 36 E. Willamette Meridian, Oregon.

B. B. Crammer, Axman.

H. Beatch, Axman.

Subscribed and sworn to before me this 14th

day of June, 1887



James P. Currier
U. S. Deputy Surveyor.

80*

Exterior of T. 3 North R. 35 East

Willamette Meridian, Oregon.

Aug. 24th 1887.

Commencing on the line betw. Sps. 3d, R. 35 & 36 E., at corner to Secs 4, 12, 13 & 18, which I rec'd table'd from burning trees, setting a basalt stone 14x12x10 ins - gneiss in the ground, marked, 2 notches on top, 4 notches on edges, from which a pine 24 ins diam bears N. 45° E., dist 42 ft, marked 23d, R. 36 E., S. 7 B. T., a pine 24 ins in diam bears S. 40° E., marked S. 18 B. T., a pine 20 ins in diam bears S. 55° W., dist 28 ft, marked R. 35 E., S. 13 B. T., a pine 20 ins in diam bears N. 40° W., dist 68 ft, marked S. 12 B. T., * hence Don't Trident Det Secs. 13 & 18,

Var 21° E.

* 17.5° Intersect W. R. bdy Set a basalt
stone 14x10x10 ins ^{10 ins in the ground} for Meander Cor
to Secs. 13 & 18, marked M. C. on

Exteriors of T. 3 North R. 35 East

Willamette Meridian, Oregon.

(8093-10 M.)

- On S. face Raised mound of stone
about 1. Pts in prairie cable - 300
40.00 Set a basalt stone 9x8x7 ins 6 ins
in the ground for 1/4 Sec Cor-
marked 1/4 on W. face
From which a pine 24 ins in diam
frans at 50° E dist 22 lks marked
1/4 D. B. T. a pine 10 ins in diam bears
S 83° W. dist 30 lks marked 1/4 D. B. T.
Leave timber + 400
- 49.50 Wagon Road Gravelly
44.30 Gilehouse W. - 20
- 80.00 Set a post 48x4x4 ins 24 ins
in the ground for Cor to Sec
13, 18, 19 & 24 marked, D. 3d, S. 13
on SW, R. 36 E, S. 18 on NE, D. 19 on
SE, R. 35 E, S. 24, etc SW, with
3 notches with 1/2 in edges from
which a pine 18 ins in diam bears
at 80° E. dist 59 lks marked
D. 3d, R. 36 E, S. 18 B. T. a pine 36 ins

87603

Extention of T. 3 North R. 36 East

Willamette Meridian, Oregon.

(8093-10 M.)

From The Cor. To Pps 3 N.
R. 35 & 36 East I run E.
on random S. Idy. of
Pp. 3 N. R. 36 E. at each
40 & 80. chains I set up
1/4 Sec. & Sec. Cor. At 2.
miles & 30 lks. I found
The Cor. To Secs. 92 & 33 1.35
N. of line & From This Cor.
which is a post 40x4x4 ins in a
mound of stone in good order
I run $889^{\circ}30'$ W on true line in
an South boundary of sec. 33
Var 22° E

200 Lnd ch. Course S. W. - 100
7.20 Intersect U. R. Idy 20.00
Ch. S 20W of 37th. Mile
post & Set a post & stone
16x16x4 ins 10 ins in the ground
for Closing Cor to Pps
243 N R. 36 East & Marked

Exteriors of T. 3 North R. 36 East-

Willamette Meridian, Oregon.

U. S. C. C. Raised a stone mound over it - pits impracticable
 15.00 Top of ridge N.W. + 200
 37.00 Gulch Cause N - 400
 40.00 Set a Yerall-stone 10x8x8 ins
 6 ins in the ground for 1/4 sec.
 Cor. Marked 1/4 an ft face.
 Raised a stone mound over it -
 pits impracticable
 50.00 Brook Cause N.W. 2 fms - 200
 62.50 Top. of ridge + 50
 79.50 Gulch Cause N.W. - 100
 80.00 Set a stone 12x10x10 ins on
 a ledge of rock for Cor. To
 secs. 31 & 32 raised a stone
 mound around it, Pits Impracticable 200
 Land Maintained 8,000 chs
 Sait 3rd date
 Scattering pine & fir timber
 Heavy under brush in places

FINAL OATHS FOR SURVEYS.

A list of the names of the individuals employed by Jas. P. Linnin
Jas. E. Poland, U. S. Deputy Surveyor, to assist in
running, measuring, and marking the lines and corners described in the
foregoing field notes of the survey of the Exterior lines of
J. 2 A. R. 32 + 33 E. lines of J. 4 A. R. 34 + 35 E.
& J. 3 A. R. 33. 34. 35 + 36 E., Willamette Meridian, Oregon,
showing the respective capacities in which they acted:

L. F. Woolley, Compassman.

Frank Belshaw, Chainman.

Guy Davis, Chainman.

H. H. Medley, Chainman.

J. D. Medley, Chainman.

Barney Croamer, Axman.

J. R. Hadley, Axman.

, Flagman.

FINAL OATHS OF ASSISTANTS.

We hereby certify that we assisted Jas. P. Linnin
Jas. E. Poland, U. S. Deputy Surveyor, in surveying
all those parts or portions of the Exterior lines of
J. 2 A. R. 32 + 33 E. J. 4 A. of R. 34 + 35 E. &
J. 3 A. R. 33. 34. 35 + 36 E., Willamette Meridian, Oregon,
as represented in the foregoing field notes as having been surveyed by
him and under his direction; and that said survey has been in all respects,
to the best of our knowledge and belief, well and faithfully surveyed,
and the corner monuments established, according to the instructions
furnished by the U. S. Surveyor General of Oregon.

L. F. Woolley, Compassman.

J. S. Medley, Chainman.

W. H. Medley, Chainman.

Frank Belshaw, Chainman.

Guy Davis, Chainman.

B. B. Croamer, Axman.

J. R. Hadley, Axman.

, Flagman.

Subscribed and sworn to before me this 30th day of

Sept

, 1887

[SEAL.]

James P. Linnin, U. S. Deputy Surveyor

FINAL OATH OF DEPUTY SURVEYOR.

I, James P. Leurin & Jas E. Poland, United States Deputy Surveyor, do solemnly swear that in pursuance of instructions

received from Douglas H. Taylor, U. S.

Surveyor General for Oregon, bearing date of the 13th

day of May, 1887, I have well, faithfully, and truly, in my own proper person, and in strict conformity with the instructions furnished by the U. S. Surveyor General for Oregon, the Surveying Manual, and the laws of the United States, surveying all

those parts or portions of the Exterior lines of T. 2 N. R. 32 W. 33

E. C. 44 R. 34 & 36 E. & T. 34 R. 33 34. 36 & 36 E.

Willamette Meridian, in the State of Oregon, as are represented in the foregoing field notes as having been surveyed by me and under my directions; and I do further solemnly swear that all the corners of said survey have been established and perpetuated in strict accordance with the Surveying Manual, printed instructions, the special written instructions of the U. S. Surveyor General for Oregon, and in the specific manner described in the field notes, and that the foregoing are the *true* field notes of such survey, and should any fraud be detected I will suffer the penalty of perjury under the provisions of an act of Congress approved August 8, 1846.

James P. Leurin James E. Poland
U. S. Deputy Surveyor.

Subscribed and sworn to before me this fifteenth
day of February, 1888.

Almondecock
Notary Public
for Oregon

Office of U. S. Surveyor General,

Portland, Oregon, June 19th, 1888.

foregoing
The following Field Notes of the Survey of the
Exterior lines of T. 2 N Rgs.
32 & 33 E. T. 4 N Rgs 34 & 35 E
and T. 3 N. Rgs 33 34 35 & 36 East
Will May Or.
executed by James J. Conin and James E. Nolan
Special Joint U.S. Deft. Surveyors.
under his Contract No. _____, dated May

4th, 1887, having been critically examined,
the necessary corrections and explanations made, the
said Field Notes and the survey they describe, are
hereby approved.

Douglas W. Taylor -
Surveyor General.