

FIELD NOTES

281

Of the survey of the Meander

Lines of The Wild Horse Creek in T. 2 N.

³³ R. 32 E. 1. 3 N. R. 33 34 35 36 E, Willamette Meridian, Oregon,

as surveyed by James P. Currin

U. S. Deputy Surveyor, under his Contract No. Special

dated May 4th, 1887

Survey commenced, Sept 10th, 1887

Survey completed, Sept 17th, 1887

NAMES AND DUTIES OF ASSISTANTS.

....., Compassman.

J. S. Medley....., Chainman.

W. H. Medley....., Chainman.

....., Chainman.

....., Chainman.

Frank Roons....., Axman.

....., Axman.

....., Flagman.

PRELIMINARY OATHS OF ASSISTANTS.

We,

282

J. S. Medley & W. H. Medley

do solemnly swear that we will faithfully execute the duties of Chain Carriers; that we will level the chain over even and uneven ground, and plumb the tally pins, either by sticking or dropping the same; that we will report the true distance to all notable objects, and the true length of all lines that we will assist in measuring, to the best of our skill and ability, and in accordance with the instructions given us in the survey

of the Meander Lines of The Wild Horse Creek.

lines of

Willamette Meridian, Oregon.

J. S. Medley, Chainman.
W. H. Medley, Chainman.
[Signature], Chainman.
[Signature], Chainman.

Subscribed and sworn to before me this

10th

day of

Sept.

, 1887

[SEAL.]

James P. Currin
U.S. Deputy Surveyor

We,

J. Frank Koons

and

do solemnly swear that we will well and truly perform the duties of Axmen in the establishment of corners and other duties, according to instructions given us, and to the best of our skill and ability, in the survey of the

Meander of The Wild Horse Creek.

Willamette Meridian, Oregon.

J. Frank Koons, Axman.

, Axman.

Subscribed and sworn to before me this

10th


day of

Sept.

, 1887

[SEAL.]

James P. Currin
U.S. Deputy Surveyor



Meander of T. Wild R. Morse

Willamette Meridian, Oregon.

Cor to Secs 12 x 13

Thence in Sec 13

S 61° E 1.95 chs.

S 36 1/2° E 430 "

S 61 3/4° E 10700 "

S 50 1/2° E 620 "

S 49 1/2° E 400 " To Meander cor.

To Tps 3 N Rs 35 & 36 E

Thence in Sec 18 Tp. 3 N R 36 E

S 16 1/4° E 150 chs Del- 2 yth Mile

Cor. A Stone 20 x 10 x 8 ins W side

27 M. on N & N. R. on W face.

Raised stone. Meander ~~over it~~

~~Pits impracticable~~

Lownd Mms on each side

Soil rocky 5th gate

Gr & Jam orack timber

course under brush 4000 chs

Sept. 16th 1887

Wander of T. Wild R. Horse

Willamette Meridian, Oregon.

(8093-10 M.)

Fence on 28th Mile

Var 21°30'E

S 16 1/4° E 500 chs.

S 40 1/2° E 4,500 "

S 35° E 4,400 "

S 20° E 2,600 "

S 40 1/2° E 5,400 "

S 53° E 11,500 "

S 82° E 6,900 "

S 7 1/2° E 3,900 "

N 72 1/2° E 3,300 " Set a basal-

stone 20x16x12 ins 15 ins in

The ground for 1/2 Mile on

Worked 1/2 M. on 20x20 R. on

S faces. from which a fir

6 ins in diam to east 36

chs. Mpd 1/2 M. N. R. 129.

Raised a stone mound

over it. Pit in practiceable

S 82° E 6,000 chs.

N 79° E 20,000 "

Mander of T. Wild R. Horse
Willamette Meridian, Oregon.

A 72 1/2° E 9.26 chs To Mander
Cor. To Secs 17 + 18

Thence in Sec. 17

A 72 1/2° E .74 chs Set a stone
15 ins in the ground.
20 x 12 x 12 ins for 28th Mile

Cor. Marked 28th Mile N + N. Run

S. Raised a stone mound over it.
Pits in practicable.
Land Mountainous

Soil 3rd rate

Pine fir + Jam or oak timber
on S side of corner 80.00 chs
open on North

*50

340

Meander of T. Wild R. Horse

Willamette Meridian, Oregon.

(8093-10 M.)

Fence on 29th Mile
Var 15° E

N 37 1/4° E 7.00 chs

N 65° E 12.00 "

N 78 1/2° E 8.00 ..

N 56° E 4.50 "

N 69° E 5.50 "

N 15° E 3.50 " Set a Gas-

alt-stone 12 x 10 x 10 ins for

1/2 M cor. Marked 1/2 M on

W & N. R on E faces

Raised a stone mound
over it. Pits impracticable
from which

a fir 5 ins. h. at 80° N 15 lbs

N 15° E 5.00 chs

N 62 1/4° E 6.52 " to Meander

cor to Secs. 8 & 17

Fence in Sec 8

N 8 1/2° W 3.98 chs

N 70° E 5.70 "

N 14 1/2° W 8.10 "

Mander of T. Wild R. Horse
Willamette Meridian, Oregon.

N 8 3/4 E 5.50 ch

N 5 1/4 E 6.20 " Sel-a pas all-
stone 12x10x10 is 8 ins in the ground
for 29th wire stone &

Marked 29 M on W. & N.R. and

raised a stone mound over it

~~its impracticable~~
Land Mammarians

Common not-so deep-

Soil 2nd rate

Pine fir Tamarack &
Spruce timber with clust
under brush of various

tricks 8000 ch

Placer of T. Wild R. Morse
Willamette Meridian, Oregon.

(8093-10 M.)

Thence on 30th Mile
Var 20°E

N 67³/₄°E 19.00 chs.

N 54¹/₂°E 18.00 "

N 32¹/₄°E 3.00 " set-a

post-48x4x4 ins 24 ins in

The ground for 1/2 Mile

post-marked 1/2 M on N.

& U.R. on S. Faces

From which a white fir 12

ins in diam to S 45°W dist

18 chs. White fir 10 ins to N

35°W dist-25 chs. marked

1/2 M. U.R. B.D.

N 49°30'E 6.97 chs To Man-

der cor to Secs. 8 & 9

Thence in Sec. 9

N 59¹/₂°E 7.03 chs

S 77¹/₄°E 6.00 "

S 49¹/₄°E 5.10 "

S 68°E 3.90 "

Remder of T. Wild R. Horse 343^b 3.
Willamette Meridian, Oregon.

S 71° E 6.70 cho

S 41° E 6.90 " Set-a post-
48x44x4 ins 24 ins in the ground
for 30th Mile post - Mkd 30
M on W & N. R. on S faces
from which a white fir 10
ins to S 5° E 43 lks. a white fir
12 ins to S 77° W 5.7 lks.

Each worked 30 M. N. R. B. I.
Creek runs in flat-can-
on. Land rolling on each
side. Soil 2nd rate
Pine fir & Jam crack timber
dense underbrush 65.00 ch.

54344

Remainder of T. Field R. Horse

Willamette Meridian, Oregon.

(8093-10 M.)

Thence on 2¹/₂ Mile
Var $19\frac{1}{2}^{\circ}E$

S $40\frac{1}{4}^{\circ}E$ 5.00 chs.

S $58^{\circ}E$ 12.00 "

S $66\frac{1}{2}^{\circ}E$ 2.50 "

S $75\frac{3}{4}^{\circ}E$ 12.00 "

N $83^{\circ}E$ 7.00 "

S $64^{\circ}E$ 1.50 " Set a

post - 48 x 4 x 4 ins 24 ins

in the ground for $\frac{1}{2}$ M

post - Nhd $\frac{1}{2}$ M on W & N.R

on S. face

from which a fir 12 ins

in diam to S $43^{\circ}N$ dist - 36

chs. A fir 4 ins N $78^{\circ}E$

dist 26 chs Nhd $\frac{1}{2}$ M

N.R. B.D.

S $64^{\circ}E$ 9.00 chs

S $33\frac{3}{4}^{\circ}E$ 5.00 "

S $28^{\circ}E$ 3.00 "

S $55^{\circ}E$ 4.57 " To corner

Meander of T. Wild R. Borse 345
Willamette Meridian, Oregon.

To Secs. 9 & 10
Fence in Sec 10
S 5 9/4 E 3.42 ch
S 22 3/4 E 5.90 "
S 39 1/2 E 2.60 "
S 74 1/2 E 2.80 "

S 83 1/2 E 3.71 " Set a
Yasael stone 10 x 10 x 10 ins
6 ins in the ground for 31 1/4
Mile stone Mkd 31 Man W.
N. R. on S. from which
a fir 4 ins S 34 lks a fir
14 ins in diam to S 15 1/2
dist 54 lks. Marked 31 M
N. R. B. D

Land rolling back side
Soil 2nd rate
Good Pine fir & Fir
ack timber & dense under-
brush along creek 80.00 ch

66

346

Meander of T. Wild R. Horse

Willamette Meridian, Oregon.

(8093-10 M.)

Thence on 32nd Mile

Var 20° E

S 83 1/2° E 7.70 chs

S 62 1/2° E 3.80 "

S. 86° E 6.24 " To Me-

ander cr. To Secs. 10 & 15

Thence in Sec 15:

S. 69 1/2° E 1.61 chs. To Dept-

Woody's 33rd Mile post-

Which I had repaired as

described in Survey of Bay
of Reservation

Total distance from
Initial point to source of
Wild Horse 3 1/4 Miles & 19.35 chs

Dense underbrush 19.35 chains

Sept. 17th 1887

A list of the names of the individuals employed by _____

360 *James P. Currier*, U. S. Deputy Surveyor, to assist in running, measuring, and marking the lines and corners described in the foregoing field notes of the survey of the *Meander* lines of *The Wild Horse Creek* Willamette Meridian, Oregon, showing the respective capacities in which they acted:


- _____, Compassman.
- J. S. Medley*, Chainman.
- W. H. Medley*, Chainman.
- _____, Chainman.
- _____, Chainman.
- Frank Hoons*, Axman.
- _____, Axman.
- _____, Flagman.

FINAL OATHS OF ASSISTANTS.

We hereby certify that we assisted *James P. Currier*, U. S. Deputy Surveyor, in surveying all those parts or portions of the *Meander* lines of *The Wild Horse Creek* Willamette Meridian, Oregon, as represented in the foregoing field notes as having been surveyed by him and under his direction; and that said survey has been in all respects, to the best of our knowledge and belief, well and faithfully surveyed, and the corner monuments established, according to the instructions furnished by the U. S. Surveyor General of Oregon.

- _____, Compassman.
- J. S. Medley*, Chainman.
- W. H. Medley*, Chainman.
- W. H. Medley*, Chainman.
- _____, Chainman.
- Frank Hoons*, Axman.
- _____, Axman.
- _____, Flagman.

Subscribed and sworn to before me this *17th* day of

Sept., 188*7*
 *James P. Currier*
 U. S. Deputy Surveyor

FINAL OATH OF DEPUTY SURVEYOR.

I, James P. Currier, United States
 Deputy Surveyor, do solemnly swear that in pursuance of instructions
 received from Douglas H. Taylor, U. S.
 Surveyor General for Oregon, bearing date of the 13th
 day of May, 1887, I have well, faithfully,
 and truly, in my own proper person, and in strict conformity with the
 instructions furnished by the U. S. Surveyor General for Oregon, the
 Surveying Manual, and the laws of the United States, surveying all
 those parts or portions of The meander
of the Wild Horse Creek
 Willamette Meridian, in the State of Oregon, as are represented in the
 foregoing field notes as having been surveyed by me and under my
 directions; and I do further solemnly swear that all the corners of said
 survey have been established and perpetuated in strict accordance with
 the Surveying Manual, printed instructions, the special written instruc-
 tions of the U. S. Surveyor General for Oregon, and in the specific man-
 ner described in the field notes, and that the foregoing are the *true* field
 notes of such survey, and should any fraud be detected I will suffer the
 penalty of perjury under the provisions of an act of Congress approved
 August 8, 1846.

James P. Currier

U. S. Deputy Surveyor.

Subscribed and sworn to before me this Fifteenth
 day of February, 1888.

Alvord
Notary Public
for Oregon

Office of U. S. Surveyor General,

Portland, Oregon, June 28, 1888

The following ^{foregoing} Field Notes of the Survey of theMeander lines of the
Wild Horse Creek.executed by James J. Currier U.S.
Joint Special U.S. Dept Surveyors
under his Contract No. —, dated May
4th, 1887, having been critically examined,the necessary corrections and explanations made, the
said Field Notes and the survey they describe, are
hereby approved.Douglas W. Taylor
Surveyor General.