

FIELD NOTES

583

Of the survey of the Subdivisional & Allotment

Lines of T. 3. N. R. 36 E

Willamette Meridian,

Oregon, as surveyed by James P. Currier

U. S. Deputy Surveyor, under his Contract No. 537

dated March 5th 1889

Survey commenced, June 7th 1889

Survey completed, June 8th 1889

NAMES AND DUTIES OF ASSISTANTS.

....., Compassman.

....., Chainman.

....., Chainman.

J. B. Laramore, Chainman.

J. L. Brown, Chainman.

Wm. Stone, Axeman.

R. E. Long, Axeman.

....., Flagman.

PRELIMINARY OATHS OF ASSISTANTS.

We, J. R. Saramore
& J. L. Brown

do solemnly swear that we will faithfully execute the duties of Chain Carriers, that we will level the chain over even and uneven ground, and plumb the tally pins, either by sticking or dropping the same; that we will report the true distance to all notable objects, and the true length of all lines that we will assist in measuring, to the best of our skill and ability, and in accordance with the instructions given us in

the survey of the Subdivisional and
Allotment lines of T. 3 N. R.
36 E. Willamette Meridian, Oregon.

J. R. Saramore, Chainman.
J. L. Brown, Chainman.
_____, Chainman.
_____, Chainman.

Subscribed and sworn to before me, this 7th
day of June, 1889

[SEAL.]

Thos Fitz Gerald
Notary Public

We, Esmer Stone and
R. E. Long, do solemnly swear

that we will well and truly perform the duties of Axemen in the establishment of corners and other duties, according to instructions given us, and to the best of our skill and ability, in the survey of the

Subdivisional and
Allotment lines T. 3 N. R. 36 E.
Willamette Meridian, Oregon.

E. M. Stone, Axeman.
R. E. Long, Axeman.

Subscribed and sworn to before me, this 7th
day of June, 1889

[SEAL.]

Thos Fitz Gerald
Notary Public

INDEX

Referring the Lines to the Pages of the Field Notes.

T. *3 North* R. *36 East* Will. Mer.

6	5	4	3	2	1
7	8	9	10	11	12
18	17	16	15	14	13
18	20	21	22	23	24
30	29	28	27	26	25
31	32	33	34	35	36

Handwritten notes in red ink:
 4
 5
 4
 1
 22
 21
 18
 19
 16
 14

Meanders of _____ Pages _____ to _____

Meanders of _____ Pages _____ to _____

Allotment

594
Subdivision of T. 3 North R. 36 East

Willamette Meridian, Oregon.

Sec 18

(8093-10 M.)

From the $\frac{1}{4}$ Sec corner betw.
Secs 13 & 18 on W. ldy of Sp.
which is a basalt stone
9 x 8 x 7 ins 6. ins in the
ground marked $\frac{1}{4}$ on W.
face from which

A pine 24 ins diam br N 50° E
22 lbs dist marked $\frac{1}{4}$ S.B.S.

A pine 16. ins diam br S 83° W
30 lbs marked $\frac{1}{4}$ S.B.S.

I run

South on true line between
Secs. 13 and 18

Var 21° E

950 Road corner E. & W.
1000 Set basalt stone 9 x 8 x 7 ins
6 ins in the ground for $\frac{1}{32}$ Sec
corner marked $\frac{1}{32}$ on W. face
dug pits 18 x 18 x 12 ins N & S
of stone 5 1/2 ft dist and
raised a mound of

Subdivision of T. 3 North R. 36 East
Willamette Meridian, Oregon.

See 18

earth $1\frac{1}{2}$ ft high $3\frac{1}{2}$ ft
base alongside

2000 Set stake 9 + 8 + 7 in 6 in in
the ground for $\frac{1}{16}$ See corner, marked
 $\frac{1}{32}$ in N.E. &
 $\frac{1}{16}$ in S.E. face; dug pits 18 + 18 + 12
in N. & S of stake $3\frac{1}{2}$ ft dirt,
raised mound of earth $1\frac{1}{2}$ ft high
 $3\frac{1}{2}$ ft base over it.

Land on Summit of Mt.
Soil 1st rate, good grain

From the $\frac{1}{32}$ See corner 10 ch
S. of $\frac{1}{4}$ See corner between
Sees. 13 + 18.

From
S 89° 28' E. in tree
line in See 18.

Var 21° E.

1500 Enter brush and descend

1925 A pine, 36 in diam which
I marked
 $\frac{1}{32}$ S. on N. face for $\frac{1}{32}$ See
corner

Allotment

11
001

Subdivision of T. 3 North R. 36 East
Willamette Meridian, Oregon.

Sec 19

From the corner to Secs. 13-18
19 and 24. on the West edge
of Township
I run

South on true line between
Secs 19 + 24.

Var $18^{\circ} 45' E$.

1000 Set post 3 ft long 3 ins square
with charred stake 12 ins
in the ground, for $\frac{1}{32}$ Sec
corner marked $\frac{1}{32}$ S on W face
dug pits 18 x 18 x 12 ins N & S
of post 5 $\frac{1}{2}$ ft dia and raised
a mound of earth 1 $\frac{1}{2}$ ft
high 3 $\frac{1}{2}$ ft base around post

2000 Set post 3 ft long 3 ins square
with marked stem 12 ins
in the ground for $\frac{1}{16}$ $\frac{1}{32}$ Sec corner
marked $\frac{1}{32}$ S. on W. face
+ $\frac{1}{16}$ on S. face — — —
dug pits 18 x 18 x 12 ins

602

Subdivision of T. 3 North R. 36. East
Willamette Meridian, Oregon.

See 19

(8093-10 M.)

N. & S. of post 5 1/2 ft dirt
and raised mound of earth
1 1/2 ft high 3 1/2 ft base
around post

3000 Set basalt stone 12 x 10 x 4.

ins 8 ins in the ground
for 1/32 See corner marked
1/32 on W face dug pits
18 x 18 x 12 ins N. & S. of stone
5 1/2 ft dirt and raised
mound of earth 1 1/2 ft high
3 1/2 ft base over it.

4000

Line through Timber
Intersect the 1/4 See corner
which is a basalt stone
12 x 10 x 8 ins 8 ins in the
ground marked 1/4 on W. face
pits 18 x 18 x 12 ins N. & S. of
stone 5 1/2 ft dirt and mound
of earth 1 1/2 ft high 3 1/2 ft
base alongside

Allotment

Subdivision of T. 3 North R. 36 East
 Willamette Meridian, Oregon.

See 19.

- over rounded summit N. 9.
- 50.00 Set basalt stone 9 + 8 + 7 ins
 6 ins in the ground for $\frac{1}{32}$
 See corner marked $\frac{1}{32}$ on W.
 face, dug pits 18 + 18 + 12 ins
 N. 9 of stone 5 $\frac{1}{4}$ ft dirt
 and raised mound of earth
 1 $\frac{1}{2}$ ft high 3 $\frac{1}{4}$ ft base over it.
- 52.50 Gulch corner W. - 50
- 60.00 Set basalt stone 12 + 12 + 6 ins
 8 ins in the ground for $\frac{1}{16}$ See
 corner marked $\frac{1}{16}$ on W. face
 dug pits 18 + 18 + 12 ins N. 9.
 of stone 5 $\frac{1}{4}$ ft dirt, raised
 a mound of earth 1 $\frac{1}{2}$ ft
 high 3 $\frac{1}{4}$ ft base over it.
- 80.00 The corner to Secs. 19-24
 25 + 30 which is a basalt
 stone 12 + 10 + 8 ins 8 ins in
 the ground marked 4 notches

Allotment

Subdivision of T. 3 North R. 36 East
Willamette Meridian, Oregon.

Sec 19

(8093-10 M.)

on N. & 2 notches on the
South edges & pits 18 x 18 x 12
ins in each sec 5 1/2 ft dist
& mound of earth 2 ft high
4 1/2 ft bar along side

Land rolling

Soil 1st rate but rocky in places

Timber in Gulches

Good grass and sunflowers

From the corner to Sec.

19-24-25+30 on the W

edge of Tp.

From

East on random line

between Secs 19 & 30

Var 19th E.

Setting temporary 1/6 Sec on

at 19.20 chains about at

39.80 Intersect the 1/4 Sec corner
between Secs 19 & 30

FINAL OATHS FOR SURVEYS.

A list of the names of the individuals employed by James P. Currier, U. S. Deputy Surveyor, to assist in running, measuring and marking the lines and corners described in the foregoing field notes of the survey of the subdivisional & allotment lines of T. 3 N. R. 36 E. Willamette Meridian, Oregon, showing the respective capacities in which they acted:

- , **Compassman.**
- J. P. Saramore, **Chainman.**
- J. L. Brown, **Chainman.**
- , **Chainman.**
- , **Chainman.**
- C. M. Stone, **Axeman.**
- R. E. Long, **Axeman.**
- , **Flagman.**

FINAL OATHS OF ASSISTANTS.

We hereby certify that we assisted James Pleurvie U. S. Deputy Surveyor, in surveying all those parts or portions of the subdivisional and allotment lines of T. 3 N. R. 36 E. Willamette Meridian, Oregon, as are represented in the foregoing field notes as having been surveyed by him and under his direction; and that said survey has been in all respects, to the best of our knowledge and belief, well and faithfully surveyed, and the corner monuments established, according to the instructions furnished by the U. S. Surveyor General of Oregon.

- , **Compassman.**
- J. P. Saramore, **Chainman.**
- J. L. Brown, **Chainman.**
- , **Chainman.**
- , **Chainman.**
- C. M. Stone, **Axeman.**
- R. E. Long, **Axeman.**
- , **Flagman.**

Subscribed and sworn to before me, this 2nd day of

[SEAL.] July 9 1889
Thos. H. Eberald
 Notary Public

FINAL OATH OF DEPUTY SURVEYOR.

I, James P. Currier
United States Deputy Surveyor, do solemnly swear that in pursuance of
instructions received from Douglas W. Taylor
U. S. Surveyor General for Oregon, bearing date of the 19th

day of March 1889, I have well, faith-
fully and truly, in my own proper person, and in strict conformity with
the instructions furnished by the U. S. Surveyor General for Oregon, the
Surveying Manual, and the laws of the United States, surveying all those

parts or portions of subdivisional and
lot lines of T. 3 N. R. 36 E

Willamette Meridian, in the State of Oregon, as are represented in the
foregoing field notes as having been surveyed by me and under my direc-
tions; and I do further solemnly swear that all the corners of said survey
have been established and perpetuated in strict accordance with the Sur-
veying Manual, printed instructions, the special written instructions of
the U. S. Surveyor General for Oregon, and in the specific manner de-
scribed in the field notes, and that the foregoing are the *true* field notes of
such survey, and should any fraud be detected I will suffer the penalty of
perjury under the provisions of an Act of Congress approved August 8,
1846.

James P. Currier
U. S. Deputy Surveyor.

Subscribed and sworn to before me, this 2nd
day of July 1889

Thos FitzGerald
Notary Public

Office U. S. Surveyor General,

Portland, Oregon, *Sept 14th* 188*9*

foregoing
The following Field Notes of the Survey of the

Subdivision and Allotment

Lines of Township 3 North
Range 36 East Will Mer Oregon

executed by

James J. Curran
U.S. Dept Survey

under his Contract No. *537*, dated

March 5 188*9* having been critically examined, the

necessary corrections and explanations made, the said Field Notes

and the survey they describe, are hereby approved.

Douglas W. Taylor

Surveyor General.