

Township 3 North Range 35 East

chs East on South boundary of
Section 35.

N. 20°30' E.

4000 Setpost and made Stone mound
for $\frac{1}{4}$ Sec. cor.

8000 Set. Stone 17 + 14 + 12 for cor. to
Secs. 35, 36, 1 + 2.

Land hilly, Soil 2^d rate.

East on South boundary of
Sec. 36.

N. 21° E.

15000 Brook, 12 chs, flows North. 100.

40000 Setpost and made mound of
Earth for $\frac{1}{4}$ Sec. corner.

8000 Setpost and made mound
of Earth for corner to Secs
2 + 3 North, Ranges 35 + 36
East of the Willamette
Meridian.

Land hilly, Soil 2^d rate.

of the Willamette Meridian. 5,
7

Chs. North on East boundary of Sec.
36

Var. $20^{\circ}30'$ East

40.00 Set post and made Stone mound
for $\frac{1}{4}$ Sec. cor.

56.40 Old Stage Road course E + N.

67.50 Umatilla river. 150 lks. flows N.

80.00 Set Stone. 16 + 14 + 9 for cor. to
Sections. 30, 31, 35 + 36

Land broken. Soil Stony. Good grass

North on East. Boundary of Sec. 25
 $N. 20^{\circ} E.$

40.00 Set Stone 16 + 14 + 9 for $\frac{1}{4}$ Sec. cor.

80.00 Set post and made mound
of Stone for cor. to Secs. 24, 25,
19 + 30.

Land rolling. Soil 2^d rate.
Good. Grass

Township 3 North Range 35 East

ch North on East Boundary of
Sec. 24.

N. $20^{\circ}31'$ E.

40.00 Set Stone 14 + 12 + 10 for $\frac{1}{4}$ S cor.

80.00 Set Stone 18 + 16 + 12 for cor. to

Secs. 24, 13, 18 + 19

Land slightly broken. Soil
Good 2d rate. Some pine timber

North on East boundary of
Sec. 13.

N. 21° E.

40.00 Support and made mound
of stone for $\frac{1}{4}$ Sec. cor.

59.50 Intersected Wild Horse cr
Northern boundary of Reser-
vation.

Land Broken. Some Pine timber.
Good Grass.

October, 17th, 1871.

24
Township

Range

U. S. Surveyor General's Office
Oregon City June 21st 1872

The foregoing field notes of the survey of Ex-
termin lines of T 3 N. R 35 E ~~#~~ and
T 21 N. Ranges 34th and 35 East Will
Mer and the Subdivisional lines
of T 4 N Rqs 34th and 35 E Will
Mer Oregon executed by J. B.
Moody deputy Surveyor under con-
tract No 164 bearing date Oct
24th 1871 having been critically
examined the necessary cor-
rections and explanations
made the said field notes and
the surveys they describe are
herby approved

W. H. Bell
Surveyor

" I, Genas F. Moody, having been appointed a deputy Surveyor of the lands of the United States in Oregon, do solemnly swear that I will well and faithfully, and to the best of my skill and ability execute the duties confided to me pursuant to a contract with W. H. Odell, Surveyor General of public lands in Oregon, bearing date the 4th day of October 1871, according to the laws of the United States and the instructions received from the said Surveyor General.

G. F. Moody

Sworn and Subscribed before me
this 14th day of October 1871
W. Davenport
U.S. Comm^r Dist of Oregon

J. J. Kent, do solemnly swear that I will faithfully execute the duties of chain carrier; that I will level the chain upon uneven ground, and plumb the tally pins, whether by striking or dropping the same; that I will report the true distances to all notable objects, and the true length of all lines that I assist in measuring, to the best of my skill and ability.

J. J. Kent

Sworn and Subscribed before me
 This 14th day of October 1871
 W. Davenport
 U.S. Commr. Dist. of Oregon.

I. O. Hathaway do solemnly
swear that I will well and truly
perform the duties of Axeman
according to the instructions given
me, and to the best of my skill and
ability

O Hathaway

Sworn and Subscribed before me
This 14th day of October 1871

M. Davenport
U.S. Commr. Dist. of Oregon.

I, Geo. W. Renne, do
 solemnly swear that I will faithfully
 execute the duties of chain carrier; that
 I will level the chain upon uneven
 ground, and plumb the tally pins,
 whether by striking or dropping the
 same; that I will report the true
 distances to all notable objects, and
 the true length of lines that I assist
 in measuring, to the best of my skill
 and ability.

Geo. W. Renne

Sworn and Subscribed before me
 this 14th day of October 1871
 W. Davenport
 U.S. Comm. Dist. of Oregon

I Edward Gariopy, do solemnly swear that I will well and truly perform the duties of Axeman, according to the instructions given me, and to the best of my skill and ability.

Edward Gariopy

Sworn & Subscribed before me
 This 14th day of October 1871
 W. Davenport
 U.S. Commr. Dist. of Oregon.