

## FIELD NOTES

Of the survey of the *Exterior boundary*  
 Lines of Townships *3 South of Ranges*  
*30 and 31 East Meridian, Oregon.*

Executed by *George S. Pershin*  
 U. S. Deputy Surveyor, under his Contract  
 No. *304* dated *Sept 19<sup>th</sup> 1878*

List of the names of the persons employed to assist in running, measuring and marking the lines of the foregoing survey.

*Herman D. Gradon* Chainman.

*Corrington Newell* Chainman.

..... Chainman.

..... Axeman.

..... Axeman.

..... Compassman.

..... Flagman.

*Errors in S. ldy of T. 39 R 30 E*  
*see page 5 of Cont. in Cont 332*

PRELIMINARY OATHS OF ASSISTANTS.

We, *Hermow D Gradon* and  
*Corrington Newell*

do solemnly swear that we will faithfully execute the duties of Chain Carriers, that we will level the chain upon uneven ground, and plumb the tally pins, whether by sticking or dropping the same; that we will report the true distance to all notable objects, and the true length of all lines, that we assist in measuring, to the best of our skill and ability.

*Hermow D. Gradon* Chainman.  
*Corrington Newell* Chainman.

Chainman.

Subscribed and sworn to before me, this *28<sup>th</sup>*

day of *October* 187*8*

*S G Lightfoot*  
*J. P.*

We, ..... and

do solemnly swear that we will well and truly perform the duties for which we have been severally employed according to instructions and to the best of our skill and ability.

Subscribed and sworn to before me, this.....

day of..... 187

# INDEX.

Referring the lines to the pages of the field notes.

Town. *3 South* Range *31 East* Willamette Meridian.

<i>18</i>	6	5	4	3	2	1	<i>28</i>	
<i>19</i>	7	8	9	10	11	12	<i>29</i>	
<i>20</i>	18	17	16	15	14	13	<i>30</i>	<i>13</i>
<i>21</i>	19	20	21	22	23	24	<i>31</i>	<i>12</i>
<i>22</i>	30	29	28	27	26	25	<i>32</i>	<i>13</i>
<i>23</i>	31	32	33	34	35	36	<i>33</i>	<i>24</i>
	<i>31</i>	<i>32</i>	<i>33</i>	<i>34</i>	<i>35</i>	<i>36</i>		<i>25</i>

*T. 3. S. R. 30 E. W. Mer.*

<i>31</i>	<i>32</i>	<i>33</i>	<i>34</i>	<i>35</i>	<i>36</i>	<i>3</i>
<i>10</i>	<i>11</i>	<i>12</i>	<i>13</i>	<i>14</i>	<i>15</i>	

Exteriors

362<sup>8</sup>

Subdivisions of Township No. 3 South Range 30  
East Willamette Meridian, Oregon.

South along the East Boundary of Sec. 36

<sup>40.00</sup> Pa.  $14^{\circ} 15'$  East

4000 Set Stone  $16 \times 10 \times 7$  on small

<sup>80.00</sup> flat for  $\frac{1}{4}$  sec. cor

8000 Set Stone  $22 \times 12 \times 6$  in Sag - 50

near shallow ravine for  
corner to Townships 3 and 4

South ranges 30 and 30 $\frac{1}{2}$

East Willamette Meridian

A Pine 48 in. diam. bis S.  $60^{\circ}$  E. 352 lbs. dist.

" " 30 " " S  $24^{\circ}$  W. 153 " "

No trees on N. side

built mound of stone at corner

Land: Surface irregular and  
broken; soil 3<sup>rd</sup> & 2<sup>nd</sup> rate

Some Pine & Fir timber in

Canyons near the line; good

grap and well adapted to  
grazing

October 29

Exteriors  
 377 Subdivisions of Township No. 3 South Range 31  
 East Willamette Meridian, Oregon.

South on the West bound-  
 ary of Section 31.  
 Pa. 20° East-

29.00 Enter timber course E & W. - 200

30.50 Brook 6 lks. wide course west

35.00 Leave timber E & W.

40.00 Set Stone 14 x 10 x 6 on open + 100  
 knoll for  $\frac{1}{4}$  Sec. cor.

A Pine 36 in diam. brs. N. 40° E. 151 lks dist

62.00 Enter timber course N. E & S. W.

80.00 Set Stone 18 x 8 x 7 in small  
 open glade for corner to Town-  
 ships 3 and 4 South Ranges  
 30 $\frac{1}{2}$  and 31 East Willamette Mer.

A Pine 24 in diam. brs. N. 55° E. 190 lks. dist.

" " 16 " " " S. 11° E. 283 " "

" " 12 " " " S. 17° W. 196 " "

" " 28 " " " N. 55° W. 111 " "

Land: Surface Mountainous  
 Soil 3<sup>rd</sup> rate good timber in  
 places. Pine, Fir & Tamarack good  
 gras.  
 Nov. 5<sup>th</sup> 1878

## Exteriors

Subdivisions of Township No. 3 South Range 31

East Willamette Meridian, Oregon.

391

General Description  
This Township is mostly mountainous, and the S. Eastern part is covered with good timber. The northwestern and northern portions contain a large amount of good agricultural lands most of which are already claimed. There are two Saw-mills in this Township one in the vicinity or on Sec. 32 the other in the vicinity or on Sec. 16. As near as I could learn there are about 14 settlers in this Township. It should be subdivided

FINAL AFFIDAVIT OF ASSISTANTS.

We hereby certify that we assisted George S. Pershin Deputy Surveyor, in surveying the Exteriors of Townships 3 South Ranges 30 & 31 East Willamette Meridian, Oregon, and that said lines have been in all respects, to the best of our knowledge and belief, well and faithfully surveyed, and the boundary monuments planted according to the instructions furnished by the Surveyor General; and we do further swear that we each of us performed the work assigned us, faithfully to the best of our ability, in the capacity hereby indicated by our signatures.

Herwan D. Gradon Chainman.

Lorington Newell Chainman.

..... Chainman.

..... Axeman.

..... Axeman.

..... Compassman.

STATE OF OREGON, }  
County of Multnomah }

Subscribed and sworn to before me, this 3<sup>d</sup> day of December 1878

E. W. Cornell  
Notary Public in  
aforesaid county & State

I George S. Pershin

Deputy Surveyor, do solemnly swear that in pursuance of a contract with James C. Tolman U. S. Surveyor General of the State of Oregon, bearing date the 19<sup>th</sup> day of September 1878, and in strict conformity with the Printed Manual of Instructions, and the instructions given me by the Surveyor General, I have faithfully surveyed the Exterior lines of Townships 3 South Ranges 30 & 31 East aforesaid, and do further solemnly swear that the foregoing are the true and original field notes of such survey.

George S. Pershin  
Deputy Surveyor.

STATE OF OREGON,  
County of Multnomah

Subscribed and sworn to before me, a Notary Public in and for the said County and State, this 15<sup>th</sup> day of January 1879

E. W. Cornell  
Notary Public  
Oregon



Office U. S. Surveyor General,

Portland, Oregon, Jan 20 1879

The foregoing Field Notes of the survey of  
the Exterior lines of S. 3 S. Rqs 30<sup>th</sup> & 31 East Will Mer  
executed by George S. Pershir, U.S. Dept Sur  
under his contract No. 304

Dated Sept 19<sup>th</sup> 1878, having been criti-  
cally examined, the necessary corrections and  
explanations made, the said field notes and  
the survey they describe, are hereby approved.

James C. Tolman  
Surveyor General.