

## FIELD NOTES

Of the survey of the *Exterior boundary*  
 Lines of Townships *3 South of Ranges*  
*30 and 31 East Meridian, Oregon.*

Executed by *George S. Pershin*

U. S. Deputy Surveyor, under his Contract

No. *304* dated *Sept 19<sup>th</sup> 1878*

List of the names of the persons employed to assist in running, measuring and marking the lines of the foregoing survey.

*Herman D. Gradon* Chainman.

*Corrington Newell* Chainman.

..... Chainman.

..... Axeman.

..... Axeman.

..... Compassman.

..... Flagman.

*Errors in S. ldy of T. 39 R 30 E*  
*see page 5 of Cont. in Cont 332*

PRELIMINARY OATHS OF ASSISTANTS.

We, *Hermow D Gradon* and  
*Corrington Newell*

do solemnly swear that we will faithfully execute the duties of Chain Carriers, that we will level the chain upon uneven ground, and plumb the tally pins, whether by sticking or dropping the same; that we will report the true distance to all notable objects, and the true length of all lines, that we assist in measuring, to the best of our skill and ability.

*Hermow D. Gradon* Chainman.  
*Corrington Newell* Chainman.  
Chainman.

Subscribed and sworn to before me, this *28<sup>th</sup>*

day of *October* 187*8*

*S G Lightfoot*  
*J. P.*

We, ..... and

do solemnly swear that we will well and truly perform the duties for which we have been severally employed according to instructions and to the best of our skill and ability.

Subscribed and sworn to before me, this.....

day of..... 187

# INDEX.

Referring the lines to the pages of the field notes.

Town. *3 South* Range *31 East* Willamette Meridian.

<i>18</i>	6	5	4	3	2	1	<i>28</i>	
<i>19</i>	7	8	9	10	11	12	<i>29</i>	
<i>20</i>	18	17	16	15	14	13	<i>30</i>	<i>13</i>
<i>21</i>	19	20	21	22	23	24	<i>31</i>	<i>12</i>
<i>22</i>	30	29	28	27	26	25	<i>32</i>	<i>13</i>
<i>23</i>	31	32	33	34	35	36	<i>33</i>	<i>24</i>
	<i>31</i>	<i>32</i>	<i>33</i>	<i>34</i>	<i>35</i>	<i>36</i>		<i>25</i>

*T. 3. S. R. 30 E. W. M. et.*

<i>31</i>	<i>32</i>	<i>33</i>	<i>34</i>	<i>35</i>	<i>36</i>	<i>37</i>
<i>10</i>	<i>11</i>	<i>12</i>	<i>13</i>	<i>14</i>	<i>15</i>	

Exteriors

Subdivisions of Township No. 3 South Range 31  
East Willamette Meridian, Oregon.

18  
372

I begin at post in mound of  
stone the corner to Townships  
2 and 3 South Ranges 30 1/2 and  
31 East and with Burts im-  
proved Solar Compass I run  
South along the west boundary of Sec. 6  
Pa. 21° East

- 3.00 Road to Sawmill & timber S 10° E & N. 10° W.
- 4.00 Set Stone 17x12x5 on N. descent  
of plain for 1/4 Sec. cor.
- 75.00 Cabin, unfinished br. S 75° W.
- 80.00 " " " " N 40° W + 150

Set Stone 16x10x5 on North  
Slope, in mound of stone  
for corner to sections, 1, 12,  
6 and 7. dug pits and drove  
Stake as per instructions  
Land: Surface plain sloping  
north; Soil 1<sup>st</sup> and 2<sup>d</sup> rate  
good grass; good farming  
land

## Exteriors

Subdivisions of Township No. 3 South Range 31

378

East Willamette Meridian, Oregon.

I find the post lying at side of mound  
the corner to Townships 2 and 3  
South Ranges 31 and 32 East and  
from this corner I run  
South along the east boundary of sec. 1.

Pa.  $20^{\circ} 50'$  East

2000 Top of ridge N. W. & S. E. + 300

3800 Ravine course West - 100

4000 Set Stone  $24 \times 14 \times 12$  on north + 20  
hillside for  $\frac{1}{4}$  sec. cor.

8000 Set Stone  $20 \times 12 \times 10$  on N. E. face + 400  
of mountain for corner to  
Sections 1, 12, 6 and 7 dug  
pits and drove stake and  
raised stone mound around  
corner.

Land surface Mountainous  
Soil 3<sup>rd</sup> and 2<sup>nd</sup> rate good  
grass

## Exteriors

Subdivisions of Township No. 3 South Range 31

East Willamette Meridian, Oregon.

391

General Description  
This Township is mostly mountainous, and the S. Eastern part is covered with good timber. The North-western and northern portions contain a large amount of good agricultural lands most of which are already claimed. There are two Saw-mills in this Township one in the vicinity or on Sec. 32 the other in the vicinity or on Sec. 16. As near as I could learn there are about 14 settlers in this Township. It should be subdivided

FINAL AFFIDAVIT OF ASSISTANTS.

We hereby certify that we assisted George S. Pershin Deputy Surveyor, in surveying the Exteriors of Townships 3 South Ranges 30 & 31 East Willamette Meridian, Oregon, and that said lines have been in all respects, to the best of our knowledge and belief, well and faithfully surveyed, and the boundary monuments planted according to the instructions furnished by the Surveyor General; and we do further swear that we each of us performed the work assigned us, faithfully to the best of our ability, in the capacity hereby indicated by our signatures.

Herwan D. Gradon Chainman.

Lorington Newell Chainman.

..... Chainman.

..... Axeman.

..... Axeman.

..... Compassman.

STATE OF OREGON,

County of Multnomah }

Subscribed and sworn to before me, this 3<sup>d</sup>

day of December 1878

E. W. Cornell  
Notary Public in  
aforesaid county & State

I George S. Pershin

Deputy Surveyor, do solemnly swear that in pursuance of a contract with James C. Tolman U. S. Surveyor General of the State of Oregon, bearing date the 19<sup>th</sup> day of September 1878, and in strict conformity with the Printed Manual of Instructions, and the instructions given me by the Surveyor General, I have faithfully surveyed the Exterior lines of Townships 3 South Ranges 30 & 31 East aforesaid, and do further solemnly swear that the foregoing are the true and original field notes of such survey.

George S. Pershin  
Deputy Surveyor.

STATE OF OREGON,  
County of Multnomah

Subscribed and sworn to before me, a Notary Public in and for the said County and State, this 15<sup>th</sup> day of January 1879

E. W. Cornell  
Notary Public  
Oregon



Office U. S. Surveyor General,

Portland, Oregon, Jan 20 1879

The foregoing Field Notes of the survey of  
the Exterior lines of S. 3 S. Rqs 30<sup>th</sup> & 31 East Will Mer  
executed by George S. Pershir, U.S. Dept Sur

under his contract No. 304

Dated Sept 19<sup>th</sup> 1878, having been criti-  
cally examined, the necessary corrections and  
explanations made, the said field notes and  
the survey they describe, are hereby approved.

James C. Dolman  
Surveyor General.