

North Range 33 East Willamette Meridian

### General Description

The quality of Land in this Township is good being generally level or gently rolling and is well watered by numerous Springs through various portions of the Township.

There is however no Timber  
There are a number of Settlers  
and it should be subdivided

---

Field notes of the Survey of the  
Eastern boundaries of Townships  
1 & 2 North Range 3 East of the Willamette  
Meridian in the State of Oregon  
by Surveyor P. Thompson Deputy  
Surveyor under his contract no.  
"106" bearing date the 16<sup>th</sup> day of  
August 1864

Commenced October 3<sup>rd</sup> 1864  
Completed October 8<sup>th</sup> 1864



South Range 31 East Willamette Meridian

South on West boundary of sec 30

40.00

Variation 19° 15' East

4000 Set Stone 18 x 12 x 8 in for 1/4 sec corner

8000 Set Stone 20 x 12 x 10 in for corner to  
Secs 30, 31, 25 & 36

Level

Soil 2<sup>nd</sup> rate

South on West boundary of sec 31

40.00

Variation 24° 30' East

4000 Set Stone 22 x 8 x 6 in for 1/4 sec corner

8000 Set post for corner to townships 2 & 3

South Range 30 & 31 East in mound  
of earth with charred stake pits  
trench & c as per instructions

Level

Soil good 2<sup>nd</sup> rate



The Survey of the Townships on the South of the Base line may not have been Surveyed in the order that they should have been but in the absence of any instructions in regard to the Survey of Townships South of a Base line before the Meridian Parallel were run I did what I thought best under the circumstances and commenced a run of Meridian South from the same corner where the Meridian North leaves the Base line and run South East and North to intersect the base line and set closing corners on the base line through both Townships.

On the Survey of Township 1 North Range 32 East I remeasured the South boundary and set half mile and mile posts commencing at the South East corner as this had been the instruction that was given in regard to the error on the base line in measuring it and making the Exception on the West boundary



On the West of Townships 182 South Range 31 East there is some country that is of some value as a grazing country but there is no farming land for a considerable distance in that direction. On the South of Townships 2 South Ranges 31 & 32 East is steep rugged mountains of no value and there is no probability that there will be ever any necessity for more surveys in that direction and the same will apply to Township 182 S. Range 32 East as they run as high on the West Slope of the Blue Mountains as the land is of any value for "farming grazing or lumber". This will also apply to Township 1 North Range 33 East as the East boundary is high up in steep rugged story mountains. On the East of Townships 2 & 3 North Range 33 East is the best land in this section of country being along the Base of the Blue Mountains which run North East and South West but this country is on the Mwatilla Indian Reservation W. H. Barnhart Agent



who informed me that there were about 1080 Indians old and young on the Reservation composed of Cayuse. Walla Walla and a part of the Yakama Tribe of Indians. He also stated that a treaty should be made with these Indians and the land purchased from them and the Indians sent to the Warm Spring. Yakama and Nezperce Reservations as the Indians here about one third speak the Nezperce language are <sup>inter</sup> married with them and are in fact a part of that tribe. The same is true of the other two thirds with the Yakamas and Warm Spring Indians. The Reservation is immediately on the great thoroughfare between the Columbia and the Gold Mines of Oregon and Idaho Territory more than one hundred thousand persons pass through this Reservation yearly to and from the mines.

The Reservation should be abolished and the Indians given other land where they will not be thrown so much in contact with the whites.



if such a treaty can be made with them, and the rich lands that they now occupy thrown open for settlement and this will become one of the most productive districts of country East of the Cascade Mountains.

On the north of Townships 3 North Range 32833 East the country is gently descending for about twelve miles then is then a short ascent to Waller Waller Valley. The lands in this section and for many miles to the North East along the northern boundary of the State is fast attracting lands with at least two hundred settlers many of whom have been on their lands for from four to seven years and are very anxious to have the lands surveyed so they may know where their lands are and get their titles to them. Surveys are more needed in this part of the country than any I know of in the State. Now that the boundary line between the State of Oregon and the Territory of Washington



has been established the settlers  
hope and expect that it will be  
Speciaily Succeeded

### List of Names

A List of the names of the men and  
employed to assist in measuring and  
marking the lines and corners as shown  
in the foregoing field notes of the  
Eastern townships of Townships 1, 2 & 3 north  
of the base line of Ranges 32 & 33 East  
and Townships 1 & 2 South Ranges 31  
& 32 East of the Willamette Meridian  
showing the respective capacities  
in which they acted

G. S. Dotson Chairman  
J. W. Newman        "  
A. McLean        Assessor



337

We hereby certify that we Assistant  
 David P Thompson deputy Surveyor in surveying  
 the exterior boundaries of Townships  
 1283 North of the base line of Range  
 32833 East and of Townships 182  
 South of the Base line of Ranges 318  
 32 East of the Willamette Meridian  
 and that since Exterior lines have been  
 in all respects  
 to the best of our knowledge and ability  
 well and faithfully surveyed and the  
 boundary monuments planted accord-  
 -ing to the instructions furnished  
 by the Surveyor General

J. S. Gotsch on chairman  
 W. Newman  
 A. H. Stan Aeman

Sworn and subscribed before  
 me this 8<sup>th</sup> day of November 1864

David P. Thompson

Notary Public Justice of the Peace



98

I Daire P Thompson deputy Surveyor

338

do solemnly swear that in pursuance  
of a contract with B. J. Puzer Surveyor of the public  
land of the United States in the State of Oregon  
bearing date the 16<sup>th</sup> day of August 1864 and  
in strict conformity to the laws of the United States  
and the instructions furnished by the Senior Sur-  
veyor General I have faithfully surveyed the  
Esteris boundaries of Townships 1. 2. 83  
North of the base line of Ranges 32 & 33 East  
of the Willamette meridian and Townships  
1 & 2 South Ranges 31 & 32 East of the Willamette  
meridian in the State of Oregon and  
do further solemnly swear that the foregoing  
are the true and original field notes  
of such survey and that the Township  
corner posts referred to in the notes are  
not less than four (4) feet long two (2) feet  
in the ground by five (5) inches in diameter  
two (2) feet above ground by four (4) inches  
square and the quarter section corner



posts are of the same length & depth in the  
 339  
 ground and height above it by three (3)

inches in the width: that the corners  
 and corner stones have been constructed  
 of not less size and dimensions pre-  
 scribed in the Manual; and that all  
 the lines and corners have been marked  
 and continued in every respect as  
 required by the surveying instructions  
 at pages 2 to 11 inclusive and that  
 they are calculated to ensure the ordinary  
 natural deterioration

David P. Thompson

Deputy Surveyor

Sworn and subscribed to before me  
 this 26<sup>th</sup> day of November 1864

W. S. Barlow

Justice of The Peace  
 for Blackhawk Co. Oregon



Surveyor Generals office  
Cincinnati

The foregoing field notes of  
the Survey of the Exterior bound-  
ary lines of Townships No. 1-  
2 & 3 N. R. No. 32 E  
Townships No. 2 & 3 N. Will.  
R. No. 33 E of the Base  
line, and Townships No.  
" 1 & 2 S. R. 31 E. Townships  
1 & 2 S. R. 32 E of the Base  
line



340 1/2

340A

Dec. 25<sup>th</sup> 1864

Surveyor General's Office  
Eugene City Dec. 25<sup>th</sup> 1864  
The foregoing field notes of the  
Survey of the Exterior lines of  
Townships Nos. 1, 2 & 3 N. of  
the Base line R. 32 E. of Tps.  
2 & 3 N. of the base line R. 33 E.  
of the Willamette Mer. Tps. No.  
1 & 2 S. R. 31 E. Tps. 1 & 2 S  
of the Base line Range 32 E.  
of the Willamette Meridian  
Executed by David P. Thompson  
under his Contract No. 106  
bearing date the 16<sup>th</sup> day of  
August 1864. Having been  
critically examined, the  
necessary explanations &  
corrections made the  
said field notes and the  
surveys they describe  
are hereby approved  
J. J. Penza  
Surv. Genl.  
of Oregon