

Field notes of the Survey of the
Exterior boundaries of Township
No 2 South of the base line of Range
No 32 East of the Willamette Meridian
in the State of Oregon by David P
Thompson Deputy Surveyor under his
Contract No "106" bearing date the
16th day of August 1864

Commenced October 9th 1864
Completed October 10th 1864

313

73

Enter boundaries of Township
 Begin at the corner of Township 283
 South Range 31832 East and run
 East on South boundary of Sec 31
 Variation 19° East

Descend hill

2250 back to NW corner plus NW Foot of Top
hill. Ascend hill

3850 Spring flows South

4000 Set stone 20x15x10 in for 1/4 Sec corner

8000 Set stone 24x10x10 in for corner
to Secs 31, 32, 33, 36 +
600

Land very steep and stony
Soil 3rd rate

East on South boundary of Sec 32
 Variation 24° East

Ascend hill

3700 Reine course SW

4000 Set stone 15x8x6 in for 1/4 Sec corner

8000 Set stone 20x12x10 in for corner
to Secs 32, 33, 34, 35-

Enter Lincoln bars N & S

General hilly

Soil 2nd rate

South Range 32 East Willamette Meridian
 Eastern South boundary of Sec 33
 Variation 21° East

Same hill

4000 Set Stone 15x12x4 in for 1/4 Sec corner

7400 Brook 3 1/2 Mts wide runs North

8000 Set Stone 16x12x5 in for corner trees

3, 4, 33 & 34

400

Same hilly Soil 2nd rate
 Timber Fir, Pine & Spruce

East on South boundary of Sec 34
 Variation 20° East

4000 Set post for 1/4 Sec corner from which

@ Fir 8 in diam bears N 40° W 13 Mts dist

@ " 12 " " " S 50° W 5 " "

4475 Brook 6 Mts wide runs North

6500 Top of hill bears N & S descent 300

8000 Set post for corner trees 2, 3, 34 & 35 from which

@ Pine 5 in diam bears N 22° W 20 Mts dist

@ Spruce 3 " " " N 45° E 18 " "

@ Pine 7 " " " S 63° E 29 " "

@ " 5 " " " S 50° W 16 " "

Same hilly Soil 3rd rate

Timber Pine Fir and Spruce

WMS

Western boundaries of Township 2
East on South boundary of sec 35
Variation 21° East

4000 Set stone $18 \times 12 \times 4$ in for $\frac{1}{4}$ sec corner
4975 Foot of hill. Brook 3 Ms river
runs north. Ascene hill 400
8000 Set stone $20 \times 15 \times 10$ in for corner to sec
1, 2, 3 & 35 from which
@ Pine 24 in diam bears $N 45^{\circ} E 30$ Ms dist
@ " 20 " " " $N 17^{\circ} W 63$ " "
Sanae hills
Soil 3rd rate 400
Timber Pine Fir & Spruce

East on South boundary of sec 36
Variation 22° East

Ascene hill along north slope
4000 Set stone $20 \times 8 \times 6$ in for $\frac{1}{4}$ sec corner
Top of hill
8000 Set post for corner to Townships
2 & 3 South Ranges 32 & 33 East
from which
@ Pine 24 in diam bears $N 30^{\circ} W 116$ Ms dist
@ " 24 " " " $N 50^{\circ} E 99$ " "
@ Fir 10 " " " $S 30^{\circ} E 175$ " "
@ Pine 20 " " " $S 47^{\circ} W 213$ " "
Sanae hills. Soil 2nd rate. Timber Pine & Fir

The Survey of the Townships on the South of the Base line may not have been Surveyed in the order that they should have been but in the absence of any instructions in regard to the Survey of Townships South of a Base line before the Meridian Parallel were run I did what I thought best under the circumstances and commenced a run of Meridian South from the same corner where the Meridian North leaves the base line and run South East and North to intersect the base line and set closing corners on the base line through both Townships.

On the Survey of Township 1 North Range 32 East I remeasured the South boundary and set half mile and mile posts commencing at the South East corner as this had been the instruction that was given in regard to the error on the base line in measuring it and making the Exception on the West boundary

On the West of Townships 182 South Range 31 East there is some country that is of some value as a grazing country but there is no farming land for a considerable distance in that direction. On the South of Townships 2 South Ranges 31 & 32 East is steep rugged mountains of no value and there is no probability that there will be ever any necessity for more surveys in that direction and the same will apply to Township 182 S. Range 32 East as they run as high on the West Slope of the Blue Mountains as the land is of any value for "farming grazing or lumber". This will also apply to Township 1 North Range 33 East as the East boundary is high up in steep rugged story mountains. On the East of Townships 2 & 3 North Range 33 East is the best land in this section of country being along the Base of the Blue Mountains which run North East and South West but this country is on the Mwatilla Indian Reservation W. H. Barnhart Agent

who informed me that there were about 1080 Indians old and young on the Reservation composed of Cayuse. Walla Walla and a part of the Yakama Tribe of Indians. He also stated that a treaty should be made with these Indians and the land purchased from them and the Indians sent to the Warm Spring. Yakama and Nezperce Reservations as the Indians here about one third speak the Nezperce language are ^{inter} married with them and are in fact a part of that tribe. The same is true of the other two thirds with the Yakamas and Warm Spring Indians. The Reservation is immediately on the great thoroughfare between the Columbia and the Gold Mines of Oregon and Idaho Territory more than one hundred thousand persons pass through this Reservation yearly to and from the mines.

The Reservation should be abolished and the Indians given other land where they will not be thrown so much in contact with the whites.

if such a treaty can be made with them, and the rich lands that they now occupy thrown open for settlement and this will become one of the most productive districts of country East of the Cascade Mountains.

On the north of Townships 3 North Range 32 & 33 East The country is gently descending for about twelve miles then is there a short ascent to Walla Walla Valley. The lands in this section and for many miles to the North East along the northern boundary of the State is fast attracting lands with at least two hundred settlers many of whom have been on their lands for from four to seven years and are very anxious to have the lands surveyed so they may know where their lands are and get their titles to them. Surveys are more needed in this part of the country than any I know of in the State. Now that the boundary line between the State of Oregon and the Territory of Washington

has been established the settlers
hope and expect that it will be
Speciaily Succeeded

List of Names

A List of the names of the men and
employed to assist in measuring and
marking the lines and corners as shown
in the foregoing field notes of the
Eastern townships of Townships 1, 2 & 3 north
of the base line of Ranges 32 & 33 East
and Townships 1 & 2 South Ranges 31
& 32 East of the Willamette Meridian
showing the respective capacities
in which they acted

G. S. Dotson Chairman
J. W. Newman " "
A. McLean Assessor

337

We hereby certify that we Assistant
 David P Thompson deputy Surveyor in surveying
 the exterior boundaries of Townships
 1283 North of the base line of Range
 32833 East and of Townships 182
 South of the Base line of Ranges 318
 32 East of the Willamette Meridian
 and that since Exterior lines have been
 in all respects
 to the best of our knowledge and ability
 well and faithfully surveyed and the
 boundary monuments planted accord-
 -ing to the instructions furnished
 by the Surveyor General

J. S. Gotsen chairman
 J. W. Newman
 A. H. Stan Aeman

Sworn and subscribed before
 me this 8th day of November 1864

David P. Thompson

Notary Public Justice of the Peace

98

I Daire P Thompson deputy Surveyor

338

do solemnly swear that in pursuance
of a contract with B. J. Pezzer Surveyor of the public
land of the United States in the State of Oregon
bearing date the 16th day of August 1864 and
in strict conformity to the laws of the United States
and the instructions furnished by the Senior Sur-
veyor General I have faithfully surveyed the
Esteris boundaries of Townships 1. 2. 83
North of the base line of Ranges 32 & 33 East
of the Willamette meridian and Townships
1 & 2 South Ranges 31 & 32 East of the Willamette
meridian in the State of Oregon and
do further solemnly swear that the foregoing
are the true and original field notes
of such survey and that the Township
corner posts referred to in the notes are
not less than four (4) feet long two (2) feet
in the ground by five (5) inches in diameter
two (2) feet above ground by four (4) inches
square and the quarter section corner

339

posts are of the same length & depth in the
 ground and height above it by three (3)
 inches in the width: that the corners
 and corner stones have been constructed
 of not less size and dimensions pre-
 scribed in the manual; and that all
 the lines and corners have been marked
 and continued in every respect as
 required by the surveying instructions
 at pages 2 to 11 inclusive and that
 they are calculated to ensure the ordinary
 natural deterioration

David P. Thompson
 Deputy Surveyor

Sworn and subscribed to before me
 this 26th day of November 1864

W. S. Barlow
 Justice of The Peace
 for Clatsop Co. Oregon

Surveyor Generals office
Cincinnati

The foregoing field notes of
the Survey of the Exterior bound-
ary lines of Townships No. 1-
2 & 3 N. R. No. 32 E
Townships No. 2 & 3 N. Will.
R. No. 33 E of the Base
^{line} ~~line~~, and Townships No.
" 1 & 2 S. R. 31 E. Townships
1 & 2 S. R. 32 E of the Base
line

340 1/2

340A

Dec. 25th 1864

Surveyor General's Office
Eugene City Dec. 25th 1864
The foregoing field notes of the
Survey of the Exterior lines of
Townships Nos. 1, 2 & 3 N. of
the Base line R. 32 E. of Tps.
2 & 3 N. of the base line R. 33 E.
of the Willamette Mer. Tps. No.
1 & 2 S. R. 31 E. Tps. 1 & 2 S
of the Base line Range 32 E.
of the Willamette Meridian
Executed by David P. Thompson
under his Contract No. 106
bearing date the 16th day of
August 1864. Having been
critically examined, the
necessary explanations &
corrections made the
said field notes and the
surveys they describe
are hereby approved
J. J. Penza
Surv. Genl.
of Oregon