

FIELD NOTES

189

Of the survey of the Subdivision
 Lines of Township 3 South
R. 22 East, Willamette Meridian,
 Oregon, as surveyed by George S.
Pershing, U. S. Deputy Surveyor,
 under his Contract No. 430, dated
March 23rd, 1882

Survey commenced, May 16 1882

Survey completed, May 27 1882

NAMES AND DUTIES OF ASSISTANTS.

-, Compassman.
- Liegh Gatch....., Chainman.
- James B Ellis....., Chainman.
- Frank F Ellis....., Chainman.
-, Chainman.
- Valentine Brown....., Axeman.
-, Axeman.
-, Flagman.

INDEX.

Referring the Lines to the Pages of the Field Notes.

T. No 3 South R. No 32 East Will. Mer.

6	5	98	4	66	3	44	2	22	1
	96		94		64		42		20
7	8	92	9	62	10	40	11	18	12
	90		88		60		38		16
18	17	86	16	58	15	36	14	14	13
	84		82		56		34		12
19	20	80	21	54	22	32	23	10	24
	78		76		52		30		8
30	29	74	28	50	27	28	26	6	25
	72		70		48		26		4
31	32	68	33	46	34	24	35	2	36

Meanders of _____ Pages _____ to _____

Meanders of _____ Pages _____ to _____

1911¹A

Subdivisions of T. 3 South R. 32 East
Willamette Meridian, Oregon.

Having surveyed the East Boundary of this Township myself with my present assistants I do not retrace the east and South Boundaries of Sec. 36

I begin at the corner to Sec. 35 and 36 on the South Boundary of this Township which is a Stone projecting 7 inches above ground and marked with one notch on E and 5 notches on W. edges from which

A Pine 32 ins. di. brs. N. 42° E 52 lks. dist
marked T 3 S. R. 32 E. S. 36 B T

A Pine 26 ins di. brs. S. 23° E 54 lks dist
marked T 4 S. R. 32 E. S 1 B. T.

A Pine 26 ins di. brs. S 38° N. 133 lks dist
Marked T 4 S. R 32 E S. 2 B T

2 192

Subdivisions of T. 3 South R. 32 East

Willamette Meridian, Oregon.

A Pine 38 ins. di. lrs. N. 15° W 66 lrs dist
Marked T 3 S, R. 32 E, S. 35 B, T.

Survey commenced May 16 1882
North between Sec. 35 and 36

or,

3550 A brook, 6 lrs. wide co. S. E.

40.00 Set a basalt-stone 16 X 8 X 7 ins. 19 ins.
in ground on S. W. slope for
 $\frac{1}{4}$ Sec. cor. Marked $\frac{1}{4}$ on W. face

A Pine 15 ins. di. lrs. N. 40° E. 25 lrs. dist
Marked $\frac{1}{4}$ S. B, T.

A Pine 27 ins. di. lrs. N. 36° W. 31 lrs. dist
Marked $\frac{1}{4}$ S. B, T.

53.50 natural meadow co. N. E & S. W.

55.00 A brook, 4 lrs. wide co. S. W.

57.00 Leave meadow. co. S. W. & N. E

80.00 Set a Granite Stone 18 X 14 X 5 ins
12 ins. in ground on West slope
for cor. to Sec., 25, 26, 35 and 36
Marked with 1 notch on S. and E
edges from which

24

214

Subdivisions of T.3 South R.32 East

Willamette Meridian, Oregon.

From the cor to sec. 34 and 35 which
is a post marked with 2 notches
on east. T 3 S. R. 32 E S. 35 on N.E

T 4 S. R. 32 E. S. 2 on S.E. T 4 S. R. 32 E

S. 3 on S.W. and T 3 S. R. 32 E. S. 3 4 on N.W.

A Pine 4 in. di. brs. N. 28° E. 30 lbs dist

marked T 3 S. R. 32 E S. 35 B.T.

A Pine 4 ins. di. brs. S 54° E 12 lbs dist

marked T 4 S. R. 32 E. S 2 B.T.

No tree S.W.

A Tamarack 4 in. di. brs. N. 60 W. 20 lbs dist

marked T 3 S. R. 32 E. S. 34 B.T.

I run

North between sec. 34 and 35

rd.

3.50 A Spring branch co. west

40.00 Set a post 4 ft long 4 ins diam
in mound of stone on slight
south slope for 1/4 sec. cor. marked

1/4 S. on N. face from which

A Pine 8 ins. di. brs. S. 86° E. 105 lbs dist

marked 1/4 S. B.T.

46

236

Subdivisions of T. 3 South R. 32 East

Willamette Meridian, Oregon.

From the cor. to Sec. 33 and 34
which is a Stone 18 x 12 x 7
marked with 3 notches on
E. and W. Edge from which

A Pine 8 in di. brs. N. 68° E. 48 lks dist

Marked T 3 S. R. 32 E. S. 34 B. T.

A Fir 5 in di. brs S. 78° E. 48 lks dist

Marked T 4 S. R. 32 E. S. 3 B. T.

A Fir 6 in di. brs S. 60° W. 110 lks dist

Marked T 4 S. R. 32 E. S. 4 B. T.

A Pine 9 in di. brs N. 76° W. 117 lks dist

Marked T 3 S. R. 32 E. S. 33. B. T.

I. run

North between Sec. 33 and 34

~~wa.~~

Undulating and slightly rising
4000. Set a post 4 ft long 4 in di on
level in mound of stone for
1/4 Sec. cor. Marked 1/4 S. on
West face from which a

68 258

Subdivisions of T.3 South R.32 East

Willamette Meridian, Oregon.

From the cor to 32 and 33
which is a stone 16 x 10 x 4
marked with 4 notches on E edge

A Tamarack. 13 lbs. di. lbs. N. 85° E 20 lbs dist

marked T3 S. R. 32 E. S 33 B, T.

A Tamarack. 4 ins. di. lbs. S. 36° E 25 lbs dist

marked. T4 S. R. 32 E. S. 4 B, T.

no tree S. W.

A Pine 28 ins di. lbs. N. 39 W. 97 lbs dist

marked T3 S. R. 32 E. S 32 B, T.

} } }

I run

North between Sec. 32 and 33

wa.

21.00 Wagon road co. E & W. to hot
Sulphur Springs

27.50 A Spring branch co. N. W.

40.00 Set a basalt Stone 18 x 16 x 5 ins
12 ins in ground on S. W.

FINAL OATHS FOR SURVEYS.

A list of the names of the individuals employed by George S Pershin, U. S. Deputy Surveyor, to assist in running, measuring and marking the lines and corners described in the foregoing field notes of the survey of the Subdivision lines of Township 3 South Range 32 East Willamette Meridian, Oregon, showing the respective capacities in which they acted :

-, Compassman.
- Leigh Gatch....., Chainman.
- James B. Ellis....., Chainman.
- Frank F. Ellis....., Chainman.
-, Chainman.
- Valentine Brown....., Axeman.
-, Axeman.
-, Flagman.

FINAL OATHS OF ASSISTANTS.

We hereby certify that we assisted George S Pershin, U. S. Deputy Surveyor, in surveying all those parts or portions of the Subdivision lines of Township No. 3 S. Range 32 East Willamette Meridian, Oregon, as are represented in the foregoing field notes as having been surveyed by him and under his direction ; and that said survey has been in all respects, to the best of our knowledge and belief, well and faithfully surveyed, and the corner monuments established, according to the instructions furnished by the U. S. Surveyor General of Oregon.

-, Compassman.
- Leigh Gatch....., Chainman.
- James B. Ellis....., Chainman.
- Frank F. Ellis....., Chainman.
-, Chainman.
- Valentine Brown....., Axeman.
-, Axeman.
-, Flagman.

Subscribed and sworn to before me, this twenty seventh day of May 1882.
[SEAL.] George S. Pershin
U. S. Deputy Surveyor

FINAL OATH OF DEPUTY SURVEYOR.

I, George S. Pershin

United States Deputy Surveyor, do solemnly swear that in pursuance of instructions

received from James C. Tolman

U. S. Surveyor General for Oregon, bearing date of the 23rd day of

March, 1882, I have well, faithfully, and truly, in my own proper person, and in strict conformity with the instructions furnished by the U. S. Surveyor General for Oregon, the Surveying Manual, and the laws of

the United States, surveyed all those parts or portions of the Subdivision lines of Township 3 South Range 32 East

Willamette Meridian, in the State of Oregon, as are represented in the foregoing Field Notes as having been surveyed by me and under my directions; and I do further solemnly swear that all the corners of said survey have been established and perpetuated in strict accordance with the Surveying Manual, printed instructions, the special written instructions of the U. S. Surveyor General for Oregon, and in the specific manner described in the field notes, and that the foregoing are the true field notes of such survey, and should any fraud be detected I will suffer the penalty of perjury under the provisions of an Act of Congress approved August 8, 1846.

George S. Pershin
U. S. Deputy Surveyor.

Subscribed and sworn to before me, this eleventh

day of July, 1882

Edmund F. Lewis
Notary Public

294A

Office U. S. Surveyor General,

Portland, Oregon, *August 12* 1882

The following Field Notes of the Survey of
the Subdivisional lines of Township
3 South, Range 32 East Willamette
Meridian Oregon
 executed by *George S. Pershin* U.S. Dept.
Surveyor under *his* contract No. *430*
 dated *March 23* 1882, having been
 critically examined, the necessary corrections and ex-
 planations made, the said field notes and the survey
 they describe, are hereby approved.

James C. Tolman
 Surveyor General.



295A
Portland, Oregon, July 21st 1880

Hon James C. Tolman U.S. Sur. Gen.

Sir

In reference to the apparent error in the closing on the South Boundary of Sec. 31 T2 S. R. 32 E. I would state that there is a deep rocky ravine at creek difficult to measure across; and the South and east boundaries of Sec. 5 T3 S. R. 32 E are on ground where accurate measurements can and were made, and that the north boundary of Sec. 5 would be practically the same as the South boundary, and that a re-measurement of said North boundary, could not render the error more apparent, as I ran the South and east boundaries very carefully with good sunshine and with a Solar.