



# INDEX DIAGRAM

Township 3 South, Range 31 East,

6	5	4	3	2	1	
7	8	9	10	11	12	
18	17	16	15	14	13	
19	20	21	22	23	24	<u>6</u>
30	29	28	27	26	25	<u>6</u>
		<u>11</u> <u>12</u>	<u>9</u> <u>10</u>	<u>8</u>	<u>7</u>	<u>5</u>
31	32	<u>11</u> 33	34	<u>8</u> 35	<u>7</u> 36	<u>5</u>
<u>4</u>	<u>4</u>	<u>3</u>	<u>3</u>	<u>2</u>	<u>2</u>	<u>1</u>

Remonumentation of Certain Original Corner Points,  
T. 3 S., R. 31 E., Willamette Meridian, Oregon

CHAINS

East Boundary T. 3 S., R. 31 E.,  
Willamette Meridian, Oregon

(Remonumenting corners established by George S. Pershin,  
U. S. Deputy Surveyor, in 1878,  
and changed to corners of minimum control by  
George S. Pershin, U. S. Deputy Surveyor, in 1882)

The  $\frac{1}{4}$  sec. cor. of sec. 36 only, on the E. bdy. of the  
Tp., determined at record bearing and distance from the  
original bearing trees:

A pine, 17 ins. diam., bears S.  $88^\circ$  E., 98 lks.  
dist., with scribe marks  $\frac{1}{4}$  S visible on open  
blaze.

A pine, 25 ins. diam., bears N.  $54^\circ$  W., 48 lks.  
dist., with scribe marks  $\frac{1}{4}$  S visible on open  
blaze.

At the corner point

Set an iron post, 28 ins. long,  $2\frac{1}{2}$  ins. diam., 22 ins.  
in the ground, and in a mound of stone, 3 ft. base, to  
top, with brass cap mkd.

T 3 S	
R 31 E	R 32 E
$\frac{1}{4}$ S 36	
1978	

from which a new bearing tree

A fir, 15 ins. diam., bears S.  $81^\circ$  W.,  $89\frac{1}{2}$  lks.  
dist., mkd.  $\frac{1}{4}$  S36 BT.

The cor. of secs. 25 and 36 only, on the E. bdy. of the  
Tp., monumented with the original basalt stone, 20 x 16  
x 7 ins., firmly set 8 ins. in the ground, mkd. with 5  
notches on N. edge, from which the remains of the  
original bearing trees:

A larch snag, 14 ins. diam., bears N.  $28^\circ$  W., 48  
lks. dist., with scribe marks 3S R31E S25  
visible on open blaze.

At the corner point

Set an iron post, 28 ins. long,  $2\frac{1}{2}$  ins. diam., 24 ins.  
in the ground, with brass cap mkd.

T 3 S		T 3 S
S 25		R 32 E
S 36		S 32
R 31 E		S 32
1978		

from which new bearing trees

A white fir, 12 ins. diam., bears N.  $84^\circ$  W.,  $74\frac{1}{2}$   
lks. dist., mkd. T3S R31E S25 BT.

A lodgepole pine, 11 ins. diam., bears S.  $14\frac{1}{2}^\circ$  W.,  
 $19\frac{1}{2}$  lks. dist., mkd. T3S R31E S36 BT.

Remonumentation of Certain Original Corner Points,  
T. 3 S., R. 31 E., Willamette Meridian, Oregon

CHAINS

Deposit corner stone alongside iron post.

The  $\frac{1}{4}$  sec. cor. of sec. 25 only, on the E. bdy. of the Tp., determined at record bearing and distance from the remains of the original bearing trees:

A pine snag, 11 ins. diam., bears East, 8 lks. dist., with scribe marks  $\frac{1}{4}$  S BT visible on open blaze.

A fir, 18 ins. diam., bears West, 28 lks. dist. with healed blaze.

At the corner point

Set an iron post, 28 ins. long,  $2\frac{1}{2}$  ins. diam., 24 ins. in the ground, with brass cap mkd.

T 3 S	
R 31 E	R 32 E
$\frac{1}{4}$ S 25	
1978	

from which a new bearing tree

A spruce, 8 ins. diam., bears S.  $37\frac{1}{2}^{\circ}$  W., 53 lks. dist., mkd.  $\frac{1}{4}$  S25 BT.

The  $\frac{1}{4}$  sec. cor. of sec. 24 only, on the E. bdy. of the Tp., determined at record bearing and distance from the remains of an original bearing tree:

A fir snag, 21 ins. diam., bears N.  $20^{\circ}$  W., 53 lks. dist., with fragmentary scribe marks visible on open and decayed blaze.

At the corner point

Set an iron post, 28 ins. long,  $2\frac{1}{2}$  ins. diam., 22 ins. in the ground, and in a mound of stone, 3 ft. base, to top, with brass cap mkd.

T 3 S	
R 31 E	R 32 E
$\frac{1}{4}$ S 24	
1978	

from which new bearing trees

A fir, 12 ins. diam., bears S.  $29\frac{1}{2}^{\circ}$  W., 20 lks. dist., mkd.  $\frac{1}{4}$  S24 BT.

A fir, 11 ins. diam., bears N.  $73^{\circ}$  W., 46 lks. dist., mkd.  $\frac{1}{4}$  S24 BT.

Subdivisions, T. 3 S., R. 31 E.,  
Willamette Meridian, Oregon

(Remonumenting corners established by George S. Pershin,  
U. S. Deputy Surveyor, in 1879)



CERTIFICATE OF SURVEY

(I) ~~(XX)~~, Craig L. Wanless, Cadastral Surveyor, HEREBY CERTIFY upon honor that, in pursuance of special instructions bearing date of the 3rd day of May, 19 57, (I) ~~(XX)~~ have remonumented certain original corner points, township 3 south, range 31 east,

of the Willamette Meridian, in the State of Oregon, which are represented in the foregoing field notes as having been executed by (me), ~~(XX)~~ and under (my) ~~(XX)~~ direction; and that said survey has been made in strict conformity with said special instructions, the Manual of Instructions for the Survey of the Public Lands of the United States, and in specific manner described in the foregoing field notes.

October 19, 1978  
(Date)

*Craig L. Wanless*  
(Cadastral Surveyor)

(Date)

(Cadastral Surveyor)

CERTIFICATE OF APPROVAL

BUREAU OF LAND MANAGEMENT  
~~Washington, D.C.~~  
Denver, Colorado

The foregoing field notes of the remonumentation of certain original corner points, township 3 south, range 31 east, Willamette Meridian, Oregon,

executed by Craig L. Wanless, Cadastral Surveyor, having been critically examined and found correct, are hereby approved.

FEB 07 1980  
(Date)

*J. Voorhes*  
(Chief, Division of Cadastral Survey)  
Chief, Cadastral Survey Examination and Approval Staff

CERTIFICATE OF TRANSCRIPT

I CERTIFY That the foregoing transcript of the field notes of the above-described surveys in \_\_\_\_\_, is a true copy of the original field notes.

(Date)

(Chief, Division of Cadastral Survey) GPO 849-526