

INDEX DIAGRAM

Township 3 South, Range 33 East,

6	5	4	3	2	1
7	8	9	10	11	12
18 <u>3</u>	17	16	15	14	13 <u>3</u>
19	20	21	22	23	24
30	29	28	27	26	25
31	32	33	34	35	36
<u>2</u>		<u>1</u>	<u>1</u>		

T. 3 S., R. 33 E., Willamette Meridian, Oregon

CHAINS

The following field notes describe the remonumentation of certain original corner points, township 3 south, range 33 east, Willamette Meridian, Oregon, as provided for in the General Special Instructions, Group Number 350, Oregon, dated May 3, 1957, "Investigation of Collateral or Physical Evidence of Corner Positions and Accessories, Followed by Remonumentation of Corner Points, with New Accessories, when Needed".

The remonumentation of original corner points was made at the request of the United States Forest Service, in conjunction with their Land Line Location Program.

The mean magnetic declination is 20° E.

South Boundary, T. 3 S., R. 33 E.,
Willamette Meridian, Oregon

(Remonumenting corners established by George S. Pershin,
U. S. Deputy Surveyor, in 1881)

The cor. of secs. 3, 4, 33, and 34, on the S. bdy. of the Tp., monumented with the original unmarked basalt stone, 16 x 10 x 5 ins., loosely set in a mound of stone, 3 ft. base, 2 ft. high, from which the original bearing trees:

A fir, 37 ins. diam., bears S. 85° E., 113 lks. dist., with fragmentary scribe marks visible on partially healed blaze. (Record, pine, S. 82° E.)

A pine, 29 ins. diam., bears N. 40° W., 175 lks. dist., with scribe marks T3S R33E S3 visible on partially healed blaze. (Record, 168 lks.)

At the corner point

Set an iron post, 28 ins. long, 2½ ins. diam., 12 ins. in the ground, to solid rock, and in a mound of stone, 3 ft. base, to top, with brass cap mkd.

T 3 S R 33 E
S 33 S 34
S 4 S 3
T 4 S
1977

from which new bearing trees

A pine, 13 ins. diam., bears N. 75° E., 48 lks. dist., mkd. T3S R33E S34 BT.

A grand fir, 10 ins. diam., bears S. 13° W., 173½ lks. dist., mkd. T4S R33E S4 BT.

Deposit corner stone alongside iron post.

The ¼ sec. cor. of secs. 4 and 33, on the S. bdy. of the Tp., monumented with the original basalt stone, 16 x 10 x 8 ins., firmly set 6 ins. in the ground, and in a mound of stone, 3 ft. base, 1 ft. high, mkd. ¼ on N. face, from which the remains of the original bearing trees:

Remonumentation of Certain Original Corner Points,
T. 3 S., R. 33 E., Willamette Meridian, Oregon

CHAINS

A root hole, bears N. 64° E., 44 lks. dist., with a down and decayed pine alongside, size indeterminate, with fragmentary scribe marks visible on decayed blaze.

A fir, 48 ins. diam., bears S. 67° E., 27 lks. dist., with healed blaze. (Record, S. 72° E., 21 lks.)

At the corner point

Set an iron post, 28 ins. long, $2\frac{1}{2}$ ins. diam., 18 ins. in the ground, to solid rock, and in a mound of stone, 3 ft. base, to top, with brass cap mkd.

T 3 S R 33 E
 $\frac{1}{4}$ $\frac{S 33}{S 4}$
 T 4 S
 1977

from which a new bearing tree

A grand fir, 9 ins. diam., bears N. 50° W., 57 lks. dist., mkd. $\frac{1}{4}$ S33 BT.

Deposit corner stone alongside iron post.

The cor. of secs. 5, 6, 31, and 32, on the S. bdy. of the Tp., monumented with the original basalt stone, 18 x 10 x 3 ins., firmly set 10 ins. in the ground, mkd. with 5 notches on E. and 1 notch on W. edges, from which the remains of the original bearing trees:

A larch, 30 ins. diam., bears S. 12° E., 13 lks. dist., with scribe marks R33E visible on partially healed blaze.

A root hole, bears S. 62° W., 23 lks. dist., with a down and decayed pine alongside, size indeterminate, no marks visible.

A larch, 23 ins. diam., bears N. 58° W., 11 lks. dist., with scribe marks S R visible on partially healed blaze.

At the corner point

Set an iron post, 28 ins. long, $2\frac{1}{2}$ ins. diam., 24 ins. in the ground, with brass cap mkd.

T 3 S R 33 E
 $\frac{S 31}{S 6} | \frac{S 32}{S 5}$
 T 4 S
 1977

from which new bearing trees

A grand fir, 11 ins. diam., bears N. 24° E., 65 lks. dist., mkd. T3S R33E S32 BT.

A grand fir, 6 ins. diam., bears S. $45\frac{1}{2}^{\circ}$ W., 33 lks. dist., mkd. T4S R33E S6 BT.

Remonumentation of Certain Original Corner Points,
T. 3 S., R. 33 E., Willamette Meridian, Oregon

CHAINS

Deposit corner stone alongside iron post.

Subdivisions, T. 3 S., R. 33 E.,
Willamette Meridian, Oregon

(Remonumenting corners established by Rufus S. Moore,
U. S. Deputy Surveyor, in 1882)

The cor. of secs. 13, 14, 23, and 24, monumented with the original basalt stone, 20 x 18 x 4 ins., loosely set 1 in. in the ground, in a collar of stone, mkd. with 1 notch on E. and 3 notches on S. edges, from which the remains of the original bearing trees:

A pine, 25 ins. diam., bears N. 57° E., 241 lks. dist., with scribe marks S23 BT visible on open blaze.

A pine, 25 ins. diam., bears S. 58° E., 134 lks. dist., with healed blaze. (Record, 131 lks.)

A pine snag, 10 ins. diam., bears S. 60° W., 35 lks. dist., with scribe marks S13 BT visible on partially healed blaze.

At the corner point

Set an iron post, 28 ins. long, 2½ ins. diam., 24 ins. in the ground, in a mound of stone, 2 ft. base, to top, with brass cap mkd.

T 3 S R 33 E
S 14 S 13
S 23 S 24
1977

from which a new bearing tree

A fir, 23 ins. diam., bears S. 69½° W., 34½ lks. dist., mkd. T3S R33E S23 BT.

Deposit corner stone alongside iron post.

The ¼ sec. cor. of secs. 18 and 19, monumented with the original basalt stone, 16 x 10 x 6 ins., firmly set 6 ins. in the ground, and in a mound of stone, 3 ft. base, 6 ins. high, mkd. ¼ on N. face, from which the remains of the original bearing trees:

A root hole, bears S. 20° W., 46 lks. dist., with a down and decayed pine alongside, size indeterminate, with scribe marks BT visible on open and decayed blaze. (Record, 40 lks.)

A twin pine, 14 ins. diam., bears N. 70° W., 53 lks. dist., no marks visible on opened blaze.

At the corner point

Set an iron post, 28 ins. long, 2½ ins. diam., 22 ins. in the ground, in a mound of stone, 2 ft. base, to top, with brass cap mkd.

CERTIFICATE OF SURVEY

(I) (~~XX~~), Craig L. Wanless, Cadastral Surveyor, HEREBY CERTIFY upon honor that, in pursuance of special instructions bearing date of the 3rd day of May, 19 57, (I) (~~XX~~) have remonumented certain original corner points, township 3 south, range 33 east,

of the Willamette Meridian, in the State of Oregon, which are represented in the foregoing field notes as having been executed by (me), (~~us~~) and under (my) (~~our~~) direction; and that said survey has been made in strict conformity with said special instructions, the Manual of Instructions for the Survey of the Public Lands of the United States, and in specific manner described in the foregoing field notes.

January 16, 1978
(Date)

Craig L. Wanless
(Cadastral Surveyor)

(Date)

(Cadastral Surveyor)

CERTIFICATE OF APPROVAL

BUREAU OF LAND MANAGEMENT
Washington, D.C.

The foregoing field notes of the remonumentation of certain original corner points, township 3 south, range 33 east, Willamette Meridian, Oregon,

executed by Craig L. Wanless, Cadastral Surveyor, having been critically examined and found correct, are hereby approved.

AUG 17 1978
(Date)

[Signature]
Acting (Chief, Division of Cadastral Survey)

CERTIFICATE OF TRANSCRIPT

I CERTIFY That the foregoing transcript of the field notes of the above-described surveys in, is a true copy of the original field notes.

(Date)

(Chief, Division of Cadastral Survey)