



# INDEX DIAGRAM

Township 3 South, Range 33½ East

6	5	4	3	2	1	
7	8	9	10	11	12	
			<u>7</u>			<u>4</u>
18	17	16	15	14	13	
				<u>7</u>		<u>3</u>
19	20	21	22	23	24	
			<u>6</u>	<u>5</u>		<u>3</u>
						<u>2</u>
30	29	28	27	26	25	
			<u>6</u>	<u>4</u>		<u>2</u>
			<u>5</u>			<u>1</u>
31	32	33	34	35	36	

## T. 3 S., R. 33½ E., Willamette Meridian, Oregon

## CHAINS

The following field notes describe the remonumentation of certain original corner points, township 3 south, range 33½ east, Willamette Meridian, Oregon, as provided for in the General Special Instructions, Group Number 350, Oregon, dated May 3, 1957, "Investigation of Collateral or Physical Evidence of Corner Positions and Accessories Followed by Remonumentation of Corner Points, with New Accessories when Needed."

The remonumentation of original corner points was made at the request of the United States Forest Service, in conjunction with their Land Line Location Program.

The mean magnetic declination is 20° E.

East Boundary, T. 3 S., R. 33½ E.,  
Willamette Meridian, Oregon

(Remonumenting corners established by  
Rufus S. Moore, Deputy Surveyor, in 1882)

The cor. of secs. 25, 30, 31, and 36, monumented with a basalt stone, 15 x 10 x 10 ins., loosely set 3 ins. in the ground, no marks visible, from which the remains of the original bearing trees:

A root hole, bears N. 66° E., 2 lks. dist., with a down and decayed pine alongside, 10 ins. diam., with scribe marks T3S R34E S30 visible on open decayed blaze.

A fir, 22 ins. diam., bears S. 28° E., 42 lks. dist., with healed blaze.

A fir, 12 ins. diam., bears S. 48° W., 18 lks. dist., with illegible scribe marks visible on partially healed blaze. (Record, pine)

A fir, 8 ins. diam., bears N. 69° W., 8 lks. dist., with scribe marks T3S R33½E S25 BT visible on open decayed blaze.

At the corner point

Set an iron post, 28 ins. long, 2½ ins. diam., 24 ins. in the ground, with brass cap mkd.

T 3 S	
R 33½ E	R 34 E
S 25	S 30
S 36	S 31
1975	

from which new bearing trees

A fir, 24 ins. diam., bears N. 23° E., 21 lks. dist., mkd. T3S R34E S30 BT.

A fir, 22 ins. diam., bears N. 20° W., 118 lks. dist., mkd. T3S R33½E S25 BT.

Deposit corner stone alongside iron post.

Remonumentation of Certain Original Corner Points,  
T. 3 S., R. 33½ E., Willamette Meridian, Oregon

CHAINS

The ¼ sec. cor. of secs. 25 and 30, monumented with a basalt stone, 16 x 12 x 4 ins., firmly set 12 ins. in the ground, mkd. ¼ on W. face, from which the original bearing trees:

A fir, 19 ins. diam., bears N. 74° E., 22 lks. dist., with illegible scribe marks visible on opened blaze.

A pine, 21 ins. diam., bears West, 10 lks. dist., with healed blaze.

At the corner point

Set an iron post, 28 ins. long, 2½ ins. diam., 24 ins. in the ground, with brass cap mkd.

T 3 S			
¼			
R 33½ E		R 34 E	
S 25		S 30	
1975			

Deposit corner stone alongside iron post.

The cor. of secs. 19, 24, 25, and 30, monumented with a basalt stone, 16 x 9 x 7 ins., firmly set 4 ins. in the ground, mkd. with 4 notches on N. and 2 notches on S. edge, from which the remains of the original bearing trees:

A pine, 35 ins. diam., bears N. 66° E., 57 lks. dist., with illegible scribe marks visible on partially healed blaze.

A pine, 30 ins. diam., bears S. 4° E., 209 lks. dist., with scribe marks 3S R3 S30 BT visible on opened blaze. (Record, 213 lks.)

A root hole, bears S. 46° W., 200 lks. dist., with a down and decayed pine alongside, 12 ins. diam., with scribe marks T3S R33½E S24 BT visible.

A pine, 12 ins. diam., bears N. 26¾° W., 121 lks. dist., with scribe marks ½ visible on partially opened blaze. (Record, N. 28° W., 123 lks.)

At the corner point

Set an iron post, 28 ins. long, 2½ ins. diam., 18 ins. in the ground, to solid rock, in a mound of stone, 4 ft. base, to top, with brass cap mkd.

T 3 S			
R 33½ E		R 34 E	
S 24		S 19	
S 25		S 30	
1975			

from which new bearing trees

A pine, 7 ins. diam., bears S. 63° W., 106 lks. dist., mkd. T3S R33½E S25 BT.

A pine, 12 ins. diam., bears N. 74¼° W., 96 lks. dist., mkd. T3S R33½E S24 BT.

Remonumentation of Certain Original Corner Points,  
T. 3 S., R. 33½ E., Willamette Meridian, Oregon

## CHAINS

Deposit corner stone alongside iron post.

The ¼ sec. cor. of secs. 19 and 24, determined at record bearing and distance from the remains of the original bearing trees:

A pine, 8 ins. diam., bears S. 50° W., 9 lks. dist., with scribe marks ¼ S BT visible on partially healed blaze.

At the corner point

Set an iron post, 28 ins. long, 2½ ins. diam., 24 ins. in the ground, with brass cap mkd.

T 3 S	
¼	
R 33½ E	R 34 E
S 24	S 19
1975	

from which a new bearing tree

A fir, 15 ins. diam., bears S. 67° E., 86 lks. dist., mkd. ¼ S19 BT.

The cor. of secs. 13, 18, 19, and 24, determined at record bearing and distance from the remains of the original bearing trees:

A decayed pine stump, 12 ins. diam., bears N. 19° E., 210 lks. dist., with scribe marks T3S R34E S18 visible on open blaze.

A root hole, bears N. 59° W., 53 lks. dist., with a down and decayed pine alongside, 12 ins. diam., with scribe marks T3S R33½E S13 visible on open blaze.

At the corner point

Set an iron post, 28 ins. long, 2½ ins. diam., 10 ins. in the ground, to solid rock, in a mound of stone, 4½ ft. base, to top, with brass cap mkd.

T 3 S	
R 33½ E	R 34 E
S 13	S 18
S 24	S 19
1975	

from which new bearing trees

A pine, 10 ins. diam., bears N. 1½° E., 105 lks. dist., mkd. T3S R34E S18 BT.

A pine, 12 ins. diam., bears S. 28° E., 162 lks. dist., mkd. T3S R34E S19 BT.

A pine, 8 ins. diam., bears S. 84° W., 79 lks. dist., mkd. T3S R33½E S24 BT.

A pine, 10 ins. diam., bears N. 67½° W., 34 lks. dist., mkd. T3S R33½E S13 BT.

Remonumentation of Certain Original Corner Points,  
T. 3 S., R. 33½ E., Willamette Meridian, Oregon

CHAINS

The cor. of secs. 7, 12, 13, and 18, determined at record bearing and distance from the remains of the original bearing trees:

A root hole, bears N. 35° E., 26 lks. dist., with a down and decayed western larch alongside, 12 ins. diam., with scribe marks BT visible on decayed blaze.

A decayed western larch snag, 24 ins. diam., bears S. 42° E., 16 lks. dist., with scribe marks S R34E S18 visible on decayed blaze.

A pine snag, 9 ins. diam., bears N. 19° W., 42 lks. dist., with scribe marks T3S R33½E S12 BT visible on partially healed blaze.

At the corner point

Set an iron post, 28 ins. long, 2½ ins. diam., 24 ins. in the ground, with brass cap mkd.

T 3 S	
R 33½ E	R 34 E
S 12	S 7
S 13	S 18
1975	

from which new bearing trees

A fir, 17 ins. diam., bears N. 35¼° E., 57 lks. dist., mkd. T3S R34E S7 BT.

A western larch, 18 ins. diam., bears S. 42¼° E., 63 lks. dist., mkd. T3S R34E S18 BT.

A fir, 12 ins. diam., bears S. 55½° W., 35½ lks. dist., mkd. T3S R33½E S13 BT.

A fir, 10 ins. diam., bears N. 15¼° W., 18 lks. dist., mkd. T3S R33½E S12 BT.

---

Subdivision, T. 3 S., R. 33½ E.,  
Willamette Meridian, Oregon

---

(Remonumenting corners established by  
Rufus S. Moore, Deputy Surveyor, in 1882)

---

The ¼ sec. cor. of secs. 25 and 26, monumented with a basalt stone, 12 x 8 x 6 ins., loosely set 2 ins. in the ground, no marks visible, from which the remains of the original bearing trees:

A fir snag, 12 ins. diam., bears East, 3 lks. dist., with healed blaze.

A western larch snag, 7 ins. diam., bears N. 70° W., 8 lks. dist., with scribe marks ¼ S visible on open blaze.

At the corner point

Set an iron post, 28 ins. long, 2½ ins. diam., 24 ins. in the ground, with brass cap mkd.

Form 9180-8  
(March 1969)

UNITED STATES  
DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT

FIELD ASSISTANTS

NAMES	CAPACITY
David E. Allen	Engineering Aid
Dennis L. Thompson	Engineering Aid

CERTIFICATE OF SURVEY

(I) ~~(W&X)~~ A. Joseph Garrison, Cadastral Surveyor, HEREBY CERTIFY upon honor that, in pursuance of special instructions bearing date of the 3rd day of May, 19 57, (I) ~~(W&X)~~ have remonumented certain original corner points, township 3 south, range 33 1/2 east,

of the Willamette Meridian, in the State of Oregon, which are represented in the foregoing field notes as having been executed by (me), ~~(us)~~ and under (my) ~~(our)~~ direction; and that said survey has been made in strict conformity with said special instructions, the Manual of Instructions for the Survey of the Public Lands of the United States, and in specific manner described in the foregoing field notes.

\_\_\_\_\_  
(Date) (Cadastral Surveyor)  
July 30, 1975  
(Date) A. Joseph Garrison  
(Cadastral Surveyor)

CERTIFICATE OF APPROVAL

BUREAU OF LAND MANAGEMENT  
Washington, D.C.

The foregoing field notes of the remonumentation of certain original corner points, township 3 south, range 33 1/2 east, Willamette Meridian, Oregon,

executed by A. Joseph Garrison, Cadastral Surveyor, having been critically examined and found correct, are hereby approved.

JUN 13 1977  
(Date) Roger T. Barron  
Acting (Chief, Division of Cadastral Survey)

CERTIFICATE OF TRANSCRIPT

I CERTIFY That the foregoing transcript of the field notes of the above-described surveys in \_\_\_\_\_, is a true copy of the original field notes.

\_\_\_\_\_  
(Date) (Chief, Division of Cadastral Survey) GPO 849-626