

INDEX DIAGRAM

Township 3 South, Range 33½ East 2 2 1

6	5	4	3	2	<u>3</u> 1
				<u>4</u>	<u>3</u>
7	8	9	10	11	12
18	17	16	15	14	13
19	20	21	22	23	24
30	29	28	27	26	25
31	32	33	34	35	36

Remonumentation of Certain Original Corner Points,
T. 3 S., R. 33½ E., Willamette Meridian, Oregon

CHAINS

A fir, 19 ins. diam., bears N. 75° W., 31½ lks.
dist., mkd. T2S R33E S36 BT.

Deposit corner stone alongside iron post.

North Boundary, T. 3 S., R. 33½ E.,
Willamette Meridian, Oregon

(Remonumenting a corner established by Rufus S. Moore,
U. S. Deputy Surveyor, in 1882)

The ¼ sec. cor. of secs. 1 and 36, on the N. bdy. of the
Tp., monumented with the original unmarked basalt stone,
16 x 16 x 3 ins., loosely set in a mound of stone, 2 ft.
base, 1 ft. high, from which the only remaining original
bearing tree:

A pine, 25 ins. diam., bears S. 41° E., 202 lks.
dist., with healed blaze.

At the corner point

Set an iron post, 28 ins. long, 2½ ins. diam., 22 ins.
in the ground, with brass cap mkd.

T 2 S R 33 E

¼ S 36
S 1

T 3 S R 33½ E
1977

from which a new bearing tree

A pine, 12 ins. diam., bears N. 50° E., 43 lks.
dist., mkd. ¼ S36 BT.

Deposit corner stone alongside iron post.

(Remonumenting a corner established by Rufus S. Moore,
U. S. Deputy Surveyor, in 1882,
and redescribed by John C. Arnold,
U. S. Deputy Surveyor, in 1891)

The cor. of secs. 1, 2, 35, and 36, monumented with the
original basalt stone, 16 x 10 x 10 ins., firmly set 10
ins. in the ground, mkd. with 1 notch on E. and 2 notches
on W. edges, from which the remains of the original
bearing trees:

A pine snag, 11 ins. diam., bears S. 56° W., 36
lks. dist., with scribe marks T3S R33½E S2 BT
visible on open blaze. (Record, S. 50° W.)

A pine snag, 24 ins. diam., bears N. 48° W., 37
lks. dist., with scribe marks R33½E S35 visible
on open and burned blaze.

At the corner point

Set an iron post, 28 ins. long, 2½ ins. diam., 22 ins.
in the ground, with brass cap mkd.

Remonumentation of Certain Original Corner Points,
T. 3 S., R. 33½ E., Willamette Meridian, Oregon

CHAINS

T 2 S R 33 E
 $\frac{S\ 35}{S\ 2} | \frac{S\ 36}{S\ 1}$
 T 3 S R 33½ E
 1977

from which new bearing trees

A grand fir, 9 ins. diam., bears N. 42° E., 20
lks. dist., mkd. T2S R33E S36 BT.

A grand fir, 12 ins. diam., bears S. 70° E., 12
lks. dist., mkd. T3S R33½E S1 BT.

A grand fir, 12 ins. diam., bears S. 43° W., 17½
lks. dist., mkd. T3S R33½E S2 BT.

A grand fir, 15 ins. diam., bears N. 56½° W., 31
lks. dist., mkd. T2S R33E S35 BT.

Deposit corner stone alongside iron post.

Subdivisions, T. 3 S., R. 33½ E.,
Willamette Meridian, Oregon

(Remonumenting corners established by Rufus S. Moore,
U. S. Deputy Surveyor, in 1882)

The cor. of secs. 1, 2, 11, and 12, determined at record
bearing and distance from the remains of the original
bearing trees:

A fir, 18 ins. diam., bears S. 10° W., 7 lks.
dist., with fragmentary scribe marks visible
on partially healed blaze.

A fir, 16 ins. diam., bears N. 37° W., 17 lks.
dist., with scribe marks 3S R33E S visible
on open blaze.

At the corner point

Set an iron post, 28 ins. long, 2½ ins. diam., 24 ins.
in the ground, with brass cap mkd.

T 3 S R 33½ E
 $\frac{S\ 2}{S\ 11} | \frac{S\ 1}{S\ 12}$
 1977

from which new bearing trees

A fir, 7 ins. diam., bears N. 34½° E., 28 lks.
dist., mkd. T3S R33½E S1 BT.

A fir, 10 ins. diam., bears S. 58° E., 68 lks.
dist., mkd. T3S R33½E S12 BT.

The ¼ sec. cor. of secs. 1 and 2, determined at record
bearing and distance from the remains of the original
bearing trees:

A pine snag, 40 ins. diam., bears N. 63° E., 102
lks. dist., with scribe marks ¼ S visible on
open blaze.

CERTIFICATE OF SURVEY

(I) (~~W~~), Craig L. Wanless, Cadastral Surveyor, HEREBY CERTIFY upon honor that, in pursuance of special instructions bearing date of the 3rd day of May, 19 57, (I) (~~W~~) have remonumented certain original corner points, township 3 south, range 33½ east,

of the Willamette Meridian, in the State of Oregon, which are represented in the foregoing field notes as having been executed by (me), (~~us~~) and under (my) (~~our~~) direction; and that said survey has been made in strict conformity with said special instructions, the Manual of Instructions for the Survey of the Public Lands of the United States, and in specific manner described in the foregoing field notes.

January 16, 1978 (Date) Craig L. Wanless (Cadastral Surveyor)

CERTIFICATE OF APPROVAL

BUREAU OF LAND MANAGEMENT Washington, D.C.

The foregoing field notes of the remonumentation of certain original corner points, township 3 south, range 33½ east, Willamette Meridian, Oregon, executed by Craig L. Wanless, Cadastral Surveyor, having been critically examined and found correct, are hereby approved.

AUG 17 1978 (Date) Acting (Chief, Division of Cadastral Survey)

CERTIFICATE OF TRANSCRIPT

I CERTIFY That the foregoing transcript of the field notes of the above-described surveys in, is a true copy of the original field notes.

(Date) (Chief, Division of Cadastral Survey) GPO 849-626