

See page 183  
for title page

22.

FIELD NOTES.

On the survey of the Eastern  
Lines of Tps 3-4-5 S. R. 34 E  
Tps 3-4-5. S. R. 33 1/2 E Willamette Meridian,  
Oregon, as surveyed by Rufus J. Moore  
U. S. Deputy Surveyor, under his Contract No. 451.  
dated June 12<sup>th</sup> 1882  
Survey commenced Oct 13<sup>th</sup> 1882  
Survey completed December 1<sup>st</sup> 1882

NAMES AND DUTIES OF ASSISTANTS.

....., Compassman.  
James Guttridge, Chainman.  
John Guttridge, Chainman.  
....., Chainman.  
....., Chainman.  
Joe Parodi, Axeman.  
....., Axeman.  
....., Flagman.

Copy  
23  
See page 184 for  
these oaths

PRELIMINARY OATHS OF ASSISTANTS.

We, James Guttridge &  
John Guttridge

do solemnly swear that we will faithfully execute the duties of Chain Carriers, that we will level the chain over even and uneven ground, and plumb the tally pins, either by sticking or dropping the same; that we will report the true distance to all notable objects, and the true length of all lines that we will assist in measuring, to the best of our skill and ability, and in accordance with the instructions given us in

the survey of the Ontario

lines of Tps 3-4 & 5  
S. R. 33 1/2 & 34 0 Willamette Meridian, Oregon.

James Guttridge, Chainman.  
John Guttridge, Chainman.  
\_\_\_\_\_, Chainman.  
\_\_\_\_\_, Chainman.

Subscribed and sworn to before me, this 15<sup>th</sup>  
day of August 1882

[SEAL.]

Rufus S. Morro  
Notary Public

We, Joe Parodi and

do solemnly swear that we will well and truly perform the duties of Axemen in the establishment of corners and other duties, according to instructions given us, and to the best of our skill and ability

in the survey of the Ontario of Townships  
3-4-5 S R 33 1/2 & 34 0 Willamette Meridian, Oregon.

Joe Parodi, Axeman.  
\_\_\_\_\_, Axeman.

Subscribed and sworn to before me, this 15<sup>th</sup>  
day of August 1882

[SEAL.]

Rufus S. Morro  
Notary Public

West body

113

Enterings of T. 3 South R. 33 1/2 East

Willamette Meridian, Oregon.

North on West boundary  
of Sec. 3

Var 21° E

- 2631 The corner to Secs 1 and  
12 T. 3 S R. 33 E.
- 3961 Old road bears NW. & SE
- 6631 The 1/4 Sec corner
- 8000 Set post 4 1/2 ft long 4 in  
square 24 in in ground  
for corner to Townships 2 and  
3 S Range 33 1/2 E and marked  
R 33 1/2 E on E  
T. 2 S S 34 on N and  
T. 3 S S 3 on S face with  
6 notches on S & 3 notches  
on E edges
- from which  
a pine 6 in diam bears N 27°  
E 42 lbs dist marked T. 2 S.  
R 33 1/2 E S 34 B.T.
- A pine 5 in diam bears  
S 67° W 15 lbs dist marked

114 West belay

114  
Containing of T. 3 South R. 33 1/2 East

Willamette Meridian, Oregon.

T. 3 S R 33 E S. 1 B.T.

a pine 4 in diameter bears  
S 40° E 19 lbs dist marked

T. 3 S R 33 1/2 E S 3 B.T.

Land high & mountainous

Soil 2d rate

Heavily timbered with

pine & fir 80. chs.

West body ~~XXB~~

155

125

Extension of T. 3 S R. 34 E

Willamette Meridian, Oregon.

North bet. Secs 1 & 6

va 20° E.

- 40.00 Set a basalt stone 12 x 10 x 8 ins 8 ins  
in the ground for 1/4 Sec cor.  
marked 1/4 on W. face. from which  
A fir 10 ins diam bears S 74° E 108 lks dist.  
marked 1/4 S B. T.
- A fir 12 ins diam bears S 82° W 65 lks dist.  
marked 1/4 S B. T.
- 79.00 Spring branch 3 lks into runs N. E.
- 80.00 Set a post 4 1/2 ft long 4 ins square  
24 ins in the ground for cor to  
Tps 2 & 3 S R 33 1/2 and 34 E.  
marked.
- T 2 S. S 31 on N. E. R 34 E S 6 on S E  
T 3 S S. 1. on S W T R 33 1/2 E S 36 on N. W.  
faces with 6 notches on each edge  
from which
- A pine 11 ins diam bears N 65° E 39 lks dist.  
marked T 2 S R 34 E S 31 B. T.
- A Willow 6 ins diam bears S 76° E 38 lks dist.  
marked T 3 S R 34 E S 6 B. T.

126

~~126~~

156

Extensior of T. 3 S R. 34 E

Willamette Meridian, Oregon.

A tamarack 27 ins. diam. bears S 43° W. 11 lbs dist-  
marked T 3 S R 33½ E S 1 B. T

A pine 11 ins. diam. bears N 24° W 36 lbs dist-  
marked T 2 S R 33½ E S 36 B. T.

Land - hilly

Soil - red soil

Heavily timbered with pine fir  
and tamarack 80 chs -

Nov 9<sup>th</sup> 1882

North body 1218

145

Exteriors of T. 3 S R. 33½ E

175

Willamette Meridian, Oregon.

From the cor to Tps 2 & 3 S. Rs. 33½ and 34 E. I run.

West on a random line on the south boundary of sees 36, 35 & 34  
va 190° 30' E

I set temporary corners at every 40 and 80 chs. and at 2 miles 6 chs and 70 lks intersect the West boundary of the Township 70 lks South of Cor to Tps 2 & 3 S. R 33½ E.

The correction for the true line will therefore be 34 lks north to the mile and its bearing will be 89° 46' E.

From the cor to Tps 2 & 3 S. R 33½ E I run

89° 46' E on a true line bet- sees 3 & 34  
va 20° E.

6.70 Set a post 4 ft. long 4 ins square 24 ins in the ground for cor to sees.

146

176

1818

Extremities of T. 3 S R. 3 3 1/2 E

Willamette Meridian, Oregon.

North boundary.

2, 3, 34 & 35. marked

T 2 S. S 35. on N. E

R 3 3 1/2 E S 2 on S E

T 3 S S 3 on S W and

S 34 on N W. faces with 2 notches  
on the E. and 1 notch on W.

edges. from which

A pine 30 ins diam. bears N 35° E 33 lbs dist.

marked T 2 S R 3 3 1/2 E S 35. B. T.

A pine 36 ins diam. bears S 73° E 12 lbs dist.

marked T 3 S R 3 3 1/2 E S 2 B. T.

A tamarack 24 ins. diam. bears S 40° W 6 lbs dist.

marked T 3 S R 3 3 1/2 E S 3 B. T.

A fir 8 ins. diam. bears N 31° W 22 lbs dist.

marked T 2 S R 3 3 1/2 E S 34 B. T.

Land hilly

Soil 2d rate

Heavily timbered with pine fir  
and tamarack -



Extensions of T. 3 S R. 33½ E

Willamette Meridian, Oregon.

North boundary

S 89° 46' E, on true line bet- Secs 2 + 35  
va 20° E

40.00 Set a basalt-stone 13x12x6 ins 9 ins in  
the ground for ¼ sec cor. marked ¼ on  
N. face. from which

A tamarack 10 ins. diam. bears N 50° E 60 lks. dist.  
marked ¼ S B. T.

A tamarack 8 ins. diam. bears S 31° W 100 lks dist-  
marked ¼ S B. T.

80.00 Set a basalt-stone 16x10x10 ins 11 ins in  
the ground for cor to Secs 1, 2, 35 +  
36. marked with 1 notch on the E  
and 2 notches on N. edges.  
from which

A pine 18 ins diam. bears N 54° E 50 lks. dist.  
marked T 2 S R 33½ E S 36 B. T.

A pine 10 ins. diam bears S 29° E 75 lks dist-  
marked T 3 S R 33½ E S 1 B. T.

A pine 10 ins. diam. bears S 51° W 36 lks dist-  
marked T 3 S R 33½ E S 2 B. T.

A pine 20 ins. diam. bears N 48° W 37 lks  
marked T 2 S R 33½ E S 35 B

148

North body

XIV

178

Esterions of T. 3 S

R. 33½ E

Willamette Meridian, Oregon.

Land hilly + Soil 2d rate -  
 Heavily timbered with pine, fir and  
 tamarack 80 cks -

S 89° 46' E on a true line bet sec 1 & 36  
 on 20° E

40.00 Set a basalt-stone 16x16x3 ins. 11 ins.  
 the ground for ¼ sec cor marked by  
 N. face. from which

A pine 30 ins diam. bears S 41° E. 202 lks dist  
 marked ¼ S B. T.

A pine 18 ins diam. bears N 36° E 234 lks. dist  
 marked ¼ S B. T.

60.00 Wagon road course N & S.

80.00 The cor to Tps. 2 & 3 S R. 33½ & 34 E

Land rolling - Soil 2d rate -  
 Heavily timbered with pine, fir 80 cks

### General Description

The land in this township is high and  
 mountainous. covered with a fine  
 quality of timber + Dec 1<sup>st</sup> 1882

Copy  
180  
see page 220  
for these oaths

### FINAL OATHS FOR SURVEYS.

A list of the names of the individuals employed by Rufus S. Moore, U. S. Deputy Surveyor, to assist in running, measuring and marking the lines and corners described in the foregoing field notes of the survey of the Enterum lines of Trs 3-4-5 S. R. 33 1/2 & 34 E. 2d Willamette Meridian, Oregon, showing the respective capacities in which they acted:

\_\_\_\_\_, Compassman.  
James Gutteridge, Chainman.  
John Gutteridge, Chainman.  
\_\_\_\_\_, Chainman.  
\_\_\_\_\_, Chainman.  
Joe Parodi, Axeman.  
\_\_\_\_\_, Axeman.  
\_\_\_\_\_, Flagman.

### FINAL OATHS OF ASSISTANTS.

We hereby certify that we assisted Rufus S. Moore, U. S. Deputy Surveyor, in surveying all those parts or portions of the Enterum lines of Trs 3-4-5 S. R. 33 1/2 & 34 E. 2d Willamette Meridian, Oregon, as are represented in the foregoing field notes as having been surveyed by him and under his direction; and that said survey has been, in all respects, to the best of our knowledge and belief, well and faithfully surveyed, and the corner monuments established, according to the instructions furnished by the U. S. Surveyor General of Oregon.

\_\_\_\_\_, Compassman.  
James Gutteridge, Chainman.  
John Gutteridge, Chainman.  
\_\_\_\_\_, Chainman.  
\_\_\_\_\_, Chainman.  
Joe Parodi, Axeman.  
\_\_\_\_\_, Axeman.  
\_\_\_\_\_, Flagman.

Subscribed and sworn to before me, this 21<sup>st</sup> day of November 1882

[SEAL] Rufus S. Moore  
Notary Public

Copy  
181

See page 22!  
for this oath

FINAL OATH OF DEPUTY SURVEYOR.

I, Rufus S Moore

United States Deputy Surveyor, do solemnly swear that in pursuance of

instructions received from James C. Tolman

U. S. Surveyor General for Oregon, bearing date of the 28<sup>th</sup>

day of June, 1882, I have well, faith-

fully and truly, in my own proper person, and in strict conformity with  
the instructions furnished by the U. S. Surveyor General for Oregon, the  
Surveying Manual, and the Laws of the United States, surveying all those

parts or portions of the Eastern line of  
Tps 3-4-5 S. R. 33 1/2 & 34 East

Willamette Meridian, in the State of Oregon, as are represented in the  
foregoing Field Notes as having been surveyed by me and under my di-  
rections; and I do further solemnly swear that all the corners of said sur-  
vey have been established and perpetuated in strict accordance with the  
Surveying Manual, Printed Instructions, the Special Written Instructions  
of the U. S. Surveyor General for Oregon, and in the specific manner de-  
scribed in the Field Notes, and that the foregoing are the *true* Field Notes  
of such survey, and should any fraud be detected I will suffer the penalty  
of perjury under the provisions of an Act of Congress approved August  
8th, 1846.

Rufus S Moore  
U. S. Deputy Surveyor.

Subscribed and sworn to before me, this 10<sup>th</sup>

day of July, 1883

Barnford Robb  
Notary Public

(Seal)

182

OFFICE U. S. SURVEYOR GENERAL,

Portland, Oregon, *Feb 1,* 1884

The following Field Notes of the Survey of the

*Outer line of Tps*

*3 - 4 - 5 South Range*

*33½ and 34 O Will Met*

*Oregon*  
executed by

*Refus S. Moore*

under his Contract No. *451*, dated *June*

*12<sup>th</sup>* 1882, having been critically examined,

the necessary corrections and explanations made, the said

Field Notes and the survey they describe are hereby approved.

*James C. Tolson*

Surveyor General.