

Conts - No 84

Exterior Lines

Eya,
Coster

Exterior Lines

N. H. Gates

Manuscript compared with
Washington transcript

Washington transcript made
H. P. J.

Manuscript compared with
Notes T. C.

We, Allen Thompson, and Lester Potter,
do solemnly swear that we will faithfully
execute the duties of chain carriers; that we
will level the chain upon uneven ground,
and plumb the tally pins, whether by sticking
or dropping the same; that we will report
the true distance to all notable objects, and
the true length of all lines that we
assist in measuring, to the best of our
skill and ability.

Allen Thompson (chairman)
Lester Potter (chairman)

Subscribed and sworn to before me this
eighteenth day of August A.D. 1859.

W. C. Murray
County Clerk
Wasco County Oregon

I, Benjamin Athy, do solemnly swear that I will well and truly perform the duties of Arman according to instructions given me, and to the best of my skill and ability.

Benjamin Athy (Arman)
Subscribed and sworn to before me,
this eighteenth day of August A.D.
1859.

Wm. Mowbray
County Clerk
Wasco County Oregon

I, J. A. Pownall, do solemnly swear that
I will faithfully execute the duties of
compassman according to instructions given
me, and to the best of my skill and ability

J. A. Pownall (Compassman)

Sworn and subscribed to before me this
eighteenth day of August A. D. 1859.

W. C. Murray
County Clerk
Wasco County Oregon

J/D

No. N. B. 28. 2. No. N. B. 29. 2. No. N. B. 30. 2.

27	26	25	24	23	22	16	15	15	14	14	13	8	7	7	6	5
26	5	4	3	2	1	56	5	4	3	2	1	5				
207	8	9	10	11	12	7	8	9	10	11	12					
19	18	17	16	15	14	13	12	11	10	9	8					
18	19	20	21	22	23	24	19	20	21	22	23	24				
18	30	29	28	27	26	25	30	29	28	27	26	25				
18	31	32	33	34	35	36	31	32	33	34	35	36				

12 ¹² N. 3 N. of R. 29 E.

chains North between Sections 7, and 12,

Variation $19^{\circ} 30'$ East

40.00 Set post for $\frac{1}{4}$ section corner in mound of earth, established as per instruction.

80.00 Set post for corner to Sections 6, and 7, 1, & 12, in mound of earth, established as per instructions.

Sand level prairie bottoms;
Soil good 2nd rate.

chains North between Sections 6, and 1,

Variation 20° East

40.00 Set post for $\frac{1}{4}$ section corner, in mound of earth, established as per instructions

45.25 Slough 2 chains wide, course N.W.

54.00 Slough 2 chains wide, course N.W.

80.00 Set post for corner to Townships 3, and 4, North, of Ranges 28, and 29 East, in earth mound, established as per instructions.

Sand level prairie bottoms;
Soil 1st rate.

20 20
T 3 N of R. 28 E.

North between Sections 7 & 12

Variation $19^{\circ} 30'$ East.

chains

40.00 Set post for $\frac{1}{4}$ Sec. corner in mound of
Earth &c. &c. as per Instructions

80.00 Set post for corner to Secs 6, 7, 1, & 12 in
earth mound built as per Instructions

Land level:

Soil 2nd rate:

North between Sections 1 & 6,

chains

Variation $20^{\circ} 20'$ East.

40.00 Set post for $\frac{1}{4}$ Sec. corner in mound of
Earth &c. &c. as per Instructions.

80.00 Set post for corner to Townships 3 & 4 North
of Ranges 27 & 28 East and established
earth mound, as per Instructions

Land level:

Soil 2nd rate & sandy.

¹⁷
C. 3 N. of R. 28 E.

21
21

chains

From the established corner to Townships
3 and 4 North of Ranges 27 and 28 East,
run East on a random line on the
North boundaries of sections 6, 5, 4, 3, 2, and 1.

Variation $20^{\circ} 30'$ East

Set temporary half mile and mile posts
at every 40. and 80. chains, and at 5 miles,
76. chains, to a point 4.20 chains North of
the corner to Townships 3 and 4 North of
Ranges 28 and 29 East.

The correction will, therefore, be 4 chains
West, and 70 links South per mile, and
the true course of line $N. 89^{\circ} 30' W.$

^m
V. 3 N. of R. 28 E.

- chains N. $89^{\circ} 30' W$ on true line between Secs 1 & 36
²³ V. 3 N. R. 28 E.
- 16.50 Spring branch, 28 links wide, course North.
- 40.00 Set post for $\frac{1}{4}$ Section corner in mound of earth, with charred stake, trenches, pits &c. as per instructions.
- 44.50 Spring branch, 30 links wide, course North.
- 70.00 Leave bottom. Course N.W. and S.E.
- 80.00 Set post for corner to sections 1, and 2, 35 and 36 in mound of earth, with charred stake, trenches, pits &c. as per instructions.

Land level.

Soil 1st rate.

October 11th 1859

N. 3 N. of R. 28 E.

23.

23.

Chains

N. $89^{\circ} 30' W.$ on true line between Sections
2 and 35

Variation $19^{\circ} 45' East$

40.00

Set post for Dr. Section Corner
in mound of earth, established
as per instructions.

80.00

Set post for Corner to Sections
2, and 3, 34, and 35, in Earth mound
established as per instructions.

Land level.

Soil good 2nd rate.

L

24

24

24

V. S. N. of R. 28 E.

chain

N. 89° 30' W. on true line between
Sections 3 and 34.

Variation 20° 10' East

40.00

Set post for $\frac{1}{4}$ Section corner in
mound of earth, established as
per Instructions.

80.00

Set post for corner to sections 3, and 4,
33 and 34, in mound of earth established
as per Instructions

Sand rolling.

Soil 2nd rate, very sandy and
mostly covered with Cactus.

N. 3 N. of R. 28 E.

25
25

chains

N. $89^{\circ} 30' W.$ on true line between
Sections 4, and 33.

Variation $20^{\circ} 05'$ East

40.00

Set post for $\frac{1}{4}$ Section Corner, in
mound of Earth, established as
per Instructions. From this corner
the mouth of Butter Creek bears $N 15^{\circ} W$;
about $1\frac{1}{2}$ miles distant; also a noted
point of Rocks on the Columbia River,
near the mouth of the Umatilla River,
bears due North, and is about 9 miles
distant.

80.00

Set post for corner of Sections 4, and 5,
32, and 33, in mound of Earth, established
as per Instructions.

Land gently rolling.

Soil 2nd rate, and sandy - and
partially covered with Cactus.

26 ²⁶ m
~~25~~ N. & N. of R. 28 E.

chains

N. $89^{\circ}30'W$. An true line between
Secs 5 and 32.

Variation $20^{\circ}15'$ East

- 3.00 Enter bottoms of Butter Creek; course N. & S.
16.50 Butter Creek, course N.E. 15 links wide.
40.00 Set post for corner to 4 sections, ~~in~~ in
mound of earth, established as
per instructions
79.00 Leave bottom, course N. $10^{\circ}E$, and S.W.
80.00 Set post for corner to sections
5. and 6. 31. and 32. in mound of earth
established as per instructions.

Land nearly level;
Soil 1st and 2nd rates.

3 N. of R. 28 E.

27

27

Chains

N. 89° 30' W. on true line between
Sections 6 and 31.

Variation 20° 15' East.

40.00
40.00

Set post for $\frac{1}{4}$ Section Corner in
mound of earth, established as per
Instructions.

76.00
76.00

Intersect the Corner to Townships ³⁴ 3 North
of Ranges 27, & 28 East.

Land gently rolling,
Soil 2nd rate, and sandy
October 12th 1859

28 28
T. S. N. of R. 28 E.

General description.

This Township contains but little 1st rate land, its soil being chiefly ^{composed} of a very sandy loam, of too light a nature to admit of a profitable cultivation; and is entirely destitute of timber.

It is generally covered with bunch grass, and will therefore make reasonably good pasturage; but in this respect, it will not be greatly advantaged by the generous beds of Cactus scattered over its surface.

List of Names

A list of the names of the individuals employed to assist in running, measuring, or marking the lines and corners described in the foregoing field notes of Township No 3 North of the base line of Range No 28 East of the Willamette Meridian, showing the capacity in which each acted

Allen Thompson,	(Chainman)
Bester Potter,	(Chainman)
Benjamin Athey,	(Axman)
J. A. Purnell,	(Compassman)

~~W. S. H. of R. 20 E.~~

35

chains

North between Sections 14 and 21.

Variation $20^{\circ}30' E.$

40.00

Set post for $\frac{1}{4}$ Section Corner in a mound of earth established as per Instructions.

80.00

Set post for corner to sections 18 and 19, 13 & 24, and drove charred stake, and built mound in road with pits, trenches, &c. Course of Road, E. & W.

Land gently rolling Soil 2nd rate.

We hereby certify that we assisted in surveying the exterior boundaries of Townships Number Three North of the base line of Ranges number Twenty eight, Twenty-nine, and Thirty East of the Willamette Meridian, and that said townships have been in all respects, to the best of our knowledge and belief, well and faithfully surveyed, and the boundary monuments planted according to the instructions furnished by the Surveyor General.

- Allen Thompson (Chairman)
- Lester Patter (Chainman)
- Benjamin They (Chainman)
- J. A. Fournall (Compassman)

Subscribed and sworn to before me, this Eighteenth day of October A. D. 1859.

W. C. Moody
 County Clerk
 Wasco County Oregon

I, N. W. Gates, deputy Surveyor, do solemnly swear that, in pursuance of a contract with W. W. Chapman, Surveyor of the public lands of the United States in the State of Oregon, bearing date the twenty ~~second~~ day of July A. D. 1859, and in strict conformity to the laws of the United States and the instructions furnished by the said Surveyor General, I have faithfully surveyed the exterior boundaries of Townships 3 North, ^{of the base line} of Ranges number 28, 29, and 30, East of the Willamette meridian, in the State aforesaid, and do further solemnly swear that the foregoing are the true and original field notes of such Survey. N. W. Gates

Deputy Surveyor.

Subscribed & Sworn to before me
this 28th day Oct 1859.

F. S. Hallard, Clerk
of Circuit Court for Clackamas
Co., Oregon

by A. Hallard, depy

Surveyor General's Office
Eugene City January 3 1866

The foregoing field notes of the
Survey of the Exterior lines of
Township T³ N³ of Ranges
T²⁸ E²⁹ & E³⁰ East of the
Willamette Meridian, Oregon
executed by N^o 46 Gates, Deputy
Surveyor, under his Contract of
the 2nd day of July 1859
having been critically examined
the necessary corrections and expla-
-ations made, the said field notes
and the Survey they describe are
herby approved

W. W. Chapman
Surveyor General of Oregon

Res No. 3. Exch

47

Subdivisions

Examination & Correction

Field notes of the Subdivision lines
in Township No. 3 North of Range 29
East of the Willamette Meridian
in the State of Oregon by W. H.
Gates deputy Surveyor under his
Contract No. 84 bearing date the
22nd day of July 1859

commenced September 15th 1859
completed September 22nd 1859

Washington transcript made
by P. J.

Transcript compared
with Notes. T. C.