



Field Notes of the Resurvey
 of Exterior boundary lines of Townships
 4 North of Range 27 East Township
 5 North, Ranges 31 & 32 East and
 fractional Townships, 6 North of the
 Base line of Ranges 31, 32 & 33 East
 of the Willamette Meridian, executed
 by Nicholas O. Walden, Deputy
 Surveyor under his contract No
 209, bearing date the 6th day of
 July 1874.

Commenced Oct. 23^d 1874.
 Completed Decemb. 9th 1874.

Index.

Referring the lines to the pages of the Field notes

T. S. N. R. 31 C.

6.	5	4.	3	2	1	6.	
						12	5
						13	5
						24	5
						25	4.
31	32	33	34.	35	36		4
8	8	9	9	9	9.		

Index:

Referring the lines to the pages of the Field notes

T. 5. N. R. 32. E.

6	5	4	3	2	1	12
					12	11
					13	11
					24	11
					25	10
31	32	33	34	35	36	10
14	14	15	15	15	15	

Index:

Referring the lines to the pages of the Fieldnotes.

J. H. N. R. 27. C.

				27	27.
25	6.			2	1. 21.
24.	7				12. 20
23	18				13. 20
23	19.				24. 19
22	30.				25. 19
22	31.				36. 18.

Resurvey of the Exterior Boundaries of Township

The Corners on the East and West-
Exterior Boundaries of this Township
being obliterated I am compelled
to make a resurvey of the same,
(See Note after line between Secs. 25
& 36, Subdivision of T. 4 N. R. 27 E.)

Accordingly I begin at
the Corner to Townships 3 & 4 North
Ranges 27 & 28 East and run

North on East boundary of Sec. 36

40.00 The Post- $\frac{1}{4}$ Sec. Cor.

80.00 Drove Chopped Stake and raised
mound of earth with pits &c. as
per instructions for corner Co.
Secs. 25 & 36

Drove Willow Stake 2 ft long 2 in
square in S. E. pit

Land gently rolling; Soil 2nd rate.

21 19.

4 North, Range 27 East Will. Mer. Oregon

North on East-Boundary of Sec. 25
Var. $21^{\circ} 15'$ East-

40.00 Drove charred stake and raised mound
of earth with spits &c as per instruc-
tions for $\frac{1}{4}$ Sec. Corner.

60.00 Wagon road bears E & W

80.00 Drove charred stake and raised mound
of earth with spits &c. as per instruc-
tions for corner to Secs. 24 & 25-

Drove Willow Stake 2 ft long 2 in square
in East spit.

Land gently rolling; Soil 2nd rate.

North on East Boundary of Sec. 24,
Var. $21^{\circ} 15'$ East-

40.00 Drove charred stake and raised
mound of earth with spits &c as
per instructions for $\frac{1}{4}$ Sec. corner.

80.00 Drove charred stake and raised
mound of earth with spits &c as
per instructions for corner to
Secs. 13 & 24

Drove Willow Stake 2 ft long 2 in

Resurvey of the Exterior Boundaries of Township

square in East - pit -
 Land gently rolling: Soil 2nd rate

North on East Boundary of Sec. 13

Var. 21° 00' East

40.00 Drove Chopped stake and raised mound of earth with spits &c. as per instructions for $\frac{1}{4}$ Sec. Cor.

67.00 Wagon Road bears N W + S E,

80.00 Drove Chopped Stake and raised mound of earth with spits &c. as per instructions for corner to Secs. 12 & 13

Drove Willow Stake 2 ft long 2 in square in East - pit.

Land gently rolling: Soil 2nd rate.

North on East Boundary of Sec. 12

Var. 20° 45' East

40.00 Drove Chopped stake and raised mound of earth with spits &c. as per instructions for $\frac{1}{4}$ Sec. Cor.

4 North Range 27 East - Will. Mer. Oregon

80.00 Drove charred stake and raised mound of earth with pits &c as per instructions for corner to Secs. 1 & 12

Drove Alder Stake 2 ft. long 2 in square in East pit -
Land gently rolling; Soil 2nd rate.

North on East Boundary of Sec. 1
Var. 21° 00' East

40.00 Drove charred stake and raised mound of earth with pits &c as per instructions for 1/4 Sec. Cor.

80.54 Intersect - 1st Standard - Parallel North
938 lbs West of the Standard corner to Townships 5 North Ranges 27 + 28 East, where

Drove charred stake and raised mound of earth with pits &c, as per instructions for closing corner to Townships 4 North Ranges 27 + 28 E

Drove Willow Stake 2 ft. long 2 in square in E. pit,
Land gently rolling Soil 2nd rate,
December 2nd 1874

List of Names

A list of the names of the individuals employed to assist in running, measuring and marking the lines and corners described in the foregoing field notes of the resurvey of the Exterior Boundary lines of Townships 4 North of Range 27 East, Townships 5 North of Ranges 31 & 32 East and Fractional Townships 6 North of the base line of Ranges 31, 32 & 33 East of the Willamette Meridian showing the respective capacities in which they acted.

Rufus S. Moore	Chairman
Henry Meldrum	Chairman
William H Cooper	Assessor

We hereby certify that we assisted
 Nicholas O. Madden, Deputy Surveyor in
 resurveying the Exterior boundary line
 of fractional Townships No. 6 North of
 the Ranges Nos. 31, 32 and 33 East of
 Townships No. 5 North, Ranges Nos 31 and
 32 East, and Township No. 4 North of
 the base line of Range No. 27 East of
 the Willamette Meridian in the capaci-
 ties indicated by our respective signa-
 tures, and that said Exterior bound-
 ary lines have been in all respects
 to the best of our knowledge and belief
 well and faithfully surveyed and
 the boundary monuments placed accord-
 ing to the instructions furnished by
 the Surveyor General.

Rufus S. Moore Chairman
 Henry Melvin Choquian
 William H. Cooper Clerk

Subscribed and sworn to before me a Notary
 Public, this 12th day of December 1874

John W. Eldrum
 Notary Public

John W. Eldrum
 Notary Public

U.S. Surveyor General's Office
Eug. Portland Oregon
June 23^d 1875

The foregoing field notes of the survey ~~made~~
the Re-Survey of the Exterior lines of T 4 N
R 27 E Will. Mer. Oregon and of the
Standard Parallel in R 27 E have
executed by N. O. Walden U.S. Deputy
Surveyor having been critically ex-
amined the necessary corrections and
explanations made the said field
notes and the surveys they describe
are hereby approved

Ben Simpson
Sur Gen of Or.

33

I Nicholas O. Walden, Deputy Surveyor do solemnly swear that in pursuance of a contract with Benjamin Simpson W. S. Surveyor General for the State of Oregon bearing date the 6th day of July 1874, and in strict conformity to the laws of the United States and the instructions furnished by the said Surveyor General, I have faithfully resurveyed the Exterior Boundaries of Township 4 North, Range 27 East; Townships 5 North, Ranges 31 & 32 East and ~~Townships~~ Townships 6 North of the base line of Ranges 31, 32 and 33 East of the Willamette Meridian in the State aforesaid, and do further solemnly swear that the foregoing are the true and original field-notes of such Survey.

Nicholas O. Walden
Deputy Surveyor

Subscribed and sworn to by the above named Nicholas O. Walden, Deputy Surveyor before me a Notary Public on this the 12th day of December 1874

John W. Meldrum
Notary Public.

Meldrum
NOTARY PUBLIC