

We, Allen Thompson, and Lester Potter,
do solemnly swear that we will faithfully
execute the duties of chain carriers; that we
will level the chain upon uneven ground,
and plumb the tally pins, whether by sticking
or dropping the same; that we will report
the true distance to all notable objects, and
the true length of all lines that we
assist in measuring, to the best of our
skill and ability.

Allen Thompson (chairman)
Lester Potter (chairman)

Subscribed and sworn to before me this
eighteenth day of August A.D. 1859.

W. C. Murray
County Clerk
Wasco County Oregon

I, Benjamin Athy, do solemnly swear that I will well and truly perform the duties of Arman according to instructions given me, and to the best of my skill and ability.

Benjamin Athy (Arman)
Subscribed and sworn to before me,
this eighteenth day of August A.D.
1859.

Wm. Mowbray
County Clerk
Wasco County Oregon

I, J. A. Pownall, do solemnly swear that I will faithfully execute the duties of compassman according to instructions given me, and to the best of my skill and ability

J. A. Pownall (Compassman)

Sworn and subscribed to before me this eighteenth day of August A. D. 1859.

W. C. Murray
County Clerk
Wasco County Oregon

J/D

1833 N. B. 28. 2
1833 N. B. 29. 2.
1833 N. B. 30. 2.
1833 N. B. 31. 2.

27	26	25	24	23	22	16	15	15	14	14	13	8	7	7	6	5
26	5	4	3	2	1	56	5	4	3	2	1	5				
207	8	9	10	11	12	7	8	9	10	11	12	5				
19	18	17	16	15	14	13	12	11	10	9	8	3				
18	19	20	21	22	23	24	19	20	21	22	23	24	3			
18	30	29	28	27	26	25	30	29	28	27	26	25	2			
18	31	32	33	34	35	36	31	32	33	34	35	36	2			

4
4

3 N. of R. 30 E.

chains North between sections 7 and 12.

Variation $19^{\circ}50'$ East.

40.00 Set post for $\frac{1}{4}$ Sec. corner in earth mound established as per Instructions.

80.00 Set post for corner to Sections 6, and 7, 1, and 12, and established same in earth mound as per Instructions.

Land level grass plains;

Soil good 2nd rate;

chains North between Sections 1 and 6.

Variation 20° East

40.00 Set post for $\frac{1}{4}$ section corner in earth mound established as per Instructions.

80.00 Set post for corner to ^{ng} Townships 3, and 4, north of Ranges 29 and 30 East, and established the same in earth mound as per Instructions.

Land level;

Soil good 2nd rate.

September 10th 1859

12

12 pp.

S. 3 N. of R. 29 E.

chains

North between Sections 7, and 12,

Variation $19^{\circ} 30'$ East

40.00

Set post for $\frac{1}{4}$ section corner in mound of earth, established as per instruction.

80.00

Set post for corner to Sections 6, and 7, 14, 12, in mound of earth, established as per instructions.

Sand level prairie bottoms;
Soil good 2nd rate.

chains

North between Sections 6, and 4,

Variation 20° East

40.00

Set post for $\frac{1}{4}$ section corner, in mound of earth, established as per instructions

45.25

Slough 2 chains wide, course N.W.

54.00

Slough 2 chains wide, course N.W.

80.00

Set post for corner to Townships 3, and 4, North, of Ranges 28, and 29 East, in earth mound, established as per instructions.

Sand level prairie bottoms;
Soil 1st rate.

T. & N. of R. 29 E.

13

13

From the established corner to Townships 3 and 4, north of Ranges 28, and 29, East, Run East on a random line on North boundaries of Secs 6, 5, 4, 3, 2, and 1,

(Set temporary half mile and mile post at every 40, and 80, chains) and at 6 miles, 6 chains, and 36 links intersected the east boundary of Sp. 2.52 chains south of corner to Townships 3, and 4, North of Ranges 29, and 30, East. The correction will, therefore, be 6.36 chains East and 43 links South per mile, and the true Course of line S. 89° 42' W.

chains

S. 89° 42' W. on true line between Sections 1, and 36,

Variation 20° 15' East

40.00 Set post for $\frac{1}{4}$ Section corner in mound of earth, established as per Instructions

80.00 Set post for corner to sections 1, and 2, 35 & 36 in mound of earth, established as per Instructions.

Land gently rolling.
Soil 2nd rate.

14. ¹⁴ N 3 N of R. 29 E

chains S 89° 42' W. on true line between Sec^s 2, and 35.

Variation 20° 20' East

40.00 Set post for $\frac{1}{4}$ Section Corner, and established same in earth mound as per instructions

80.00 Set post for Corner to Sections 2, and 3, 34 and 35, in earth mound, and established same as per instruction.

Land gently rolling.

Soil 2nd rate.

chains S 89° 42' W. on true line between Sec^s 3, and 34.

Variation 20° 35' East

40.00 Set post for $\frac{1}{4}$ Section Corner in mound of earth, established as per instructions.

80.00 Set post for Corner to Sections 3, 4, 33 & 34, in earth mound, established as per instructions.

Land gently rolling.

Soil 2nd rate.

September 13th 1859

T. 3 N. of R. 29 E

~~75~~
15

chains S 89° 42' W. on true line between Sec^s 4, and 33.
Variation 21° East

35.36 Trail, Course N. W. and S. E.

40.00 Set post for $\frac{1}{4}$ Section Corner in mound of Earth
established as per Instructions

58.00 Trail, course N. W. and S. E.

80.00 Set post for $\frac{1}{4}$ Section Corner, (in Earth mound
established as per Instruction) to sections
4, and 5, 32, and 33.

Land gently rolling; Soil 2nd rate.

chains S 89° 42' W. on true line between Sec^s 5, and 30.
Variation 20° East

40.00 Set post for $\frac{1}{4}$ Section Corner in earth mound
established as per Instructions

58.50 Enter bottom, Course N. and S.

66.50 Enter Timber, do. do.

68.75 Umatilla River, 2.00 chains wide; Course North.

75.50 Leave timber, course N. & S.

80.00 Set post for corner to sec^s 5, and 6, 31, and 32. in
earth mound established as per Instructions

Land gently rolling.

Soil 1st and 2nd rates.

16
T. 3 N. of R. 29 E

chain's S. 89° 42' W. on true line between Secs 6 and 31.

Variation 19° East.

40.00 Set post for $\frac{1}{4}$ Section Corner, in earth mound, established as per instructions

86.36 Intersect the corner to Townships 3 and 4, north of Range 28 and 29 East

Land level: Soil 1st rate:

Timber Balm: Crabapple, cherry &c. &c.

September 14th 1859

General description

This Township contains a large amount of 1st rate land; the Umatilla river flows through it from S. E. to N. W. and supplies in its bottoms plenty of timber for the purposes of the settler;

Note = For "List of Names" see that for T. 3 N. R. 28 E.

T. S. N. of R. 28 E.

General description.

This Township contains but little 1st rate land, its soil being chiefly ^{composed} of a very sandy loam, of too light a nature to admit of a profitable cultivation; and is entirely destitute of timber.

It is generally covered with bunch grass, and will therefore make reasonably good pasturage; but in this respect, it will not be greatly advantaged by the generous beds of Cactus scattered over its surface.

List of Names

A list of the names of the individuals employed to assist in running, measuring, or marking the lines and corners described in the foregoing field notes of Township No 3 North of the base line of Range No 28 East of the Willamette Meridian, showing the capacity in which each acted

Allen Thompson,	(Chainman)
Bester Potter,	(Chainman)
Benjamin Athey,	(Axman)
J. A. Purnell,	(Compassman)

~~W. S. H. of R. 20 E.~~

35

chains

North between Sections 14 and 21.

Variation $20^{\circ}30' E.$

40.00

Set post for $\frac{1}{4}$ Section Corner in a mound of earth established as per Instructions.

80.00

Set post for corner to sections 18 and 19, 13 & 24, and drove charred stake, and built mound in road with pits, trenches, &c. Course of Road, E. & W.

Land gently rolling Soil 2nd rate.

We hereby certify that we assisted in surveying the exterior boundaries of Townships Number Three North of the base line of Ranges number Twenty eight, Twenty-nine, and Thirty East of the Willamette Meridian, and that said townships have been in all respects, to the best of our knowledge and belief, well and faithfully surveyed, and the boundary monuments planted according to the instructions furnished by the Surveyor General.

- Allen Thompson (Chairman)
- Lester Patter (Chainman)
- Benjamin They (Ampman)
- J. A. Fournall (Compassman)

Subscribed and sworn to before me, this Eighteenth day of October A. D. 1859.

W. C. Moody
County Clerk
Wasco County Oregon

I, N. W. Gates, deputy Surveyor, do solemnly swear that, in pursuance of a contract with W. W. Chapman, Surveyor of the public lands of the United States in the State of Oregon, bearing date the twenty ~~second~~ day of July A. D. 1859, and in strict conformity to the laws of the United States and the instructions furnished by the said Surveyor General, I have faithfully surveyed the exterior boundaries of Townships 3 North, ^{of the base line} of Ranges number 28, 29, and 30, East of the Willamette meridian, in the State aforesaid, and do further solemnly swear that the foregoing are the true and original field notes of such Survey. N. W. Gates

Deputy Surveyor.

Subscribed & Sworn to before me
this 28th day Oct 1859.

F. S. Hallard, Clerk
of Circuit Court for Clackamas
Co., Oregon

by A. Hallard, depy

Surveyor General's Office
Eugene City January 3 1866

The foregoing field notes of the
Survey of the Exterior lines of
Township T³ N. of Ranges
T²⁸ S. 29. & 30 East of the
Willamette Meridian, Oregon
executed by N. H. Gates, Deputy
Surveyor, under his Contract of
the 2nd day of July 1859
having been critically examined
the necessary corrections and expla-
-ations made, the said field notes
and the Survey they describe are
herby approved

W. W. Chapman
Surveyor General of Oregon

Res Nov. 3^d. Exch

47

Subdivisions

Examina & Correcting

Field notes of the Subdivision lines
in Township No 3 North of Range 29
East of the Willamette Meridian
in the State of Oregon by W. H.
Gates deputy Surveyor under his
Contract No 84 bearing date the
22nd day of July 1859

commenced September 15th 1859
completed September 22nd 1859

Washington transcript made
by P. J.

Manuscript compared
with Notes. T. C.