

Field Notes of the survey of the
 Subdivisional lines of Town-
 ship No. 3, North of Range No
 3 East of the Willamette Merid-
 ian, in the State of Oregon, by
 Wm. B. Campbell, deputy surveyor,
 under his contract No 95,
 bearing date the 19th day of
 September 1860.

Commenced Oct 18th 1860
 Finished October 26th do

Index Diagram

6	5	4	3	2	1
63	62	45	34	23	12
7	8	9	10	11	12
60	59	43	32	21	10
18	17	16	15	14	13
57	56	41	31	20	9
19	20	21	22	23	24
54	53	39	28	17	6
31	29	28	27	26	25
51	49	37	26	15	4
31	32	33	34	35	36

Township 3 Range 3 E. Tiltamatt Meridian
chains

North, On a random line between sec
1 & 2.

Variation 2035 E

40.00 Set a temporary post, for quarter corner,

~~70.11~~ Commence to ascend hill

83.11 Intersect North boundary of -50
Township 3 & 4 East of post
corner to sec. 1 & 2

Sec 21 E. On a true line between
sec. 1 & 2, commencing at

13.11 To top of ascent +50

43.11 Set a post for quarter section
corner, drove a char'd stake
& raised a mound of earth with
trench & hills, as per instructions,

83.11 The corner to sec. 1, 2, 11 & 12,

Land gently rolling prairie,

Soil good 2nd rate.

Oct. 18th 1860

Township 3 N. Range 30 E. Willamette Mer.
chains

Both, On a random line between
Sections 2 & 3

Variation $19^{\circ} 15' E$

41000 - Set a temporary quarter section
post,

82.27' Intersect North boundary of
Township 71 lks East of post

511030' On a true line between Sec.
2 & 3,

4227' Set a post for quarter sec corner
Drove a char'd Stake & raised
mound with trench & pits.
as per instructions.

82.27' The post corner to sec 2, 3,
10 & 11.

Land considerably rolling,
Soil good Good rate

Township 3, N. R. 3, E. Willamette Meridian
Main

North, On a random line between Sec 3 & 4

~~Variation 19° 35' E.~~

40.00 Set a temporary quarter section post

81.75 Intersect North boundary of

81.75 Township 31 N. East of post,
corner to sec - 3, & 4.

S 00° 13' E. On a true line between Sec. 3 & 4.

41.75 Set a post for quarter section

41.75 corner, drove a char'd stake
raised mound of earth, with
trench & pits, as per instructions;

81.75 The corner to sec. 3, 4, 9, 8, 10,

91.75 Land, rolling prairie, soil
good 2nd Rate

October 20th 1860

W. H. May, Jr. D.M.M.

46 86

Township 3 N Range 30 E Willamette Meridian,
Chasing

North. On a random line between Sect 4 & 5
Variation 21° 00' E.

Common ascent

- 16.57 To top of ascent & descent +100
- 40.00 Set temporary quarter sec post 150
- ~~70.00 To foot of descent~~ 150 50
- 80.00 Common ascent 50
- 82.62 Intersect North boundary +50
of Township 3 N R 30 E East
of post. corner to Sect 4 N 50
Rock Mountain

Township 3, N, Range 3, E, Tarrant Merid.
chains

North, On a random line
between Sec 5 & 6,

Variation 20° 15' E.

40.00 Set a temporary quarter sec. post

~~45.00 Commence descent~~

~~65.00 To foot of descent~~

-100

~~69.00 To a Nail E. W. corner~~

81.09 Intersect North boundary +100

of Township 5 links East of
post. corner to Sec. 5 & 6.

S 22° E. On a line between Sec 5 & 6
commence descent from post.

11.49 To foot of descent by Nail running E. W. -100

16.09 Commence ascending

36.09 To top of ascent +100

41.09 Set a post for quarter sec corner

drove a char'd Stake & raised

ground 4 in. with trench filled as per instr.

81.09 The corner to Sec 5 & 6 - 7 & 8.

Sand rolling prairie soil

2nd rate, Oct 26th 1860

List of Names.

List of the names of the individuals employed to assist in running, measuring, or marking the lines and corners described in the foregoing field notes, of Township No 3 North of the base line of Range No 30 East of the Willamette Meridian, showing the capacities in which they acted:

Samuel Campbell Chairman
 Josephus Comptons do
 Robert Handfield Roman

We hereby certify that we assisted
 Saml Campbell deputy surveyor,
 in surveying the subdivisinal
 lines of Township No 3 North
 of the base line of Range number
 Thirty East of the

Pillmate Meridian, and that
said Township has been in all
respects, to the best of our knowl-
-edge and belief, well and
faithfully surveyed, and the
boundary monuments planted
according to the instructions
furnished by the Surveyor General,

Samuel L Campbell Chairman.
Josephus Tompkins Chairman
Robert F. Canfield Assnary

Subscribed and sworn to
before me at Oregon City this
3rd day of Decr AD 1860

Jas Winston
Clerk of the Circuit
Court for the County
of Clatsop as State
of Oregon

69
189

Wm. Campbell deputy surveyor,
do solemnly swear that, in
pursuance of a contract with
W. W. Chapman Surveyor of the
public lands of the United States,
in the State of Oregon, bearing
date the 19th day of September,
1860, and in strict conformity
to the laws of the United States,
and the instructions furnished by
the Surveyor General, I have
faithfully surveyed the subdivi-
sional lines of Township No. 11
Three North of the base line of Range
number thirty East of the Willamette
Meridian, in the State aforesaid,
and do further solemnly swear
that the foregoing are the true
and original field notes of
such survey of Wm. Campbell
deputy Surveyor

Subscribed and sworn

119

To Before me at Oregon
City this 3rd day of Dec
A.D. 1860

John Wessington
Clerk of the Circuit
Court for the County
of Lincoln in the State
of Oregon

110A

Sur General's Office
Eugene City, Jan'y 29th 1861.

The foregoing field notes of the
survey of the subdivisions of Town-
ships No. 3 North, Range No. 30
East of the Willamette Meridian
executed by Wm. B. Campbell, dep-
uty Surveyor, under his contract
of the 19th day of September 1860:
having been critically exam-
ined, the necessary corrections
and explanations made the
said field notes and the sur-
veys they describe are hereby
approved.

W. W. Chapman

Sur: General of Oregon