

~~97~~
617

Index
To the Field Notes of the
Exterior Lines of Town-
ship No 4 North of Range
No 31 East of Williamette
Meridian.

over	1200	107
	12	101
	13	100
	24	99
	25	99
	36	98

Suspended - to report more
and appear

Commenced the
 Survey of the Exterior
 Lines of Township No.
 4th, Range 3rd East Will. Mer.
 May 4th 1865

North on East boundary
 of section 36, 40, 39, 2,
 bearing $20^{\circ}45' E$,

40.00 Set 4th Section post cor,
 on side hill sloping
 to the North, Drove Charred
 Stake, dug pits, and
 raised Mound as
 per instructions,

80.00 Set post corner for sections
 25, 36, 30 & 31, on top of ridge
 sloping to the West, Drove
 Charred stake, dug pits,
 and raised Mound as
 per instructions,

This line passes over
 high rolling grounds
 Good grass Soil 2nd Rate

Township 4 N. R. 31 E. Will, also,
North on East boundary of
section 25 S 4 N. R 31 E,
Bar $20^{\circ}30' E$,

40.00 Set $\frac{1}{4}$ Section post cor,
on top of ridge, Drove
Charred stake, dug pits
and raised mound as
per instruction,

80.00 Set post corner for sections
24, 25, 19 & 30, set post on
right bank of dry branch
Drove Charred stake,
dug pits & raised
Mound as per instructions
Land broken good
grass soil 2 on pate,

North on West boundary
of section 24 S 4 N, R 31 E,
Bar $20^{\circ}30' E$,

40.00 Set $\frac{1}{4}$ Sec Post Drove Charred
Stake dug pits & raised mound

Township 4 North Range 31 East Will, Minn.
as Per Instructions.

8000 Sep Post Corner for Secs 18, 19,
13 & 24. Head of gully South side
Drove Charred Stake Dug Pit
raised Ground as Per Instructions
Sand Rolling grass good
Soil 2^d Rate.

North on West Boundary of Sec 18
Town 4, North, Range 32 East.
Variation 20: 30' East.

4000 Sep 1/4 Sec Post Drove Charred
Stake, Dug Pit & raised
Ground as Per Instructions

8000 Sep Post Corner for Secs 18, 13,
12 & 14. Drove Charred Stake
Dug Pit & raised Ground
as Per Instructions.

Sand Rolling grass good
Soil 2^d Rate.

Township 4 North Range 31 East, Hill, Minn.
 North on West Boundary of Sec 9,
 Town 4, North, Range 32 East,
 Variation 20° 30' East.

40.00 Sec 1/4 Sec Post. Drove Charred
 Stake dug Pit - raised mound
 as Per Instructions.

80.00 Sec Post Corner for Secs 10, 12,
 14. Drove Charred Stake dug
 Pit - raised mound as Per
 Instructions. Land Rolling
grass good soil 2^d Rate.

North on West Boundary of Sec 6,
 Town 4, North, Range 32 East,
 Variation 20° 30' East

40.00 Sec 1/4 Sec Post Drove Charred
 Stake dug Pit - raised
 mound as Per Instructions.

72.00 Intersected Standard
 Parallel 81 lbs east of post
 Made C.C. corner by
 planting Chisel Stake

Township No 4 N, R. 31 E, Mill, Mer,
 with pit, and mound
 as per instructions,
 This line passes over
 high rolling ground
 Good grass soil 2nd Rate,

This Township is
 entirely destitute
 of timber and quite
 broken but is well
 set with grass yet
 is comparatively
 valueless until wells
 are sunk from the
 fact of the great
 scarcity of water,

Surveyed by W. H. Bell, Assisted
 by W. W. Johnson Compassman
 C. C. Harcombs Chimneyman
 A. Shibles
 William Warren Axeman

I William H. Odell, do hereby
certify that the foregoing
are the true and original
Field Notes of the surveys
of the Exterior lines of Township
No. 4 North of Base Line of Range
31 East of Willamette Meridian
in the State of Oregon: made, under
contract No. 110 with B. F. Pezra
Surveyor General, and bearing
date February 7th 1865, in
accordance with the Laws
of the United States and the
Instructions furnished by
the Surveyor General; as will
appear from affidavits duly
made out at the Close of said
Contract and attached to the
field notes of Township No.
6 N of R No. 37 East

William H. Odell

Deputy Surveyor,

Surveyor General's Office
Eugene City, Feb. 9, 1866

~~The foregoing field notes of the Survey of
Exterior Lines of Twp. 4 N. Rgs. 31, 32 &
33 East Will. Mer. Oregon, Executed by
Odell & Lewis under contract No. 110 bearing
date Feby. 7th 1865, having been critically
examined, the necessary explanations &
corrections made, the said field notes
and the surveys they describe are
hereby approved~~

E. L. Applegate
Sur. Genl. of Oregon

This certificate is apparently
all right + There are no other
notes of these lines, and
there is a corresponding plat
duly approved -

J. W. P.