

Index

Referring the lines to the pages in the field notes

Township 4 N. Range 31 E. Will. Mex.

6	40	5	30	4	23	3	17	2	10	1
40		39		29		23		16		9
7	38	8	29	9	22	10	15	11	8	12
38		37		28		22		15		8
18	37	17	28	16	21	15	14	14	7	13
36		35		27		20		13		6
19	35	20	27	21	20	22	13	23	6	24
34		33		26		19		12		5
30	33	29	26	28	19	27	12	26	4	25
32		31		25		18		11		4
31	31	32	24	33	17	34	11	35	3	36

Field notes of the Subdivision
lines of Township number 4,
North of the Base Line of Range
31 East of the Willamette Meridian

From corner to sections
1. 2. 35 & 36 on south boundary
I. run

North between sections 35 & 36.

40,000 Set post corner for 1/4 section
drove charred stake, dug
pit and raised mound
as per instructions

80,000 Set post corner for sections 25. 26
35 & 36, drove charred stake, dug pit
and raised mound as per
instruction,

Land broken, grass good,
soil 2^d rate.

4

354

Township No. 4 North, Range 31 East, Will. Mo. Co.

East on random between
sections 25 & 26. Bar 2

Bar 21° East.

40.00 Set temporary $\frac{1}{4}$ section corner,79.63 Intersected North and South line
25 lbs South of post corner
S 89° 45' W on true line.39.81 Set post corner for $\frac{1}{4}$ section on
line of bar course S.W.Drove churred stake dug pits
and raised mound as per
instructions,

79.63 To post corner,

Land broken, good
grass soil 2^d rate,

corn

North between sections 25 & 26.

40.00 Set post corner for $\frac{1}{4}$ sectionDrove churred stake, dug pits,
and raised mound asper instructions, Land at
corner slopes to the S.W.

Township No 4 North, Range 31 East Will Mer 355⁵

80.00 Set post corner for sections 40
23, 24, 25 & 26, on East side of
Cavine, course N, E, drove
cherryed stake, dug pits, and
raised mound as per instructions.
Land broken, grass good
+ Soil 2nd Rate.

East on random between sections
24 & 25

Bar 20° East.

40.00 Set temporary 1/4 section post corner

79.71 Intersected North and South line 23 the
South of post corner,

$88^{\circ}50' W$ on true line.

39.85 Set post corner for 1/4 section,
drove cherryed stake, dug pits
and raised mound as per
instructions,

Stage Station bears N 20° E

about 10 chains,

79.71 To post corner.

6 356

Township 40 North, Range 31 East Will. Mer.

Land broken, good grass

X

Soil 2^d rate,

North between sections 23 & 24

40.00 Set post corner for 1/4 section
drove charred stake, dug pits,
and raised mound as per
instructions,

57.00 Stage Road from Boise City to 40
Armatilla City course N.W.

80.00 Set post corner for sections 13, 14, 40
23 & 24, drove charred stake, dug
pits and raised mound as per
instructions,

Land broken, grass

X

good, Soil 2^d rate,

East on ranch line between
sections 13 & 24,

Bar 20° 30' East,

40.00 Set temporary 1/4 section post
corner,

+

Township No 4 North, Range 31. East, T11, Mer, 357

7980 Intersect North and South line
32 links South of post corner
S 89° 46' W on true line,

3990 Set post corner for $\frac{1}{4}$ sections
Drove charred stake dug
pits, and raised pits as per
instructions

7980 To post corner,
Land broken, grass good,
X Soil 2^d rate,

North between sections 13 & 14

4000 Set post corner for $\frac{1}{4}$ sections 15
Drove charred stake, dug pits
and raised mound as per
instructions.

8000 Set post corner for sections 40
11. 12. 13 & 14 Drove charred stake,
dug pits and raised mound
as per instructions
Land broken, good grass,
X Soil 2^d rate,

Township No. 4 North, Range 31 East Will. Mer.
East on random between sections
12 & 13.

Bear 20° East,

40.00 Set temporary 1/4 section post corner

79.86 Intersect North and south line

89 fms South of post corner,

S. 89° 43' W. on true line,

35.00 Bottom of ravine course N. W. 100 100

39.93 Set post corner for 1/4 section, drove
churned stake dug pits, and
raised mound as per instructions
Corner on steep hillside facing
the N. East

+ 40
+ 60

79.86 To post corner

Land broken, grass

X good soil 2nd rate,

North between sections 11 & 12.

40.00 Set post corner for 1/4 section, on steep
hillside facing the N. E.

Drove churned stake, dug pits, and
raised mound as per instructions

3598

Township No. 4 North, Range 31 East, Will. Mer

60.60 Bottom of Ravine course N. W. 70

There is running water at this place and probably continues here all the year. Yet a short distance below the channel is dry. Yet water can be found standing in holes in many places both above and below.

80.00 Set post corner for sections 1, 2, 11 & 12 80.

drove charred stake dug pits and raised mound as per instructions

Land quite broken, good grass, soil 2nd rate

East on random between sections 1 & 12,

Bear 21° 30' East,

40.00 Set temporary 1/4 section post corner

71.90 Intersected North and south line

48 lbs South of post corner,

S 89° 39' W on true line.

31.95 Set post corner for 1/4 section

A list of the names
of the persons employed to assist
in running measuring or
marking the lines and corners
described in the foregoing field
notes of Township No 4 North
of the Base Line of Range 31 East
of Willamette Meridian, showing
the respective capacities in
which they acted;

J. J. Henderson }
John A. Rigg } Chairmen
P. M. Denney }
A. A. Auman

We hereby certify that we assisted William
 H. Odell, deputy surveyor, in subdividing
 Township No. 4 North of Range 31 East
 of Willamette Meridian, and that
 said Township has been in all respects
 to the best of our knowledge and belief
 well and faithfully surveyed and
 the boundary monuments planted
 according to the instructions furnished
 by the Surveyor General,

J J Henderson	Chairman
J A Prigg	Chairman
J P M. Demney	Member

State of Oregon }
 County of Umatilla } S.S. Subscribed
 and sworn to before me this
 22 day of September 1866.

William Luccallen, Justice of the Peace

J. William H. Odell,

395

deputy surveyor, do solemnly swear that in pursuance of a contract with E. L. Applegate surveyor of the public lands of the United States in the State of Oregon, bearing date July 2nd 1866, and in strict conformity to the laws of the United States and the instructions furnished by said Surveyor General, I have faithfully surveyed the subdivisional lines of Township No. 4 North of Range 31 East of Willamette Meridian in the State aforesaid and do further solemnly swear that the foregoing are the true and original field notes of such survey.

William H. Odell

State of Oregon }
County of Lane } ss Subscribed and
sworn to before me this 22nd day
of December 1866.

Joel Ware

Notary Public

Surveyor General's Office
 Eugene City January 11th 1867

The foregoing field notes of the
 of the ~~subdivision~~ ^{subdivision} ~~lines~~
 Survey of Township No 4 North
 Range 31 East Will. Mer. Oregon
 executed by William H. Odell Dept.
 Surveyor under his contract No
 114 bearing date July 2nd, 1866
 having been critically examined
 the necessary corrections and expla-
 nations made the field notes and
 the Survey they describe are hereby
 approved

E. L. Applegate
 Surveyor General of Oregon