

Index  
 To the Field Notes of the  
 Exterior Lines of Town-  
 ship No 4 North of Range  
 No 31 East of Williamette  
 Meridian.

over	1200	107
	12	101
	13	100
	24	99
	25	99
	36	98

Suspended - to report more  
 and appear

Township 4 North Range 31 East, Hill, Minn.  
 North on West Boundary of Sec 9,  
 Town 4, North, Range 32 East,  
 Variation 20° 30' East.

40.00 Sec 1/4 Sec Post. Drove Charred  
 Stake dug pit - raised mound  
 as per instructions.

80.00 Sec Post Corner for Secs 10, 12,  
 14. Drove Charred Stake dug  
 pit - raise mound as per  
 instructions. Land Rolling  
grass good soil 2<sup>d</sup> Rate.

North on West Boundary of Sec 6,  
 Town 4, North, Range 32 East,  
 Variation 20° 30' East

40.00 Sec 1/4 Sec Post Drove Charred  
 Stake dug pit - raised  
 mound as per instructions.

72.00 Intersected Standard  
 Parallel 81 lbs east of post  
 Made C.C. corner by  
 planting chisel stake

Township No 4 N, R. 31 E, Mill, Mer,  
 with pit, and mound  
 as per instructions,  
 This line passes over  
 high rolling ground  
 Good grass soil 2<sup>nd</sup> Rate,

This Township is  
 entirely destitute  
 of timber and quite  
 broken but is well  
 set with grass yet  
 is comparatively  
 valueless until wells  
 are sunk from the  
 fact of the great  
 scarcity of water,

Surveyed by W. H. Bell, Assisted  
 by W. W. Johnson Compassman  
 C. C. Harcombs Chimneyman  
 A. Shibles  
 William Warren Axeman

I William H. Odell, do hereby  
certify that the foregoing  
are the true and original  
Field Notes of the surveys  
of the Exterior lines of Township  
No. 4 North of Base Line of Range  
31 East of Willamette Meridian  
in the State of Oregon: made, under  
contract No. 110 with B. F. Pezra  
Surveyor General, and bearing  
date February 7<sup>th</sup> 1865, in  
accordance with the Laws  
of the United States and the  
Instructions furnished by  
the Surveyor General; as will  
appear from affidavits duly  
made out at the Close of said  
Contract and attached to the  
field notes of Township No.  
6 N of R No. 37 East

William H. Odell

Deputy Surveyor,

Surveyor General's Office  
Eugene City, Feb. 9, 1866

~~The foregoing field notes of the Survey of  
Exterior Lines of Twp. 4 N. Rgs. 31, 32 &  
33 East Will. Mer. Oregon, Executed by  
Odell & Lewis under contract No. 110 bearing  
date Feby. 7<sup>th</sup> 1865, having been critically  
examined, the necessary explanations &  
corrections made, the said field notes  
and the surveys they describe are  
hereby approved~~

E. L. Applgate  
Sur. Genl. of Oregon

This certificate is apparently  
all right + There are no other  
notes of these lines, and  
there is a corresponding plat  
duly approved -

J. W. P.