

Index

Referring the lines to the pages in the field notes

Township 4 N. Range 31 E. Will. Mex.

6	40	5	30	4	23	3	17	2	10	1
40		39		29		23		16		9
7	38	8	29	9	22	10	15	11	8	12
38		37		28		22		15		8
18	37	17	28	16	21	15	14	14	7	13
36		35		27		20		13		6
19	35	20	27	21	20	22	13	23	6	24
34		33		26		19		12		5
30	33	29	26	28	19	27	12	26	4	25
32		31		25		18		11		4
31	31	32	24	33	17	34	11	35	3	36

Field notes of the Subdivision
 lines of Township number 4,
 North of the Base Line of Range
 31 East of the Willamette Meridian

From corner to sections
 1. 2. 35 & 36 on south boundary
 I. run

North between sections 35 & 36.

40,000 Set post corner for 1/4 section
 drove charred stake, dug
 pit and raised mound
 as per instructions

80,000 Set post corner for sections 25. 26
 35 & 36, drove charred stake, dug pit
 and raised mound as per
 instruction,

Land broken, grass good,
 soil 2^d rate.

Township No 4 North, Range 31 East, Will. Mo. Co.

East on random between sections 25 & 26. Bar 2

Bar 21° East.

40.00 Set temporary 1/4 section corner,
79.63 Intersected North and South line
25 lbs South of post corner
S 89° 45' W on true line.

39.81 Set post corner for 1/4 section on
line of bar in course S.W.
Drove churred stake dug pits
and raised mound as per
instructions,

79.63 To post corner,
Sand broken, good
X grass soil 2^d rate,

corn North between sections 25 & 26.

40.00 Set post corner for 1/4 section
Drove churred stake, dug pits,
and raised mound as
per instructions, Sand at
corner slopes to the S.W.

Township No 4 North, Range 31 East Will Mer 355⁵

80.00 Set post corner for sections 23, 24, 25 & 26, on East side of Ravine, course N, E, drove cherruel stake, dug pits, and raised mound as per instructions. Land broken, grass good
+ Soil 2nd Rate.

40

East on random between sections 24 & 25

Bar 20° East.

40.00 Set temporary 1/4 section post corner

79.71 Intersected North and South line 23 the South of post corner,

$88^{\circ}50' W$ on true line.

39.85 Set post corner for 1/4 section,

drove cherruel stake, dug pits and raised mound as per instructions,

Stage Station bears N 20° E

about 10 chains,

79.71 To post corner.

6 356

Township 40 North, Range 31 East Will. Mer.

Land broken, good grass

X Soil 2^d rate,

North between sections 23 & 24

40.00 Set post corner for 1/4 section
drove charred stake, dug pits,
and raised mound as per
instructions,

57.00 Stage Road from Boise City to 40
Armatilla City course N.W.

80.00 Set post corner for sections 13, 14, 40
23 & 24, drove charred stake, dug
pits and raised mound as per
instructions,

Land broken, grass

X good, Soil 2^d rate,

East on ranch line between
sections 13 & 24,

Bar 20° 30' East,

40.00 Set temporary 1/4 section post
corner,

X

Township No 4 North, Range 31. East, T11, Mer, 357

7980 Intersect North and South line
32 links South of post corner
S 89° 46' W on true line,

3990 Set post corner for $\frac{1}{4}$ sections
Drove charred stake dug
pits, and raised pits as per
instructions

7980 To post corner,
Land broken, grass good,
X Soil 2^d rate,

North between sections 13 & 14

4000 Set post corner for $\frac{1}{4}$ sections 15
Drove charred stake, dug pits
and raised mound as per
instructions.

8000 Set post corner for sections 40
11. 12. 13 & 14 Drove charred stake,
dug pits and raised mound
as per instructions
Land broken, good grass,
X Soil 2^d rate,

Township No. 4 North, Range 31 East Will. Mer.
East on random between sections
12 & 13.

Bar 20° East,

40.00 Set temporary 1/4 section post corner

79.86 Intersect North and south line

89 fms South of post corner,

S. 89° 43' W. on true line,

35.00 Bottom of ravine course N. W. 100 100

39.93 Set post corner for 1/4 section, drove
churned stake dug pits, and
raised mound as per instructions
Corner on steep hillside facing
the N. East

+ 40
+ 60

79.86 To post corner

Land broken, grass

X good soil 2nd rate,

North between sections 11 & 12.

40.00 Set post corner for 1/4 section, on steep
hillside facing the N. E.

Drove churned stake, dug pits, and
raised mound as per instructions

3598

Township No. 4 North, Range 31 East, Will. Mer-

60.60 Bottom of Ravine course N. W. 70

There is running water at this place and probably continues here all the year. Yet a short distance below the channel is dry. Yet water can be found standing in holes in many places both above and below.

80.00 Set post corner for sections 1, 2, 11 & 12 80.

drove charred stake dug pits and raised mound as per instructions

Land quite broken, good grass, soil 2nd rate

East on random between sections 1 & 12,

Bear 21° 30' East,

40.00 Set temporary 1/4 section post corner

71.90 Intersected North and south line

48 lbs South of post corner,

S 89° 39' W on true line.

31.95 Set post corner for 1/4 section

10 2360

Township N. 4 North Range 31. East Will-Mer-

drove charred stake, dug, pits, and raised mounds as per instructions

7,90 To post corner.

40

Land broken, grass good

X Soil 2¹/₂ rate,

North between sections 142.

40,00 Set post corner for 14 section, on.

+ 40

Summit of bridge course S.W.,

drove charred stake, dug pits, and raised mound as per instructions

80,50 Intersect First Standard Parallel North 10 lbs West of post, corner for sections 35 & 36.

T 5 N, R 31 E,

At point of intersection

set post closing corner for sections 142, drove charred

stake, dug pit and raised mound as per instructions

Land broken, grass good, Soil 2¹/₂ rate,

Township 46 North, Range 31 East, Will. Mer. 36'

August 9th 1866.

X
corn

North between sections 34 & 35.

16.50 Bottom of Beavin course N, W.

50

40.00 Set Bassalt Stone 5x8x12. corner for
1/4 Section.

50

80.00 Set post corner for sections 26, 27, 34 &

35, drove charred stake, dug pits,
and raised mound as per instructions
Land broken, grass excellent,
Soil 2^d Rate.

East on Random between sections
26 & 35.

Bar 20° 30' East

40.00 Set temporary 1/4 section corner

79.68 Intersected North and South line
at post corner

West on true line

39.84 Set 1/4 section corner, post,

drove charred stake dug pits,
75.68 To post corner.

Township No 4 North, Range 31 East, Will-Mer-
and raised mound as per instructions
Land broken, grass good Soil 2nd rate,

+

North between sections 26 & 27.

40.00 Set post corner for 4 sections, drove 70
Charred stake, dug pits, and raised
mound as per instructions.

44.00 Bottom of Ravine course M. W. 20

80.00 Set post corner for sections 22, 23, 26 & 27. 80
drove charred stake, dug pits and
raised mound as per instructions
Land broken, good grass -
Soil 2nd rate.

+

East on Random between sections
23 & 26

Bar 21st East -

40.00 Set temporary 1/4 section post corner,
79.74 Intersected North and South line 22 Sec
South of post corner

S 89° 51' W. on true line,

39.87 Set post corner for 1/4 section,

+

Township No. 4 North, Range 31 East, Will-Mer-

drove charred stake, dug pits, and raised mound as per instructions

Land broken, grass good, Soil 2nd rate,

7,974 Go post corner,

Land broken, good grass,

X Soil 2nd rate -

North between sections 22 & 23.

4000 Set post, on summit of ridge, for

70

1/4 section corner, drove charred stake, dug pit and raised mound as per instructions

89.00 Set post corner for sections

100

14, 15, 22 & 23 Land slopes to the West, drove charred stake, dug pits and raised mound as per instructions

Land broken, good

X Grass, Soil 2nd rate -

East on Ranelson between sections

X 14 & 23,

14 364

Township 4 North Range 31 East Will. Mer.

Bar 20° 30' East.

40.00 Set temporary 1/4 section post corner.

79.76 Intersect North and south line 36 links south of post. corner S 89° 45' W on true line.

33.00 Stage Road, course N W 50

^{25.98}
~~37.88~~ Set post corner for 1/4 section drove charred stake, dug pit and raised mound as per instructions. 15

79.76 To post corner. 30

Land broken, good grass

X Soil 2nd rate.

North between sections 14 & 15.

39.00 Stage Road, course N.W. & S.E. - 45

38.50 Bottom of Ravine course N.W. 5

40.00 Set post corner for 1/4 section, drove charred stake dug pit and raised mound as per instructions. 4

80.00 Set post corner for sections 10.11. 45

Township 4 North, Range 31 East, Will-Mer-

365¹⁵

14 & 15. Drove charred stake dug pits,
and raised mound as per instructions
Land broken, good grass soil 2^d rate-

x

East on random between sections 11 & 14

Bar 20°30' East-

40.00 Set temporary 1/4 section post corner

79.85 Intersected North and south

line 40 links south of post corner

S 85° 43' W on true line

39.92 Set post corner for 1/4 section.

+
40

Drove charred stake, dug pits,

and raised mound as per
instructions

79.85 To post corner

+
20

Land broken grass excellent,

Soil 2^d rate,

x

North between sections 10 & 11

40.00 Set post corner 1/4 section, drove

charred stake, dug pits, and

raised mound as per instructions.

Township 4 North, Range 31 East, Will-Mer-

80.110 Set post corner for sections 2, 3, 80

10 & 11. Above channel stake, dug pits, and raised mound as per instructions.

Land rolling, good grass, Soil 2^d rate,

X

com East on Random, between sections 2 & 11.

Bar 21° East

40.00 Set temporary 1/4 section post corner.

79.94 Intersected North and south line 38 links South of post corner -

S 89° 46' W. on true line.

^{11.50} 81.50 Bottom of Prairie Course N.W. 80

39.97 Set post corner for 1/4 section, 60

above channel stake, dug pits and raised mound as per instructions

79.94 To post corner - 20

Land broken, good

X grass. Soil 2^d rate,

Township 4 North, Range 31 East, Will Merf 367¹⁷

North between sections 2 & 3.

40.00 Set 1/4 section post corner,
above charred stake dug pit,
and raised mound as per
instructions.

67.50 Bottom of Ravine course N, W, 80

80.39 Intersected 1st Standard Parallel 75⁺

North 22 links West of Post
Corner - for section 34 & 35 - T. 5 N.

R. 31 E. Set post closing corner
for sections 2 & 3, above charred
stake dug pit and raised mound
as per instructions.

Land broken, grass good,

Soil 2nd rate -

August 11th 1866.

X

North between sections 33 & 34.

2.00 Ravine course N W 10

40.00 Set post corner for 1/4 section +
20

above charred stake, dug pit,
and raised mound as per

X

189 368

Township 4 North Range 31 East - Will-er-
instructions,

80.00 Set post corner for sections 27, 28,

33 & 34 drove charred stake, dug pits
and raised mound as per instructions

Land broken, good grass,

Soil 2^d Rate-

X

East on random between sections

27 & 34

Bar 21° East.

40.00 Set temporary 1/4 section post
corner,

80.10 Intersected North & South line

32 lbs North of Post.

N 89° 46' W on true line,

40.05 Set post corner for 1/4 section

20

drove charred stake dug pits
and raised mound as per
instructions,

66.50 Bottom of Ravine course NW

30

80.10 To post corner

5-

Land broken, good grass, Soil 2^d Rate.

X

Township 4 North, Range 31 East Will-Mer

North between sections 27 & 28,

4,000 Set post corner for 1/4 section
drove charred stake, dug pits
and raised mound as per
instructions.

60,50 Bottom of ravine course N. W. 60

80,00 Set post corner for sections 40
+ 40

21, 22, 27 & 28, drove charred stake,
dug pits and raised mound
as per instructions.

Land broken, good grass,
Soil 2^d rate,

+

East on boundary between sections 22 & 27.

Bar 21° East =

40,00 Set temporary 1/4 section post corner

80,21 Intersected North and South line 40
links North of post corner,
N 89° 43' W on true line.

40,10 Set post corner for 1/4 sections drove
charred stake dug pits, and

20 370

Township 4 North, Range 31 East, Will-Mer-

raised mound as per instructions

80.21 To post corner,

20

Land broken, good grass

X Soil 2nd rate,

North between sections 21 & 22.

40.00 Set post corner for 1/4 section above
churned stake, dug pits and raised
mound as per instructions

80.00 Set post corner for sections 15, 16, 21 & 22 ⁺ 25

Above churned stake dug pits and raised
mound as per instructions.

Land broken, grass good,

X Soil 2nd rate

East on random between sections

15 & 22.

Bar 20° 30' East,

40.00 Set temporary 1/4 section post
corner -

79.90 Intersected North and south line
18 links North of post corner
N 89° 52' W on true line

Township 4 North Range 31 East Will. Mer. 37²¹

39.95 Set post corner for $\frac{1}{4}$ section, on +
30
land facing the East - drove
charrred stake, dug pits and raised
mound as per instructions.

19.90 To post corner - +
20
Land broken, grass
good Soil 2^d rate.

North between sections 15 & 16.

40.00 Set post corner for $\frac{1}{4}$ section, in 30
the head of ravine on steep hill
side facing the N. E. drove
charrred stake dug pits and raised
mound as per instructions.

74.50 Stage Road course N. W. & S. E. -
40

80.00 Set post corner for sections 9. 10. 15 & 16 +
20
dove charrred stake dug pits and
raised mound as per instructions
Land broken,
good grass,
Soil 2^d rate,

+

22 372

Township 4 North, Range 31 East, Will. Mer.

East on random between sections

10 & 15-

Bar 21° East-

40.00 Set temporary 1/4 section corner post

80.15 Intersect North and South line

26 links North of post corner-

N 89° 49' W. on true line -

40.07 Set post corner for 1/4 section, 40

in bottom of ravine course, S, W,

above charred stake dug pits,

and raised mound as per

instructions.

80.15 To post corner,

Land broken,

Grass good, Soil 2^d rate,

North between sections 9 & 10.

40.00 Set post corner for 1/4 section, on 60

land sloping to the S, W, above

charred stake dug pits and

raised mound as per instructions

80.00 Set post corner for 1/4 sections 3, 4, 9 & 10

37²³₃

12 Township 4 North, Range 31 East, Will-Mer-
and 10., on level, drove charred
Stake dug pits and raised mound
as per instructions,
Land broken, grass good
Soil 2^d rate,

+

East on random between section 34~~40~~
Bar 20 East,

40.00 Set temporary 1/4 section post corner,
50.28 Intersected North and south line 34 the
north of post corner.

N 89° 45' W on true line

40.14 Set post corner for 1/4 section, on 30
land sloping to the West,
drove charred stake, dug pits,
and raised mound as per
instructions

80.28 To Post Corner — 20
Land broken Soil 2^d rate,

+

North between sections 34-4-

40.00 Set 1/4 section post corner, drove

24 374

Township 4 North, Range 31 East Will-Mer-

Charred stake dug pits and raised mound as per instructions,

80.05 Intersected of first Standard Parallel North 28th West of Post-Corner for sections 33 & 34 T⁵ N R 31 East, at point of intersection set post Closing Corner for sections 3 & 4. Above Charred stake dug pits, and raised mound as per instructions,

Soil broken grass good

Soil 2^d rate,

X

August 11th 1866-

North between sections 32 & 33

40.00 Set post corner for 1/4 section,

on land sloping to the N.W. Above Charred stake, dug pits, and raised mound as per instructions,

59.00 Bottom of ravine course N.W.

20 X

Township 4 North Range 31 East Willamette Meridian

80.00 Set post corner for sections 28, 29, 20

32 & 33, on land sloping to the South
Drove charred stake, dug pits, and
raised mound as per instructions,
Land broken, grass good,
Soil 2nd Rate -

+

East on random between sections 28 & 33.
Bar 21° East,

40.00 Set temporary 1/4 section post corner

79.88 Intersected North and South line
52 links North of Post corner,
N89° 38' W on true line.

28.00 Summit of ridge course S.W,

+
60

39.84 Set post corner for 1/4 section, on

-
20

side of small ravine, course S.W,
Drove charred stake, dug pits and
raised mound as per instructions.

79.88 To post corner,

-
20

Land broken, good grass
Soil 2nd Rate -

x

Township 4 North, Range 31. East Will-Mer.

North between sections 28 & 29 -

- | | | |
|-------|---|----|
| 40.00 | Set post corner for 1/4 section, on
southern slope of ravine, drove
charred stake dug pit and
raised mound as per instructions | 20 |
| 60.00 | Bottom of ravine course N.W. | 30 |
| 80.00 | Set post corner for sections 20, 21,
28 & 29. on land facing the N.W.
Land broken, good grass
Soil 2 ^d rate. | 45 |

East on Random between sections

20 & 28

bar 21° East

- | | |
|-------|---|
| 40.00 | Set temporary 1/4 Section post
corner |
| 79.92 | Intersected North and south
line 61 links North of post
corner,
N 89° 34' W on true line |
| 39.96 | Set post corner for 1/4 section
on gentle slope to the West, |

3737

Township 4 North, Range 31 East, Will-Mer-

Drove charred stake deep pits, and raised mound as per instructions.

77.92 Go post corner -

X Land broken good grass. Soil 2^d rate

North between sections 20 & 21.

40.00 Set post corner for 4 section, on gentle slope to the south, drove charred stake, dug pits and raised mound as per instructions

80.00 Set post corner for sections 16, 17, 20 & 21, 25⁺ on hill side facing the East. Drove charred stake, dug pits, and raised mound as per instructions.

X Land broken, grass good, Soil 2^d rate,

East on random between sections 16 & 21.

Bar 20° 30' East

40.00 Set temporary 1/4 section post corner

80.10 Intersected North and South line 5-7 links North of post corner -

X N 89° 36' W on true line,

28 378

Township 4 North, Range 31 East, Will. Mer-

40.05 Set post corner for $\frac{1}{4}$ section, drove charred
Stake, dug pits, and raised mound as
per instructions.

80.10 To post corner.

Land broken good grass
X Soil 2nd Rate,

North between sections 16 & 17.

40.00 Set post corner for $\frac{1}{4}$ section,
drove charred stake, dug pits and
raised mound as per instructions.

80.00 Set post corner for 8. 9. 16 & 17.

drove charred stake dug pits and
raised mound as per instructions.

Land broken, grass good,
X Soil 2nd Rate,

East on random between sections 9 & 16
Bar 20' 30" East -

40.00 Set temporary $\frac{1}{4}$ section post corner

80.38 Intersected North and South line

X 63 links North of Post corner,

Township 4 North Range 31 East Will. Mer ²⁸ 379

N 85° 33' W on true line -

10.25 Stage Road course N.W. and S.E. 20

25.00 Summit of ridge + 60

40.15 Set post corner for 1/4 section, on west side of Marine course ~~North~~ 40

Drove charred stake dug pits and raised mound as per instructions.

80.38 To post corner,

Land broken, good grass -

X Soil 2^d rate,

North between sections 8 & 9 -

20.00 Stage Road course N.W. & S.E. 60

40.00 Set post corner for 1/4 section 30

Drove charred stake dug pit and raised mound as per instructions

80.00 Set post corner for sections 4, 5, 8 & 9.

Drove charred stake, dug pits and raised mound as per instructions

Land broken, good grass,

X Soil 2^d rate -

East on random between sections 4 & 9.

30 380

Township 4 North Range 31 East. Will-Mer-
Car 20° East

40.00 Set temporary $\frac{1}{4}$ section post corner,

80.26 Intersected North and south line 58
links North of post corner,
N 89° 35' W on true line,

40.13 Set post corner for $\frac{1}{4}$ section 37

Above charred stake dug pit
and raised mound as per instructions

80.26 To post corner -

Land broken, grass good, 20

+ Soil 2^d Rate,

North between sections 445,

40.00 Set post corner for $\frac{1}{4}$ section. Above
charred stake, dug pit, and
raised mound as per instructions

79.82 Intersected 1st Standard Parallel

North 52 links West of Standard
Corner for sections 32 & 33 T. 5 N. R. 31 E.

Set Closing corner at point
of intersection, for sections 445,
Above charred stake, dug pit

38,31

Township 4 North Range 31 East Will-Mer-
and raised mound as per instructions
Land broken good grass
Soil 2^d rate,
August 12th 1866.

North between sections 31 & 32,
40.00 Set post corner for 4 section (on level)
drove charred stake dug pit and
raised mound as per instructions
80.00 Set post corner for sections
29, 30, 31 & 32, on land sloping to
the North West, drove charred
stake dug pit and raised mound
as per instructions.
Land rolling good grass
Soil 2^d rate,

East on random between sections
29 & 32,
Bar 20° East,
40.00 Set temporary 1/4 section post corner
80.15 Intersected North and South line

Township 4 North, Range 31 East, Will, Mer-
 71 links North of Post corner.

N 89° 30' W on true line,

25.65 A small spring bears N 100 yds 30

30.00 Bottom of Ravine course N. W. 15

40.07 Set post corner for 1/4 section corner 25

Drove charred stake dug pit
 and raised mound as per
 instructions

80.15 To post corner, 20

Land broken, good grass

X Soil 2^d rate,

West on Parcel between sections

30 & 31.

40.00 Set temporary 1/4 section post
 corner,

79.61 Intersected North and south line,

10 links South of Post corner,

S 89° 56' East on true line,

39.61 Set post corner for 1/4 section on

land gently sloping to the North

Drove charred stake, dug pit,

Township 4 North, Range 31 East, Will, Mer,
and raised mound as per instructions

75.61 To post corner,

Land broken good grass

+ Soil 2nd Rate,

North between sections 29 & 30-

40.00 Set post corner for $\frac{1}{4}$ section, drove
charred stake dug pits and raised
mound as per instructions

20

42.50 Bottom of ravine course N.W.

15

80.00 Set post corner for sections 19, 20,

30

29 & 30, on level, drove charred stake
dug pits and raised mound as
per instructions

Land broken, good grass

+ Soil 2nd Rate,

East on random between sections

20 & 29

Bar 21° East

40.00 Set temporary $\frac{1}{4}$ section post,

+ Corner.

Township 4 North, Range 31 East, Will. Mer,

80.22 Intersected North and South
line 55 links north of post
corner,

N 89° 36' W on true line

40.11 Set post corner for 4 section
above charred stake dug pits,
and raised mound as per
instructions

80.22 To post corner,
Land broken good grass

X Soil 2^d rate,

West on random between X
sections 19 & 30.

40.00 Set temporary 4 section post
corner,

79.56 Intersected North and south line
12 links north of post corner
N 89° 55' East on true line.

39.56 Set post corner for 4 section
above charred stake dug pits
and raised mound as per

385-35

Township 4 North, Range 31 East, Will, Mer-
instructions

79.56 To post corner
Land broken, grass good,
Soil 2^d Rate,
+

North between sections 19 & 20.

40.00 Set post corner for $\frac{1}{4}$ section,
Arise charred stake, dug pits,
and raised mound as per
instructions,

80.00 Set post corner for sections 17, 18, 19 & 20
Land broken, good grass,
Soil 2^d Rate,
x

East on railroad between sections
17 & ²⁰ 18.

Bar 21° East.

40.00 Set temporary $\frac{1}{4}$ section post corner,

80.27 Intersected North and South line
48 links North of post corner
N 89° 33' W on true line

40.18 Set post corner for $\frac{1}{4}$ section

Township 4 North, Range 31 East, Will, Mo.
 Drove charred stake, dug pit
 and raised mound as per
 instructions.

79.27 To post corner
 Land broken, grass good.
 Soil 2^d rate

X

West on random between
 sections 18 & 19

40.00 Set temporary 1/4 section post corner

79.52 Intersected North and South
 line 22 links North of post
 corner,

N 83° 51' E on true line,

39.52 Set post corner for 1/4 section 25-

Drove charred stake dug pit
 and raised mound as per
 instructions.

79.52 To post corner

+ 35-

Land broken, good

grass, Soil 2^d rate,

X August 13th 1866.

Township 4 North, Range 31 East, Will, Mex
North between sections 17 & 18. 38³⁷

40.00 Set post corner for 4 sections, in gulch 20
course N, W.

80.00 Set post corner for sections 7, 8, 17, 25
& 18, on level, above charred
stake dug pit and raised mound
as per instructions.

X Land broken, good grass
Soil 2^d rate,

East on random between sections
8 & 17.

Bar 20° East,

40.00 Set temporary 1/4 section post corner

80.19 Intersected North and south line
54 links North of post corner
N 85° 37' W on true line,

40.00 Set post corner for 1/4 section
on level that slopes to the N, W.
Above charred stake, dug pit
and raised mound as per
instructions,

382 388

Township 4 North, Range 31 East, Will. Mer.
80.19 To post corner,

Land broken, good
X grass, Soil 2^d Rate,

West on random between sections
7 & 18.

40.00 Set temporary 1/4 section post corner,

79.63 Intersected North and south
line 15 links North of post,
N 89° 54' East on true line,

39.63 Set 1/4 section post corner
Above charred stake dug
pits and raised around
as per instructions

79.83 To post corner,

Land broken grass
X good Soil 2^d Rate,

North between sections 7 & 8.

32.50 Stage Road course West,

40.00 Set post corner for 1/4 section
Above charred stake, dug

32
389
Township 4 North, Range 31 East, Will. Mer,

pit and raised mound as
per instructions,

80.00 Set post corner for sections 5, 6.

7 & 8, on level, drove charred
stake along pits and raised
mound as per instructions

+ Land broken, grass
good, Soil 2^d rate,

East on Random between sections
5 & 8,

Bar 21° E

40.00 Set temporary 1/4 section post corner,

79.70 Intersect North and south line
68 links North of Post corner.

N 85° 31' W on true line.

39.85 Set post corner for 1/4 section, on
bank of Prairie course N. W.

80

79.70 To post corner

+
60

Land broken, good grass,
Soil 2^d rate,

+
80

40 390

Township 4 North, Range 31 East Will, Mer,

West on random between sections

6 & 7.

40.00 Set temporary $\frac{1}{4}$ section post corner

79.43 Intersected North and south line

25 links North of post corner

$N 89^{\circ} 41'$ East on true line,

39.43 Set post corner for $\frac{1}{4}$ section

above charred stake, dug pits
and raised mound as per
instructions,

79.43 To post corner.

Land broken, grass
good Soil 2^d rate,

North between sections 5 & 6,

40.00 Set post corner for $\frac{1}{4}$ section

above charred stake dug
pits and raised mound
as per instructions,

61.00 Bottom of Parvin course $N 75^{\circ}$

79.61 Intersected ⁷⁵ Standard Parallel

North 76 links West of Post

Township 4 North, Range 31 East, Will. Mer - ³⁹¹
Standard corner for sections 31 & 32

T 5 N R 31 E, at point of intersection
set Closing corner for sections 5 & 6
above charred stake dug pit, and
raised mound as per instructions

Land broken, good
grass, Soil 2^d rate,

The lands of this Township
are well set with rich bunch
grass, affording extensive and
excellent range for stock,

There is water in the N. E.

Corner of the Township, standing
in holes during the dry season
But with little labor could
be so arranged as to afford a good
supply of water for a large amount
of stock, Timber is wholly wanting
and agricultural lands can be found
only in very limited quantities,
August 14th 1866

A list of the names
of the persons employed to assist
in running measuring or
marking the lines and corners
described in the foregoing field
notes of Township No 4 North
of the Base Line of Range 31 East
of Willamette Meridian, showing
the respective capacities in
which they acted;

J. J. Henderson }
John A. Rigg } Chairmen
P. M. Denney }
A. A. Auman

We hereby certify that we assisted William
 H. Odell, deputy surveyor, in subdividing
 Township No. 4 North of Range 31 East
 of Willamette Meridian, and that
 said Township has been in all respects
 to the best of our knowledge and belief
 well and faithfully surveyed and
 the boundary monuments planted
 according to the instructions furnished
 by the Surveyor General,

J J Henderson	Chairman
J A Prigg	Chairman
J P M. Demney	Member

State of Oregon }
 County of Umatilla } S.S. Subscribed
 and sworn to before me this
 22 day of September 1866.

William Luccallen, Justice of the Peace

J. William H. Odell,

395

deputy surveyor, do solemnly swear that in pursuance of a contract with E. L. Applegate surveyor of the public lands of the United States in the State of Oregon, bearing date July 2nd 1866, and in strict conformity to the laws of the United States and the instructions furnished by said Surveyor General, I have faithfully surveyed the subdivisional lines of Township No. 4 North of Range 31 East of Willamette Meridian in the State aforesaid and do further solemnly swear that the foregoing are the true and original field notes of such survey.

William H. Odell

State of Oregon }
County of Lane } ss Subscribed and
sworn to before me this 22nd day
of December 1866.

Joel Ware

Notary Public

Surveyor General's Office
 Eugene City January 11th 1867

The foregoing field notes of the
 of the ~~subdivision~~ ^{subdivision} ~~lines~~
 Survey of Township No 4 North
 Range 31 East Will. Mer. Oregon
 executed by William H. Odell Dept.
 Surveyor under his contract No
 114 bearing date July 2nd, 1866
 having been critically examined
 the necessary corrections and expla-
 nations made the field notes and
 the Survey they describe are hereby
 approved

E. L. Applegate
 Surveyor General of Oregon