

Index

Referring the lines to the pages in the field notes

Township 4 N. Range 31 E. Will. Mex.

6	40	5	30	4	23	3	17	2	10	1
40		39		29		23		16		9
7	38	8	29	9	22	10	15	11	8	12
38		37		28		22		15		8
18	37	17	28	16	21	15	14	14	7	13
36		35		27		20		13		6
19	35	20	27	21	20	22	13	23	6	24
34		33		26		19		12		5
30	33	29	26	28	19	27	12	26	4	25
32		31		25		18		11		4
31	31	32	24	33	17	34	11	35	3	36

Field notes of the Subdivision
lines of Township number 4,
North of the Base Line of Range
31 East of the Willamette Meridian

From corner to sections
1. 2. 35 & 36 on south boundary
I. run

North between sections 35 & 36.

40,000 Set post corner for 1/4 section
drove charred stake, dug
pit and raised mound
as per instructions

80,000 Set post corner for sections 25. 26
35 & 36, drove charred stake, dug pit
and raised mound as per
instruction,

Land broken, grass good,
soil 2^d rate.

Township 4 North, Range 31 East, Will, Mer-
71 links North of Post corner.

$N 89^{\circ} 30' W$ on true line,

25.65 A small spring bears N. 100 yds 30

30.00 Bottom of Ravine course N. W. 15

40.07 Set post corner for $\frac{1}{4}$ section corner 25

Drove charred stake dug pit
and raised mound as per
instructions

80.15 To post corner, 20

Land broken, good grass

X Soil 2^d rate,

West on Parcel between sections

30 & 31.

40.00 Set temporary $\frac{1}{4}$ section post
corner,

79.61 Intersected North and south line,

10 links South of Post corner,

$S 89^{\circ} 56'$ East on true line,

39.61 Set post corner for $\frac{1}{4}$ section on

land gently sloping to the North

Drove charred stake, dug pit,

Township 4 North, Range 31 East, Will, Mer,
and raised mound as per instructions

75.61 To post corner,

Land broken good grass

+ Soil 2nd Rate,

North between sections 29 & 30-

40.00 Set post corner for $\frac{1}{4}$ section, drove
charred stake dug pits and raised
mound as per instructions

20

42.50 Bottom of ravine course N.W.

15

80.00 Set post corner for sections 19, 20,

30

29 & 30, on level, drove charred stake
dug pits and raised mound as
per instructions

Land broken, good grass

+ Soil 2nd Rate,

East on random between sections

20 & 29

Bar 21° East

40.00 Set temporary $\frac{1}{4}$ section post,

+ Corner.

Township 4 North, Range 31 East, Will. Mer,

80.22 Intersected North and South
line 55 links north of post
corner,

N 89° 36' W on true line

40.11 Set post corner for 4 section
above charred stake dry pit,
and raised mound as per
instructions

80.22 To post corner,
Land broken good grass

X Soil 2^d rate,

West on random between X
sections 19 & 30.

40.00 Set temporary 4 section post
corner,

79.56 Intersected North and south line
12 links north of post corner
N 89° 55' East on true line.

39.56 Set post corner for 4 section
above charred stake dry pit
and raised mound as per

385-35

Township 4 North, Range 31 East, Will, Mer-
instructions

79.56 To post corner
Land broken, grass good,
Soil 2^d Rate,
+

North between sections 19 & 20.

40.00 Set post corner for $\frac{1}{4}$ section,
Arise charred stake, dug pits,
and raised mound as per
instructions,

80.00 Set post corner for sections 17, 18, 19 & 20
Land broken, good grass,
Soil 2^d Rate,
x

East on railroad between sections
17 & ²⁰ 18.

Bar 21° East.

40.00 Set temporary $\frac{1}{4}$ section post corner,

80.27 Intersected North and South line
48 links North of post corner
N 89° 33' W on true line

40.18 Set post corner for $\frac{1}{4}$ section

Township 4 North, Range 31 East, Will, Mo.
 Drove charred stake, dug pit
 and raised mound as per
 instructions.

79.27 To post corner
 Land broken, grass good.
 Soil 2^d rate

X

West on random between
 sections 18 & 19

40.00 Set temporary 1/4 section post corner

79.52 Intersected North and South
 line 22 links North of post
 corner,

N 83° 51' E on true line,

39.52 Set post corner for 1/4 section 25-

Drove charred stake dug pit
 and raised mound as per
 instructions.

79.52 To post corner

+
35-

Land broken, good

grass, Soil 2^d rate,

X August 13th 1866.

Township 4 North, Range 31 East, Will, Mex
North between sections 17 & 18. 38³⁷

40.00 Set post corner for 4 sections, in gulch ²⁰
course N, W.

80.00 Set post corner for sections 7, 8, 17, ²⁵
& 18, on level, above charred
stake dug pit and raised mound
as per instructions.

X Land broken, good grass
Soil 2^d rate,

East on random between sections
8 & 17.

Bar 20° East,

40.00 Set temporary 1/4 section post corner

80.19 Intersected North and south line
54 links North of post corner
N 85° 37' W on true line,

40.00 Set post corner for 1/4 section
on level that slopes to the N, W.
Above charred stake, dug pit
and raised mound as per
instructions,

382 388

Township 4 North, Range 31 East, Will. Mer.
80.19 To post corner,

Land broken, good
X grass, Soil 2^d Rate,

West on random between sections
7 & 18.

40.00 Set temporary 1/4 section post corner,

79.63 Intersected North and south
line 15 links North of post,
N 89° 54' East on true line,

39.63 Set 1/4 section post corner
Above charred stake dug
pits and raised around
as per instructions

79.83 To post corner,

Land broken grass
X good Soil 2^d Rate,

North between sections 7 & 8.

32.50 Stage Road course West,

40.00 Set post corner for 1/4 section
Above charred stake, dug

32
389
Township 4 North, Range 31 East, Will. Mer,

pit and raised mound as
per instructions,

80.00 Set post corner for sections 5, 6.

7 & 8, on level, drove charred
stake along pits and raised
mound as per instructions

+ Land broken, grass
good, Soil 2^d rate,

East on Random between sections
5 & 8,

Bar 21° E

40.00 Set temporary 1/4 section post corner,

79.70 Intersect North and South line
68 links North of Post corner.

N 85° 31' W on true line.

39.85 Set post corner for 1/4 section, on
bank of Prairie course N. W.

80

79.70 To post corner

+
60

Land broken, good grass,
Soil 2^d rate,

+
80

40 390

Township 4 North, Range 31 East Will, Mer,

West on random between sections

6 & 7.

40.00 Set temporary $\frac{1}{4}$ section post corner

79.43 Intersected North and south line
25 links North of post corner

N $89^{\circ}41'$ East on true line,

39.43 Set post corner for $\frac{1}{4}$ section

above charred stake, dug pits
and raised mound as per
instructions,

79.43 To post corner.

Land broken, grass
good Soil 2^d rate,

North between sections 5 & 6,

40.00 Set post corner for $\frac{1}{4}$ section

above charred stake dug
pits and raised mound
as per instructions,

61.00 Bottom of Parvin course N 75°

79.61 Intersected ⁷⁵ Standard Parallel

North 76 links West of Post

A list of the names
of the persons employed to assist
in running measuring or
marking the lines and corners
described in the foregoing field
notes of Township No 4 North
of the Base Line of Range 31 East
of Willamette Meridian, showing
the respective capacities in
which they acted;

J. J. Henderson }
John A. Rigg } Chainmen
P. M. Denney }
A. A. Auman

We hereby certify that we assisted William
 H. Odell, deputy surveyor, in subdividing
 Township No. 4 North of Range 31 East
 of Willamette Meridian, and that
 said Township has been in all respects
 to the best of our knowledge and belief
 well and faithfully surveyed and
 the boundary monuments planted
 according to the instructions furnished
 by the Surveyor General,

J J Henderson	Chairman
J A Prigg	Chairman
J P M. Demney	Member

State of Oregon }
 County of Umatilla } S.S. Subscribed
 and sworn to before me this
 22 day of September 1866.

William Luccallen, Justice of the Peace

J. William H. Odell,

395

deputy surveyor, do solemnly swear that in pursuance of a contract with E. L. Applegate surveyor of the public lands of the United States in the State of Oregon, bearing date July 2nd 1866, and in strict conformity to the laws of the United States and the instructions furnished by said Surveyor General, I have faithfully surveyed the subdivisional lines of Township No. 4 North of Range 31 East of Willamette Meridian in the State aforesaid and do further solemnly swear that the foregoing are the true and original field notes of such survey.

William H. Odell

State of Oregon }
County of Lane } ss Subscribed and
sworn to before me this 22nd day
of December 1866.

Joel Ware

Notary Public

Surveyor General's Office
Eugene City January 11th 1867

The foregoing field notes of the
of the subdivision lines
Survey of Township No 4 North
Range 31 East Will. Mer. Oregon
executed by William H. Odell Dept.
Surveyor under his contract No
114 bearing date July 2nd, 1866
having been critically examined
the necessary corrections and expla-
nations made the field notes and
the Survey they describe are hereby
approved

E. L. Applegate
Surveyor General of Oregon