

# Index

Page	10	10	11	12	12	13	14	15	15	16	17	17	18
Sections	32	33	34	35-	36	31	32	33	33	35	36	31	32

Range 31 East

18	20	20	21	22	23	24	24	25	26	27	28	29	30
33	34	35-	36	39	32	33	34	35-	36	31	32	33	34

Range 33 East

34	32	33	34	34	35-	36	36	37	38	40	40	41	42
35-	36	39	32	33	34	35-	36	31	32	33	34	35-	36

Range 36 East

Range 37 East  
copying this

445

6 446

We William H. Odell and William S. Lewis, having been appointed deputy Surveyors of the lands of the United States in Oregon, do solemnly swear that we will well and faithfully, and to the best of our skill and ability, execute the duties confided to us pursuant to a contract with B. J. Pengra, surveyor general of the public lands in Oregon bearing date the seventh day of February 1865 according to the laws of the United States and the instructions received from the said surveyor general.

William H. Odell,  
William S. Lewis,

State of Oregon }  
County of Washtilla } ss

sworn and subscribed  
to before me this 13<sup>th</sup> day March  
1865-

J. W. Northrup  
A Justice of the Peace

447  
7

We Cyrus Dixon and D. C. Wallace  
do solemnly swear that we will  
faithfully execute the duties of  
chain carriers; that we will level  
the chain upon uneven ground,  
and plumb the tally pins,  
whether by sticking or dropping  
the same, that we will report  
the true distance to all notable  
objects, and the true length of  
all line that, <sup>we</sup> assist in measuring,  
to the best of our skill and ability

Cyrus Dixon  
D. C. Wallace

State of Oregon }  
County of Wmatilla } ss Sworn and  
subscribed to before me this  
13<sup>th</sup> day of March 1865

J. W. Northrup  
A Justice of the Peace

448

~~8~~ 348

I Robert Cook do solemnly  
swear that I will well and  
truly perform the duties of  
Axeman, according to instruc-  
tions given me, and to the  
best of my skill and  
ability.

Robert Cook

State of Oregon }  
County of Yamhill } 38 Sworn  
and subscribed to before  
me this 13<sup>th</sup> day of  
March 1865.

J. W. Northrup  
A Justice of Peace

March 15<sup>th</sup> 1865.

Commenced the survey of the first  
Standard Parallel North of Base Line  
and East ~~between~~ <sup>through</sup> Ranges 31. 32. 33.

34. 35. 36 & 37. between Township 4. 45

North, at the North East Corner of  
Township No 4 North in Range No 30

East of Willamette Meridian, Thence

East on South boundary of section

31 Town <sup>5<sup>th</sup></sup> North in Range 31 East,

Variation 20 East.

40.00 Set Standard corner for 1/4 sec,

Drove charred Stake and dug  
Pit & constructed Mound as per  
Instructions

73.00 Dry Gulch course North West 100

80.00 Set post <sup>Standard</sup> corner for sec 31 & 32. 60

Drove charred Stake and raised  
Mound with pits as per Instruction

This line passes over Rolling  
grounds good grass and  
Timber Soil 2<sup>nd</sup> Rate

~~12 352~~ 452

First Standard Parallel North  
This line passes over broken  
land good grass 2<sup>nd</sup> Rate

East on South boundary of sec,  
35 Township No 5 N Range 31 E,  
Bar. 20° East,

40.00 Set post Standard corner for 1/4 Sec  
Drove charred Stake dug pits  
and raised Mound as per  
Instructions,

80.00 Set post corner for sections 30  
35 & 36, on steep hill side sloping  
the North West, Drove charred  
Stake, dug pits, and raised  
Mound as per Instructions,  
Land Broken good  
grass 2<sup>nd</sup> Rate,

East on South boundary of section  
36 Township No 5 N Range 31 E,  
Bar 21° East,

Between T. 495 N in Range 31 East of Will. Mer.

40.00 Set post Standard Cor, for 1/4 Sec.

Drove charred Stake, dug pits and raised Mound as per Instructions

80.00 Set post Standard corner for 80<sup>+</sup>

Townships N. 5 North in Ranges

31 & 32, also sections 36 & 31.

Drove Charred Stake, dug pits and raised mound as per Instructions.

This line passes over land high and rolling good grass soil 2<sup>nd</sup> Rate

Thursday March 16<sup>th</sup> 1865.

East on South boundary of Sec,

31. Township N. 5 N. Range 32 East.

Bar 21<sup>st</sup> E.

40.00 Set post Standard corner for

1/4 Sec. Drove charred Stake

dug pits & raised Mound

as per Instructions.

80.00 Set post Standard corner for

First Standard Parallel North Between  
sections 31 & 32, on hill side  
facing the East, Drove  
Charred Stake, dug pits and  
raised Mound as per  
Instructions

This line passes over quite  
broken land good grass.

Soil 2<sup>nd</sup> Rate

East on South boundary of  
section 32 Township R. 5 N. Range  
32 E,

Per 20<sup>th</sup> E,

4000 Set post standard cor for 14 Sec  
on hill side sloping to the  
South East, Drove Charred  
Stake dug pits and raised  
Mound as per Instructions,

75.60 Dry Gulch Course N. W. 60

80.00 Set post cor, per sections  
32 & 33. Land slopes to the  
S. W. Drove Charred Stake, dug



Township 45 N. Range 32 East Will Mer,  
 pits and raised Mound as  
 per Instructions,  
 Land Broken good grass  
 Soil 2<sup>nd</sup> Rate

East on South boundary of section  
 33 Township N. 5 N. in Range 32 East,  
 Cor. 20° E,

10.00 Set post Standard Corner for 1/4 Sec 30  
 Drove Churned Stake, dug pits  
 and raised Mound as per  
 Instructions.

80.00 Set post Standard corner for sections  
 33 & 34 Drove Churned Stake, dug  
 pits and raised Mound as per  
 Instructions  
 Land quite Broken good  
 grass Soil 2<sup>nd</sup> Rate

East on South boundary of sec  
 34. Township N. 5 N. Range 32 E—  
 Cor 20° E.

First Standard Parallel North Between  
4000 Set post Standard Corner for ~~sec 4~~ Sec  
Drove Charred Stake dug pits  
and raised Mound as per  
Instructions.

8000 Set post Standard corner for  
sections 34 & 35. Drove Charred  
Stake dug pits and raised  
Mound as per Instructions,  
Land Rolling good  
Grass Soil 2<sup>nd</sup> Rate

East on South boundary of sec, 35  
Township N. 5 N. Range 32. East  
Bar 20° E.

4000 Set post Standard Corner for 4 Sec,  
Drove Charred Stake dug  
pits and raised Mound  
as per Instructions.

8000 Set post Standard Corner for  
sec 35 & 36 Land slopes to  
the South, Drove Charred  
Stake dug pits & raised

Township 45 N. in Range 32 East Well Mer  
Mound as per Instructions.  
This line passes over rolling  
land good grass Soil 2<sup>d</sup> Rate

East on South boundary of section  
36 Township 5 N. Range 32 East.

Bar, 20<sup>th</sup>.

40.00 Set post Standard Corner for 1/4 Sec.  
Drove Charred Stake dug pits as  
per Instructions.

80.00 Set post Standard corner for  
Townships 5 North in Ranges  
32 & 33 East. Drove Charred  
Stake dug pits and raised  
Mound as per Instructions.  
Land gently rolling  
good grass Soil Good  
2<sup>nd</sup> Rate

East on South boundary of  
section 31 Township 45 N.  
Range 33 East

Townships 4 & 5 north In Range 37 East.

Fir Tree 20 inches in diam N. 24° 31' E. 19 Sinks

Fir Tree, 10 do do do S. 4° 30' W. 80 do

Fir Tree 8. do do do N. 73° W. 60 Sinks.

This Line Passes through Heavy  
Timber Fir, Pine & Larch.

Undergrowth Same & Vine  
Maple. Land gently rolling.

This Standard line passes  
over high rolling lands  
covered with good grass  
along the whole extent  
affording an extensive  
range for stock, But  
from the fact that water  
is scarce over most of the  
distance the land will  
not be considered very  
valuable until enterprise  
shall sink wells to  
give water to stock,

which can be done  
 at very little expense,  
 The timbered lands  
 in the Mountains  
 are considered valuable  
 and would soon be  
 entered by the settlers  
 in the Valley if offered  
 at public or private  
 sale.

The Standard Parallel of  
 which the foregoing are the  
 field notes was surveyed  
 Deputy W. H. Odell assisted  
 through Ranges 31, 32, 33, 34, 35  
 & 37 by Cyrus Dixon } Chairman  
 D. C. Wallace }  
 Robert Cook } Axman  
 Through Range 36 by  
 W. W. Johnson Compassman  
 C. C. Harcane } Chairman  
 A. Shibles }  
 William Warren Axman

I William H. Odell, do hereby certify that the foregoing are the true and original field notes of the survey of the First Standard Parallel North between Townships 5 & 6 North and East through Ranges 31, 32, 33, 34, 35, 36 & 37, East of Willamette Meridian, made under contract No. 110, bearing date February 7<sup>th</sup> 1865, in accordance with the laws of the United State and the Instructions furnished by the Surveyor General, as will appear from affidavits duly made out and attached to the field notes of Township No. 5 North of Range 36 East of Will; Mer;

William H. Odell

Deputy Surveyor

Surveyor General's Office  
Eugene City, Aug. 23, 1865

The foregoing field notes of the survey of  
the 1<sup>st</sup> Standard Parallel North through  
Ranges 31, 32, 33, 34, 35, 36 and 37 E  
Will. Mer. Oregon, executed by Odell &  
Lewis, Deputy Surveyors, under their con-  
tract No. 110, bearing date Feby. 7<sup>th</sup>  
1865, having been critically examined  
the necessary explanations and corrections  
made, the said field notes and the sur-  
veys they describe are hereby ap-  
proved.

E. L. Applegate  
Surveyor General of Oregon.