

Field notes of the Survey of the Exterior  
boundaries of Township No 3 North of  
Range No 32 East of the Willamette  
Meridian in the State of Oregon by  
Savior P Thompson deputy Surveyor  
pursuant to his contract No 106 bearing  
date the 16<sup>th</sup> day of August 1864

Commenced September 14<sup>th</sup> 1864  
Completed September 15<sup>th</sup> 1864

Field notes of the Survey of the Exterior  
boundaries of Township No 3 North of  
Range No 32 East of the Willamette  
Meridian in the State of Oregon by  
Sevier P Thompson deputy Surveyor  
under his contract No 106 bearing  
date the 16<sup>th</sup> day of August 1864

Commenced September 14<sup>th</sup> 1864  
Completed September 15<sup>th</sup> 1864

Exterior boundaries of Township 3  
 North on East boundary of Sec 12  
 Variation  $20^{\circ}E$

4000 Set post for  $\frac{1}{4}$  Sec corner in corner  
 of Earth with charred stake pits trench  
 & asper instructions

8000 Set post for corner to Sec 6, 7, 12  
 in corner of Earth with charred  
 stake pits trench & asper instructions  
 Land gently rolling  
 Soil good  $\frac{2}{1}$  rate

North on East boundary of Sec 1  
 Variation  $20^{\circ}E$

4000 Set post for  $\frac{1}{4}$  Sec corner in corner  
 of Earth with charred stake pits  
 trench & asper instructions

8000 Set post for corner to Township  
 3 & 4 North Ranges 33 & 33  
 East in corner of Earth with charred  
 stake pits trench & asper instruc-  
 = tions  
 Land gently rolling  
 Soil  $\frac{1}{1}$  rate



Extensive boundaries of Township 3  
 N 9° 48' E. on north boundary of Sec 5  
 Variation 1930' East

4000 Set post for 1/4 Sec corner in Monney  
 Earth with charred stake pits trench  
 & as per instructions

8000 Set post for corner to Secs 4, 5, 32 & 33  
 in Monney of Earth with charred stake  
 pits trench & as per instructions  
 Seed gently polling  
 Soil 2<sup>nd</sup> rate

N 9° 48' E. on north boundary of Sec 4  
 Variation 1930' East

4000 Set 1/4 post in Monney of Earth with  
 charred stake pits trench & as per  
 instructions

8000 Set post for corner to Secs 3, 4, 33 & 34  
 in Monney of Earth with charred  
 stake pits trench & as per  
 instructions  
 Seed gently polling  
 Soil 1<sup>st</sup> rate

North Range 32 East Willamette Meridian

N<sup>89°48'E</sup> on North boundary of Sec 3

Variation 20° East

4000 Set post for  $\frac{1}{4}$  Sec corner in Mound  
of Earth with charred Stake pit trench  
& as per instructions

8000 Set post for corner to Secs 2, 3, 34 & 35  
in Mound of Earth with charred  
Stake pit trench & as per instructions  
Ground pretty rolling  
Soil  $\frac{1}{2}$  rate

N<sup>89°48'E</sup> on North boundary of Sec 2

Variation 20° East

4000 Set post for  $\frac{1}{4}$  Sec corner in Mound  
of Earth with charred Stake pit  
trench & as per instructions

8000 Set post for corner to Secs 1, 2, 34 & 36  
in Mound of Earth with charred  
Stake pit trench & as per  
instructions

Ground pretty rolling  
Soil  $\frac{1}{2}$  rate

267

27

3<sup>rd</sup> N Range 32 E Willamette Meridian

Extreme boundaries Township

N 89° 48' E on North boundary of sec 1

Variation 20° East

4000 Set post for 1/4 Sec corner in bound  
of Earth with charred stake pit stencils  
&c as per instructions

8000 The corner to Townships 3 & 4 North

Range 32 & 33 East

Var 20° 30' East

Land gently rolling

Soil 1<sup>st</sup> rate Sept 15<sup>th</sup> 1864

### General Description

The land in this Township is generally  
level or gently rolling.

The soil is 1<sup>st</sup> and good 2<sup>nd</sup> rate  
and is covered with a very heavy  
growth of grass

There is no timber in this Township  
There are a few springs but no streams  
but water can be had by digging wells  
anywhere in the prairie

It should be submerised

The Survey of the Townships on the South of the Base line may not have been Surveyed in the order that they should have been but in the absence of any instructions in regard to the Survey of Townships South of a Base Line before the Meridian Parallel were run I did what I thought best under the circumstances and commenced a run of Meridian South from the same corner where the Meridian North leaves the Base Line and run South East and North to intersect the base line and set closing corners on the base line through both Townships.

On the Survey of Township 1 North Range 32 East I remeasured the South boundary and set half mile and mile posts commencing at the South East corner as this had been the instruction that was given in regard to the error on the base line in measuring it and making the Exception on the West boundary



On the West of Townships 182 South  
 Range 31 East there is some country  
 that is of some value as a grazing  
 country but there is no farming  
 land for a considerable distance  
 in that direction. On the South  
 of Townships 2 South Ranges 31 & 32  
 East is steep rugged mountains  
 of no value and there is no probability  
 that there will be ever any necessity  
 for more surveys in that direction  
 and the same will apply to Township  
 182 S. Range 32 East as they run as  
 high on the West Slope of the Blue Moun-  
 tains as the land is of any value for  
 "farming grazing or lumber". This will  
 also apply to Township 1 North Range  
 33 East as the East boundary is high  
 up in steep rugged story mountains.  
 On the East of Townships 2 & 3 North  
 Range 33 East is the best land in  
 this section of country being along  
 the Base of the Blue Mountains which  
 run North East and South West but  
 this country is on the Mwatilla Indian  
 Reservation W. H. Barnhart Agent

who informed me that there were about 1080 Indians old and young on the Reservation composed of Cayuse. Walla Walla and a part of the Yakama Tribe of Indians. He also stated that a treaty should be made with these Indians and the land purchased from them and the Indians sent to the Warm Spring. Yakama and Nezperce Reservations as the Indians here about one third speak the Nezperce language are <sup>inter</sup> married with them and are in fact a part of that tribe. The same is true of the other two thirds with the Yakamas and Warm Spring Indians. The Reservation is immediately on the great thoroughfare between the Columbia and the Gold Mines of Oregon and Idaho Territory more than one hundred thousand persons pass through this Reservation yearly to and from the mines.

The Reservation should be abolished and the Indians given other land where they will not be thrown so much in contact with the whites.

if such a treaty can be made with them, and the rich lands that they now occupy thrown open for settlement and this will become one of the most productive districts of country East of the Cascade Mountains.

On the north of Townships 3 North Range 32833 East the country is gently descending for about twelve miles then is then a short ascent to Waller Waller Valley. The lands in this section and for many miles to the North East along the northern boundary of the State is fast attracting lands with at least two hundred settlers many of whom have been on their lands for from four to seven years and are very anxious to have the lands surveyed so they may know where their lands are and get their titles to them. Surveys are more needed in this part of the country than any I know of in the State. Now that the boundary line between the State of Oregon and the Territory of Washington

has been established the settlers  
hope and expect that it will be  
Speciaily Succeeded

### List of Names

A List of the names of the men  
employed to assist in measuring and  
marking the lines and corners as shown  
in the foregoing field notes of the  
Eastern townships of Townships 1, 2 & 3 north  
of the base line of Ranges 32 & 33 East  
and Townships 1 & 2 South Ranges 31  
& 32 East of the Willamette Meridian  
showing the respective capacities  
in which they acted

G. S. Dotson Chairman  
J. W. Newman        "  
A. McLean        Assessor

337

We hereby certify that we Assistant  
 David P Thompson deputy Surveyor in surveying  
 the exterior boundaries of Townships  
 1283 North of the base line of Range  
 32833 East and of Townships 182  
 South of the Base line of Ranges 318  
 32 East of the Willamette Meridian  
 and that since Exterior lines have been  
 in all respects  
 to the best of our knowledge and ability  
 well and faithfully surveyed and the  
 boundary monuments planted accord-  
 -ing to the instructions furnished  
 by the Surveyor General

J. S. Gotsch on chairman  
 W. Newman  
 A. H. Sean Aeman

Sworn and subscribed before  
 me this 8<sup>th</sup> day of November 1864

David P. Thompson

Notary Public Justice of the Peace

98

I Daire P Thompson deputy Surveyor

338

do solemnly swear that in pursuance  
of a contract with B. J. Puzer Surveyor of the public  
land of the United States in the State of Oregon  
bearing date the 16<sup>th</sup> day of August 1864 and  
in strict conformity to the laws of the United States  
and the instructions furnished by the Senior Sur-  
veyor General I have faithfully surveyed the  
Esteris boundaries of Townships 1. 2. 83  
North of the base line of Ranges 32 & 33 East  
of the Willamette meridian and Townships  
1 & 2 South Ranges 31 & 32 East of the Willamette  
meridian in the State of Oregon and  
do further solemnly swear that the foregoing  
are the true and original field notes  
of such survey and that the Township  
corner posts referred to in the notes are  
not less than four (4) feet long two (2) feet  
in the ground by five (5) inches in diameter  
two (2) feet above ground by four (4) inches  
square and the quarter section corner

339

posts are of the same length & depth in the  
 ground and height above it by three (3)  
 inches in the width: that the corners  
 and corner stones have been constructed  
 of not less size and dimensions pre-  
 scribed in the Manual; and that all  
 the lines and corners have been marked  
 and continued in every respect as  
 required by the surveying instructions  
 at pages 2 to 11 inclusive and that  
 they are calculated to ensure the ordinary  
 natural deterioration

David P. Thompson  
 Deputy Surveyor

Sworn and subscribed to before me  
 this 26<sup>th</sup> day of November 1864

W. A. Barlow  
 Justice of The Peace  
 for Clatsop Co. Oregon

Surveyor Generals office  
Cincinnati

The foregoing field notes of  
the Survey of the Exterior bound-  
ary lines of Townships No. 1-  
2 & 3 N. R. No. 32 E  
Townships No. 2 & 3 N. Will.  
R. No. 33 E of the Base  
line, and Townships No.  
" 1 & 2 S. R. 31 E. Townships  
1 & 2 S. R. 32 E of the Base  
line



340 1/2

340A

Dec. 25<sup>th</sup> 1864

Surveyor General's Office  
Eugene City Dec. 25<sup>th</sup> 1864  
The foregoing field notes of the  
Survey of the Exterior lines of  
Townships Nos. 1, 2 & 3 N. of  
the Base line R. 32 E. of Tps.  
2 & 3 N. of the base line R. 33 E.  
of the Willamette Mer. Tps. No.  
1 & 2 S. R. 31 E. Tps. 1 & 2 S  
of the Base line Range 32 E.  
of the Willamette Meridian  
Executed by David P. Thompson  
under his Contract No. 106  
bearing date the 16<sup>th</sup> day of  
August 1864. Having been  
critically examined, the  
necessary explanations &  
corrections made the  
said field notes and the  
surveys they describe  
are hereby approved  
J. J. Penza  
Surv. Genl.  
of Oregon