

Index.

Referring the lines to the pages of the field notes
 Township 4 North, Range 34 East, Will. Mer.

6	38	5	28	4	22	3	15	2	8	1
57		37		28		21		14		8
17	36	8	27	9	21	10	14	11	7	12
35		35		26		20		13		7
18	34	17	26	16	19	15	13	14	6	13
34		23		25		19		12		5
19	33	20	25	21	18	22	12	23	5	24
32		31		27		18		11		4
30	31	29	24	28	17	27	11	26	3	25
30		29		23		16		10		3
31	29	32	23	33	16	34	9	35	2	36

Field Notes of the subdivision
lines of Township No. 4 North
Range 34 East of Willamette
Meridian.

Subdivision commenced
July 31st 1866.

From the corner to sections
1. 2. 35 & 36. on the South
boundary of the Township.

I run
North between sections 35 & 36.

40.00 Set post corner for 1/4 section
drove charred stake; dug pits;
and raised mound as per
instructions.

80.00 Set post corner for sections 25, 26 level
35 & 36, drove charred stake; dug
pits; and raised mound as
per instructions.

Land gently rolling, good

430

Township No 4 North Range 34 East, Will-Mer-

Bar 20° East.

40.00 Set temporary $\frac{1}{4}$ section post corner

79.52 Intersect North and south line

56 links North of post.

N 89° 36' W. on true line.

39.76 Set post corner for $\frac{1}{4}$ section, drove
charrred stake, dug pits and raised
mound as per instructions

79.52 To post corner.

Land rolling, good grass,
Soil 2^d Kate,

+

West on random between sections

30 & 31.

40.00 Set temporary $\frac{1}{4}$ section post corner,

80.08 Intersect North and South line

22 links South of post corner,

S 89° 51' E on true line.

40.08³ Set post corner for $\frac{1}{4}$ section

drove charrred stake, dug
pits and raised mound as
per instructions.

31 431

Township No. 4 North, Range 34 East - Will-Mer-

80.08 To post corner,

Land rolling, good grass,
Soil 2^d rate.

X

North between sections 29 & 30.

40.00 Set post corner for 1/4 section.

drove charred stake dug pit, and
raised mound as per instructions

80.00 Set post corner for sections 19, 20,

29 & 30, drove charred stake dug
pits and raised mound as
per instructions.

Land rolling, grass excellent,
Soil 2^d rate.

X

East on random between sections
20 & 29.

Bar 21° East

40.00 Set temporary 1/4 section corner

79.47 Intersected North and South
line 36 chs North of post
corner.

Township N. 4 North, Range 34 East, Will-ell-
 N 89° 45' W on true line.

3973 Set post corner for 1/4 section
 drove charred stake dug pits,
 and raised mound as per
 instructions,

7947 Go post corner,
 Land rolling grass Excellent
 Soil 2^d rate.

X

West on random between sections
 19 & 30.

4000 Set temporary 1/4 section post corner

8012 Intersect North and south line
 17 lbs South of post,

S. 89° 53' E. on true line.

4012 Set post corner for 1/4 section,
 drove charred stake dug pits,
 and raised mound as per
 instructions.

8012 Go post corner.

Land rolling, grass

Excellent, Soil 2^d Rate

E

Township 4th North, Range 34 East, Will. Mer.

North between sections 17 & 20.

40,000 Set post corner for 1/4 section, drove charred stake dug pits and raised mound as per instructions.

80,000 Set post corner for sections 17, 18,

19 & 20. Drove charred stake dug pits and raised mound as per instructions.

Land rolling grass excellent

* Soil 2^d rate,

East on random between sections 17 & 20.

Bar 21° East,

40,000 Set temporary 1/4 section post corner

79,65 Intersected North and South line

28 lbs North of post.

N 89° 48' West on true line

39,82 Set post corner for 1/4 section, drove

charred stake, dug pits and raised mound as per instructions.

79,65 To post corner,

Land rolling, grass.

Township No 4 North, Range 34 East Will. Mer-
excellent, Soil 2nd Rate-

x

West on random between sections
18 & 19.

40.00 Set temporary 1/4 section post,
corner,

80.07 Intersected North and South
line 23 lbs South of post.
S 89° 50' E on true line

40.07 Set post corner for 1/4 section.
Drove charred stake, dug pit,
and raised mound as per
instructions

80.07 To post corner
Linnel rolling, grass
good, Soil 2nd rate
August 4th 1866.

x

North between sections 17 & 18,

40.00 Set 1/4 section corner post
dove charred stake dug pit
and raised mound as per

35

435

Township No 4 North, Range 34 East, Wyo. No.,
instructions

80.00 Set post corner for sections 7, 8, 17 & 18

drove charred stake, dug pits, and
raised mound as per instructions.

Land rolling, grass excellent
soil 2nd rate,

X

East on random between sections

8 & 17.

Bar 21° East.

40.00 Set temporary $\frac{1}{4}$ section corner post.

79.71 Intersected North and South line

39 lbs north of post.

N 89° 43' W. on true line.

39.85 Set post corner for $\frac{1}{4}$ section, drove
charred stake, dug pits, and
raised mound, as per instructions

79.71 To post corner.

Land rolling grass
excellent. Soil 2nd Rate,

West on random between section

436

Township No. 4 North, Range 34 East, Will. Mer-
7418.

40.00 Set post corner for 1/4 section temporary

80.09 Intersected North and south line
25 links south of post corner,
S, 89° 49' E, on true line.

40.09 Set post corner for 1/4 section, drove
charred stake, dug pits and raised
mound as per instructions.

80.09 Go post corner.

Land rolling, grass
excellent - Soil 2nd Rate.

X

North between sections 748

40.00 Set post corner 1/4 section corner
drove, charred stake, dug pits,
and raised mound as per
instructions.

80.00 Set post corner for 1/4 sections
5. 6. 748. drove charred stake,
dug pits, and raised mound
as per instructions.

Land rolling, good grass, soil 2nd Rate

+

372 437

Township No. 4 North, Range 34 East, Will-Mer-

com East on random between sections 548

40.00 Set temporary $\frac{1}{4}$ section post corner

79.76 Intersect North and south line

18 links North of post corner,
 $N 89^{\circ} 52' W$ on true line

39.88 Set post corner for $\frac{1}{4}$ section, drove
charred stake, dug pit and
raised mound as per instructions

79.76 To post corner.

Land rolling, grass excellent,

+ Soil 2 $\frac{1}{2}$ Rate.

West on random between sections
647.

Bar 20° East.

40.00 Set temporary $\frac{1}{4}$ section post corner

80.23 Intersect N & S line 42 links
South of post corner.

$S 89^{\circ} 42' E$ - on true line.

40.23 Set post corner for $\frac{1}{4}$ section, drove
charred stake dug pit and
raised mound as per instructions.

A list of the names of the individuals employed to assist in running, measuring, or marking the lines and corners described in the foregoing field notes of Township No. 4 North of the Base Line of Range No. 34 East of Willamette Meridian, showing the respective capacities in which they acted:

J. J. Henderson	} Chairmen
John A. Bigg	
P. M. Demney	Axeman

+

We hereby certify that we assisted
William H. Odell, deputy survey, in
surveying the subdivisioinal lines of
Township No 4 North of Base Line of Range
No 34 East of Willamette Meridian, and that
said Township has been in all respects, to the
best of our knowledge and belief, well and
faithfully surveyed and the boundary
monuments planted according to the
instructions furnished by the Surveyor
General.

J J Henderson Chairman
J A Pigg Chairman
P C M. Demmey Foreman

State of Oregon
County of Washtilla } ss, Subscribed and
Sworn to before me this day
of September A.D. 1866, at
William L. Waller
Justice of the Peace

I William H. Odell, deputy surveyor, do solemnly swear that, in pursuance of a contract with E. S. Applegate surveyor of the public lands of the United States in the State of Oregon, bearing date the 2^d day of July 1866, and in strict conformity to the laws of the United States and the instructions furnished by said Surveyor General, I have faithfully surveyed the subdivisions of Township number 4 North of the Base Line of Range 34 East of the Willamette Meridian, in the State aforesaid, and do further solemnly swear that the foregoing are the true and original field notes of such survey.

William H Odell

State of Oregon }
 County of Lane } ss. Subscribed
 and sworn to before me this
 22^d day of December 1866

Joel War

Notary Public

449
Surveyor General's Office

Eugene City, Jan 17th 1867

The foregoing field notes of the survey of
the Subdivisional series of Township No 4
North Range 34 East Will. Mer. Oregon
Executed by William H. Odell, Deputy
Surveyor under his contract No 114 bearing
date July 2nd. 1866 having been critically
examined the necessary corrections and
examinations made the field notes and
the surveys they describe are hereby
accepted

E. L. Applegate

Surveyor General of Oregon