

250 250 B

Index

Referring to the pages of the field notes.

Town 3 N. Range 36 E. Will. Mer-

14	15	16	17	18	19
6	5	4	3	2	1

12 17

all of this

13 10

24 9

25 9

31	32	33	34	35	36
2	2	33	4	5	6

7

Field notes of the survey of
the exterior lines of Township
number 3 North of the Base
Line of Range 36 East of Willamette
Meridian in the State of Oregon
by William H. Odell, deputy
Surveyor under his contract
No 114 bearing date July
2nd 1866.

Commenced September 3rd
1866 and completed
September 25th 1866.

Township 3 North Range 36 East

North on East boundary
of section 1,

Bar 16° East,

40.00 Set post corner for 1/4 section ⁵⁰

from which,

A Larch 10 in. dia bears N 15° W, 32 lbs

do - do - 12 do - do - do - S 35° E 26 do

Bar 20° East -

80.00 Set post corner for Townships

344. North Range 36437

East Sections 1, 6, 31, 36,

from which

A Fir 10 in dia bears N 10° W, 24 lbs

do - do - 8 do - do - do - N 55° E, 20 do,

do - do - 6 do - do - do - S 45° E, 30 do -

do - do - 12 do - do - do - S 3° W, 18 do,

This line passes through
thick timber, considerable
of it fallen. Timber Fir and
Larch. Under growth the
same with Willow

September 5th / 1866,

264

Township 3 North Range 36 East,

West on North boundary

bur $19^{\circ}30'$ East

At 40.00 and 80.00 chains
set half mile and mile post
temporarily and intersect
Western boundary 2 chains
and 87 links South of
post corner, 5 miles and
77 chains 31 links;

Therefore the connection
will be $S 89^{\circ}39'$ East on
true line,

September 25th 1866.

$S 89^{\circ}39'$ E. on North boundary
of section 6.

37.31 Set post corner for $\frac{1}{4}$ section 60

deposited marked stone
and made stone mound
as per instructions.

53.00 Pine Creek channel dry
course $S 75^{\circ} W$.

Township 3 North Range 36 East

77.31 Set post corner for sections 5, 6, 31. 300⁺

732 on steep hillside facing the north from which

A Pine 12 in-dia-bears N, 88° E, 94 lbs

do- do- 10. do- do- do- S, 85° E, 90 do-

do- do- 12 do- do- do- S, 35° W, 12 do-

do- do- 12 do- do- do- N 78° W, 65 do-

This line passes up Pine Creek, the bottoms very narrow and crooked and the hillsides on the north steep and rocky, without timber, on the south timbered Pine & Fir.

See how to Record
S 88° 35' E on north boundary of section 5.

Bar 21° East.

40.00 Set post corner for 4 section on hillside facing the north from which

A Larch 8 in-dia-bears N, 75° E, 59 lbs

do- Fir 12 do- do- do- S, 78° W, 42 do-

80.00 Set post corner for sections 4, 5. 22933 150

Township 3 North Range 36 East
 on hillside facing the north
 from which

A Fir 18 in-dia-bears North 20 the

do- do- 10 do- do- do- N 50° W, 64 do-

A Pine 6 do- do- do- S, 40, W, 18 do-

No tree near in section 4

This line passes over very
 broken hillsides facing the north
 scattering timber, soil stony;

S 89° 39 E on North boundary
 of section 4

bar 20° East.

3.00 Pine Creek channel dry 150 150

course N 70° W-

28.25 Pine Creek channel dry course S.W.

40.00 Set post corner for 1/4 section 600 600

from which

A Pine 36 in-dia-bears South 7 the

do- do- 24 do- do- do- N 85° W 80 do-

8.000 Set post corner for sections 3.4,

33 & 34. from which

Township 3 North Range 36 East, ²⁶⁷

A Larch 20 in-dia-bears-S, 76° W. 20 lbs

do- do- 10 do- do- do-N, 40° E, 18 do-

do- do- 5 do- do- do-S, 3° E, 22 do-

no green tree near in section

33. This line passes

up Pine Creek the hill
sides steep & rocky.

Good grass on the summit
to the north.

S 89° 39' E on North boundary
of section 3

Bar 20° East-

4000 Set post corner for 4 section
from which

A Larch 4 in-dia-bears-S, 84° E, 18 lbs

do- do- 3 do- do- do-N, 15° W 13 do-

8000 Set post corner sections 2. 3. 34 & 35.

from which

A Fir 20 in-dia-bears N, 2° E, 40 lbs

do- do- 3 do- do- do-N 55° W, 29 do,

do- do- 3 do- do- do-S 57° W 25 do-

Township 3 North Range 36 East

A Fir 24 in-dia-bears East 28 lbs

This line passes through thick
timber of small growth,

Considerable down timber

Undergrowth thick,

Timber Fir Larch

and Pine Undergrowth

the same with willow.

Com

$S 89^{\circ} 35' E$ on North boundary
of section 2,

Bear 19° East-

4000 Set post corner for $\frac{1}{4}$ section
from which

A Larch 12 in-dia-bears $N 60^{\circ} W$, 30 lbs

do- do- 8 do- do- do- $S 40^{\circ} E$ 38 do-

8000 Set post corner for sections

1. 2. 35 & 36. from which

A Fir 18 in dia-bears $S 88^{\circ} E$, 35 lbs

do, do- 6 do- do- do- $N 10^{\circ} E$, 110 do-

do do 14 do- do- do- $N 45^{\circ} W$ 60 do-

Township 3 North Range 36 East 269

A Fir 12 in-dia-bears West, 40 lbs
This line passes through
thick timber, valuable to
farmers, considerable dead
and fallen Undergrowth
thick, making it tedious
getting through.

Timber Fir Sarch
and Pine, Undergrowth
the same with Willow,

Began

S 85° 39' E on North boundary
of section 1.

bar 18° 30' E.

40.00 Set post corner for 1/4 section
on hillside facing the west
from which

A Fir 10 in-dia-bears N 80° W, 43 lbs
do- do- 8 do- do- do- S 77° W 50 do-

80.00 To post corner,

This line passes along
near the break of the hill

770
Township 3 North Range 36 East
towards Pine Creek to the
north.

The timber of small growth
considerable dead and fallen
undergrowth thick. Larch
Fir & Willows.

271²¹

Township 3 North Range 36 East -

The South West corner of this Township is on the Armatillo Reservation and all of that portion South the Armatillo River except immediately along the river bottoms is wholly unfit for settlement. That portion on the north side will in time be settled nearly all of this portion is valuable for its timber. The farmers are cutting and drawing away large quantities of it for fencing and building purposes.

Consequently that portion should be subdivided and put into the market as soon as practicable in order that the Government may

have the benefit of the
proceeds of the sale of such
land and the adjacent
farmers may secure a
title to the timbered land
so that personal interest
will prompt them to guard
against unnecessary waste.
September 26th 1866.

A list of the names of the persons employed to assist in running measuring or marking the lines and corners described in the foregoing field notes of the Exterior boundaries of Township No 3 North of the Base Line of Range 36 East of Willamette Meridian, showing the respective capacities in which they acted.

J. J. Henderson, }
 John A. Riggs } Chairman
 P. M. Denney Axeman.

Carroll J. Applegate

William H. Odell, ²⁷⁵

Deputy surveyor, do solemnly swear that in pursuance of a Contract entered into with E. L. Applegate surveyor of the public lands of the United States in the State of Oregon, bearing date July 2^d 1866, and in strict conformity to the laws of the United States and the instructions furnished by said Surveyor General, I have faithfully surveyed the Exterior boundaries of Township number 3 North of the Base line of Range 36 East of Willamette Meridian, in the State aforesaid, and do further solemnly swear the foregoing are the true and original field Notes of such survey.

William H. Odell

State of Oregon

County of Lane

} ss. Subscribed, and

Sworn to before me, this 23^d day of December 1866.

Joel Ware

Notary Public

We hereby certify that we assisted
 William H. Odell Deputy surveyor, in
 surveying the exterior boundaries of
 Townships No 3 North of Ranges No
 35 & 36 East of Willamette Meridian, also
 No. 4 North of Ranges 34 & 35 East of
 Willamette Meridian, and that said
 exterior boundaries have been in all
 respects, to the best of our knowledge and
 belief well and faithfully surveyed and the
 boundary monuments planted according
 to the instructions furnished by the Surveyor
 General.

J J Henderson Chairman
 J A Trigg Chairman
 P A. Demney Assessor

State of Oregon }
 County of Wasatch } 33 Subscribed and
 Sworn to before me this day
 of September A. D. 1866.

William Luellen Justice of the Peace

com

278

Surveyor General's Office
Eugene City January 17 1867

The foregoing field notes of the survey
of the Exterior boundaries of Township
N^o 3 North Range 36 East Will. Mer
Oregon executed by William H
Odell. Deputy Surveyor under his
contract N^o 114. bearing date
July 2nd. 1866 having been critic-
ally examined, the necessary correc-
tions and explanations made
the field notes and the surveys
they describe are hereby approved

E. I. Applegate

Surveyor General of Oregon

Recd
to this