

501

Index

Township 4 North, Range 36 East, Will, Mer,

6	41	5	31	4	24	3	16	2	8	1
40		39		30		23		16		8
7	39	8	29	9	22	10	15	11	7	12
38		37		29		22		14		7
18	37	17	28	16	21	15	14	14	6	13
36		36		28		21		13		6
19	35	20	27	21	20	22	12	23	5	24
34		34		27		19		12		4
30	33	29	26	28	19	27	11	26	4	25
32		32		25		18		10		3
31	31	32	25	33	17	34	9	35	2	36

Field Notes of the
 Subdivision lines in Township
 4 North of the Base Line of Range
 36 East of Willamette Meridian

Commence at post corner for
 sections 1, 2, 3, 5 & 36, on south
 boundary of Township

Hence

North between sections 35 & 36,

15.00 Pine Creek channel dry course W, 140

40.00 Set post corner for $\frac{1}{4}$ section from 130

Which a Pine 30 in dia bears N 85° W 165 Links

do. do, 36 do-do-do- South 300 do-

80.00 Set post corner for sections 25, 26, 35 & 36.

from which

a Fir 24 in dia bears N 40° W, 22 links

do, do, 7 do, do, do, S 15° E 13 do,

do, do, 10 do, do- do- S 20° W, 19 do,

do- Willow 4 do- do- do- N 35° E, 21 do-

The north $\frac{1}{2}$ of this mile passes

3 2 503

Township 4 North, Range 36 East Will. Mer.

through open pine timber
well suited for lumber.

South half through thick timber
of small growth.

Lumber fir and Larch,

Soil 2^d rate,

x

East on random between
sections 25 & 36.

Bar 21° East,

40.00 Set temporary 1/4 section corner,

79.92 Intersected North and South line

31 links South of post corner,

S 89° 47' W on true line

39.96 Made corner for 1/4 section on Larch

tree 12 in. dia. from which

A Larch 14 in. dia. bears South 7 links

do. do. 16 do. do. do. N 75° W, 26 do

79.92 To post corner,

Land gently rolling, Lumber

Pine Fir and Larch, Undergrowth

the same with Willow, Soil 2^d rate.

x

504⁴
Township 4 North Range 36 East Will. Mer.

North between sections 25 & 26.

40.00 Set post corner for $\frac{1}{4}$ section,

40.00 from which a pine 20 in dia

bears South 10° W 350. lbs not

other tree near mounds Stone Mound
as per instructions.

80.00^{90.00} Set post corner for sections 23, 24,

25 & 26. on hillside facing the East.

Drove charred stake ~~any~~ feet and

Mound Stone Mound as per instructions

Land rolling good grass

Lumber Fir & Pine,

Soil. 2^d Rate,

x

East on random between sections

24 & 25,

Bear $15^{\circ} 30'$ East,

40.00^{40.00} Set temporary $\frac{1}{4}$ section corner,

77.87 Intersect North and South line

41 links South of post corner

$89^{\circ} 43'$ W on true line

x

5/2 505
 Township 4 North Range 36 East Will. Mer.

39.93	Set Bassalt Stone 5 x 10 x 15. for $\frac{1}{4}$ section corner, on hillside facing the west,	70
67.50	Bottom of ravine course North	340
79.87	Lo post corner	+ 350
	Sand broken good grass Soil on East $\frac{1}{2}$ 2 nd note, West $\frac{1}{2}$ Stony, September 26 th 1866	

X

	North between sections 2, 3 & 24.	
40.00	Set post corner for $\frac{1}{4}$ section on steep hillside, in edge of timber from which A Larch 18 in dia - bears 8,5° W, 18 links do - do - 20 do - do - do - N, 10° E, 15 do -	375
41.00	Dry Creek very little water course N, W,	15
80.00	Set post corner for sections 13, 14, 23 & 24. on steep hillside facing the west, drove churced stake and raised Stone Mound as per instructions, Sand broken, Soil Stony,	+ 300

X

Township 4 North Range 36 East, Will. Mer.

East on random between sections

13 & 24,

Bar 24 East,

40.00
40.11 Set temporary 1/4 section post corner

80.09 Intersected North and South line
38 links South of post corner,

S 89° 44' W on true line

40.04
40.14 Set post corner for 1/4 section from which

A Fir 18 in dia - bears N 15° E, 7 links -

do - Arch 6 do - do - do - S 88° E 8 do -

80.09
80.09 To post corner,

Land broken, good grass,

Soil 2^d rate,

North between sections 13 & 14.

39.00 Bottom of Navin's Course West 300

40.00 Set post corner for 1/4 section
from which

A Fir 18 in dia - bears N 43° E 38 links

do - do - 12 do - do - do - S 5° W 32 do -

71.30 Road Course West 400

7
507
Township 40 North Range 36 East T11 Mer

80.00 Set post corner for sections
11. 12. 13 & 14, drove charred stake
and raised Stone Mound as
per instructions,

x Land broken and
Stony, good grass,

East on random between
sections 12. & 13.

Bar 21° East,

40.00 Set temporary $\frac{1}{4}$ section corner,

80.20 Intersected N & S line 49 links
South of post corner.

S 89° 39' W on true line.

40.10 Set Bassalt Stone 5 x 9 x 14, corner
for $\frac{1}{4}$ section,

80.20 To post corner,

Land rolling & stony,

x good grass,

North between sections
11 & 12,

Township 4 North Range 36 East Will Mer

- | | | |
|----------------|--|-----|
| 40.00
40.00 | Set post corner for 4 section on hillside facing the west, drove charred stake, and raised stone mound as per instructions | 100 |
| 80.00 | Set post corner for sections 1, 2, 11 & 12
Drove charred stake, and raised stone mound as per instructions,
Land broken, good grass,
Soil 2 nd Rate, | 50 |

East on random between sections
1 & 12,

Bar 20° East,

- | | | |
|----------------|--|--|
| 40.00
40.00 | Set temporary 4 section corner | |
| 80.26 | Intersected N & S line 57 links south of post corner,
S 89° 36' W on true line, | |
| 40.13 | Set Bassalt Stone 7x6x16. for 1/4 section corner, | |
| 80.26 | To post corner,
Land very broken, good grass, | |

X

9 ⁵⁰⁹
Township 4 North, Range 36 East, Will. Mer.

North between sections 1 & 2,

37.25 Creek channel dry course West 500

40.00 Mound Stone corner for $\frac{1}{4}$ section 750

on steep hill side, facing the South, Set Basalt Stone

6 x 12 x 18,

68.44 Intersected 1st Standard North 400

12.87 West of Standard corner for sections 35 & 36, T. 5 N, R. 36 E.

Set Closing corner above channel stake, and raised Stone Mound as per instructions,

Land very broken
good grass, soil stony,
X September 27th 1866

North between sections 34 & 35,

40.00 Set post corner for $\frac{1}{4}$ section from which

A Pine 36 in. dia - bears S. 60° W, 26 links

do - do - 10 do - do - do - N. 62° E, 18 do -

55.00 Pine Creek channel dry course W 250

510

Township 4 North, Range 36 East, Williston

80.00 Set post corner for Sections 26 & 27.

34 & 35 from which

A Pine 24 in dia bears S. 25° E, 97 links

do - do - 30 do - do - do - S. 45° W - 47 do -

do - do - 20 do - do - do - N. 30° W, 89 do -

do - do - 24 do - do - do - N. 40° E, 79 do.

Land on south side of Pine Creek
heavily timbered, Pine Larch and
Fir, on North side open good
X grass, Soil Stony,

East on Prunella between
Sections 26 & 35

Bar 20° 30' East,

40.00 Set temporary 1/4 section corner

80.25 Intersected North and South line

15 links North of Post corner

N 89° 54' West on true line

40.12 Set post corner for 1/4 section

from which a Pine

24 in dia bears S. 45° W, 45 lbs

X

11/9 511
Township North Range 36 East, Will, Mer-

A Pine 28 in-dia-bears $N, 50^{\circ} W, 51$ lbs.

8025 To post corner,

Land gently rolling,

open Pine timber good grass

Soil 2^d rate,

X

North between sections 26 & 27,

4000 Set $\frac{1}{4}$ section corner post,

from which

A Pine 20 in-dia-bears, $S 40^{\circ} E, 112$ lbs

do - do - 36 do - do - do - $N, 23^{\circ} W, 49$ do -

A Steam Saw Mill bears

$S 35^{\circ} E$ about 8,00

a dwelling house $S 75^{\circ} E$ about

4,00.

8000 Set post corner for sections 22,

23, 26 & 27. from which

A Pine 18 in-dia-bears - $S, 50^{\circ} W, 58$ lbs

do - do - 20 do - do - do - $S, 70^{\circ} E, 59$ do -

do - do - 24 do - do - do - $N 58^{\circ} E 28$ do -

do - do - 20 do - do - do - $N, 27^{\circ} W, 93$ do -

This line passes through

5192

Township 4 North, Range 36 East, Will. Mer.

x open pine timber, well adapted
to lumbering good grass soil 2^d rate,

East on random between
Sections 23 & 26.

Bar 20° East

40.00 Set temporary $\frac{1}{4}$ section corner

80.70 Intersected N & S line 38 links
North of post corner,

N 89° 44' W on true line,

40.35 Set post corner for $\frac{1}{4}$ section in

various course North, from which,
A Fir 10 in - dia bears N 61° W, 50 links
do - do - 5 do - do - do - S. 47° E, 18 do,

120

80.00 To post corner,

Land broken, good
grass soil 2^d rate, Timber
x open pine,

North between sections 22 & 23.

40.00 Set post corner for $\frac{1}{4}$ section

13/513

Township 4 North, Range 36 East, Will, Mer,

from which
A pine 20 in dia - bears South 362,
no other tree, dug pit
and raised mound as per
instructions.

80.00 Set post corner for sections 14, 15,
22 & 23. Above charred stake,
and raised stone mound as
per instructions.

X Land gently rolling
good grass Soil 2^d Rate,

East on random between
sections 14 & 23.

Bar 19° East,

40.00 Set temporary $\frac{1}{4}$ section corner

80.64 Anticipated N & S line

40.00 51 links North of post corner,
N 89° 44' W on true line,

28.25 Bottom of Ravine course North 350

40.32 Set post corner for $\frac{1}{4}$ section 200
above charred stake dug

14
514
Township 4 North, Range 36 East - Will - Mer -

and raised Stone Mound as per instructions

47, 00 Summit of ridge + 150

62, 50 Bottom of ravine, course North 350

80, 64 To post corner,
Land broken, good grass,
Sail Stony,

x

North between sections 14 & 15,

40, 00 Set Basalt stone 9 x 11 x 12. for 375

1/4 section corner, on steep
hill side facing the north,

42, 00 Dry Creek 5-6 mile course West 15-

80, 00 Set post corner for sections
10, 11, 14 & 15, drove charred stake
and raised mound as per instructions

x

Land broken & Rocky,

October 3rd 1866.

Cast on random between
sections 14 & 20.

Township 4 North, Range 36 East Will. Nev,

Bar 19° East,

40.00 Set temporary 1/4 section corner,

80.61 Intersected N & S line 72 links north
of post corner,

N 89° 29' W on true line

40.30 Set Bassalt Stone 9x10x15 for
1/4 section corner

76.00 Road course N, W,

25

80.61 To post corner,

Land gently descending

X good grass, soil 2^d rate,

North between sections 10 & 11.

2.50 Road course N, W,

40.00 Set Bassalt Stone 4x12x16, for

X

1/4 section corner, on hillside
facing the west,

80.00 Set post corner of sections 2, 3,

10 & 11. Drove charred stakes, dug
pits and raised mound as per
instructions,

X

Land broken, good grass

Township 4 North, Range 36 East, Will, Mer.

16
516

X Soil 2^d rate,

East on random between sections 2 & 11
Bar 20° East

40.00 Set temporary $\frac{1}{4}$ section corner

80.66 Intersected North and South line

49 North of post corner,

N 89° 39' W on true line

35.00 Bottom of ravine course North

500

40.33 Made ^{Corner on} Bassalt Boulder 36 x 42. and

as deep as may be, on steep hillside ⁴⁰
facing the East,

80.66 To post corner,

Land broken, good grass,

X Soil 2^d rate,

North between sections 2 & 3.

20.75 Creek 5 links wide course West

500

40.00 Set Bassalt Stone 7 x 9 x 14 corner
for $\frac{1}{4}$ section.

750

68.50 Intersected 1st Standard

740

Parallel North 1273 West

1719 517

Township 4 North, Range 36 East, Will. Mer,

of corner for sections 33 & 35

T5 NR 36 East

Set post Closing corner
for sections 2 & 3, drove churried
stake, and raised mound of stones
as per instructions,

Land broken, good grass,

Soil 2^d rate,

X October 4th 1866.

North between sections 33 & 34,

375.0 Pine Creek channel dry course W, 275 275

40.0 Set post corner for 1/4 section 7 15

Drove churried stake, raised Muck
stone mound as per instructions

80.00 Set post corner for sections 27. 28.

33 & 34, from which

A Pine 30 in-dia bears- S 37° E 119 links

do- do- 36 do- do- do- N 1° E 106 do-

do- do- 24 do- do- do- N 85° W 144 do-

no tree near in section

35, Land broken,

Township 4 North Range 36 East, Will, Mer,

thick timber on South side of
Pine Creek, Pine Larch & Fir
on North side open Pine timber
good grass, Soil 2^d rate,

X

Cast on random between sections
27 & 34.

411 Bar 2030 East,

40.00 Set temporary $\frac{1}{4}$ section corner,

79.81 Intersected N & S line 39 links
North of Post corner,

N 89° 43' W on true line,

39.90 Set post corner for $\frac{1}{4}$ section
from which

a Pine 40 in-dia-bears N 15° W, 36 lbs

do - do - 30 do - do - do - S, 80° W, 158 do -

79.81 To post corner

Land gently rolling, good
grass, open Pine timber,

X

Township 4 North, Range 36 East, Will, Mex

North between sections 27 & 28,

3950 Road to Steam Mill course East

4000 Set post corner for $\frac{1}{4}$ section
from which

A Pine 36 in-dia - bears $N, 10^{\circ} W, 275$ lbs

do - do - 36 do - do - do - $S, 30^{\circ} E, 232$ do,

8000 Set post corner for sections 21. 22.

27 & 28 from which

A Pine 36 in-dia - bears $S, 20^{\circ} E, 60$ lbs

do - do - 30 do - do - do - $S, 6.8^{\circ} W, 139$ do,

do - do - 24 do - do - do - $N, 30^{\circ} W, 129$ do,

do - do - 4 do - do - do - $N, 55^{\circ} E, 17$ do -

Land gently rolling, good
grass, Limber Pine well
suited making lumber

X

East on rancho between
sections 22 & 27,

Bar $20^{\circ} 30'$ East,

4000 Set temporary $\frac{1}{4}$ section corner

7958 Intersected N & S line 43 links

North of Post Corner

X

Township 4 North, Range 36 East, Will, Mer,

20
570

N 89° 42' W on true line

3979 Set post corner for 4 sections

75

Above charred stake, and raised
stone mound as per instructions.

4450 Bottom of rubbers course North

70

7958 To post corner,

140

Land broken, good grass,

Timber open Pine,

Soil 2^d rate,

North between sections 21 & 22,

4000 Set post corner for 4 section

above charred stake, dug
pit and raised mound as
per instructions.

8000 Set post corner for sections 15. 16.

21 & 22, from which

A Pine 20 in - dia bears North 136 links

do - do - 20 do - do - do - S 85° W, 310 do -

do Birch 18 do - do - do - N 80° W 236 do -

no tree near in sec, 22,

Land broken Soil 2^d rate -

X

21 2524

Township 4 North, Range 36 East, Will. Mer.

East on random between sections

15 & 22,

Bear 20° East

40.00 Set temporary $\frac{1}{4}$ section corner

79.65 Intersected N 4 S line 40 links

North of Post corner,

N 89° 43' W on true line,

39.82 Set post corner for $\frac{1}{4}$ section

above charred stake, depth raised

Stone mound as per instructions,

61.00 Bottom of ravine course N 250

250

79.65 To post corner

+ 250

+ 250

Land broken, good grass,

Soil 2nd rate,

X

North between sections 15 & 16.

10.00 Bottom of ravine course N, E,

200

40.00 Set Bassalt Stone 5 X 11 X 15. corner for

+ 300

$\frac{1}{4}$ section on point of ridge

course N E,

66.50 Dry creek channel dry course West,

350

80.00 Set post corner for sections

+ 400

Township 4 North, Range 36 East, Will. Mer,

9. 10. 15 & 16. Above charred stake, and raised Stone mound as per instructions,

Land broken, good grass

x Soil stony,

East on random between sections 10 & 15

Bear 15° 30' East

4000 Set temporary 1/4 section corner,

7971 Intersected North and South line 57 links North of post corner,

N 89° 36' W on true line,

3980 Set Basalt Stone 8 x 10 x 15 corner

for 1/4 section, on hillside facing the South,

7971 To post corner,

Land broken, good grass Soil rocky,

October 5th / 1866

+

North between sections 9 & 10,

23/9 543

Township 4 North, Range 36 East, Will. Mer,

15.00 Road course E & W.

40.00 Set Basalt Stone 9x10x12. for
¼ section corner.

80.00 Set post corner for sections
3.4. 9 & 10. Above charred stake,
dig pit and raised.

Mound as per instructions,
Lund broken, good
grass soil 2½ rate,

X

Cast on random between sections

3 & 10

Per 20.30' Cast,

40.00 Make temporary ¼ section corner,

79.87 Intersect N & S line 63 links
North of post corner

N 89° 33' W on true line

36.00 Bottom of curve course North 500

39.83 Set post corner for ¼ section
on side hill facing the N.E. 350

Above charred stake, dig pit
and raised mound as per instructions

Township 4 North, Range 36 East, Will, Mer,

60.00	Summit of ridge course North	300
77.50	Bottom of drain course North	340
79.67	To post corner	30

Land very broken

X good grass Soil 2^d rate

North between sections 3 & 4.

15.75	Crack 5 links with course West.	50
-------	---------------------------------	----

40.00	Set Bassalt Stone 6 x 12 x 14. for $\frac{1}{4}$ section corner	300
-------	---	-----

68.23 Intersected the 1st Standard Parallel North 12 30 West of post corner for sections 33 & 34 T. 5 N. R. 36 East, Set post Closing corner for sections 3 & 4. Above churruet stake dry pits and raised mound as per instructions.

Land broken good grass Soil 2^d rate

X October 5th 1866.

257 525

Township 4 North, Range 31 East, T11, Mer,

North between sections 32 & 33

2250 Pine Creek channel dry corner ²⁰⁰ W 200

40.00 Set post corner for 1/4 section ²⁰⁰

Above channel stake, and raised Stone mound as per instructions.

80.00 Set post corner for sections

28, 29, 32 & 33, in prairie, above channel stake, dug pit and raised mound as per instructions

Land broken good grass

+ Quit 2 1/2 rate,

⁵⁰ Cast on ranch between sections 28 & 33

Bear 20° 30' East,

40.00 Set temporary 1/4 sections corner

80.15 Intersected N & S Line 41 links

South of post corner,

S 89° 42' W on true line

40.07 Set post corner for 1/4 section, from which

A Fir 10 in dia - bears S. 20° W. 46 links

526²⁶

Township 4 North, Range 36 East, Will. Mer.

75,000 A Pine 20 in dia - bears N. 33° W, 41 links
Cross corner of ploughed land to the
South,

80,15 To post corner,

Land broken, good grass,
Soil 2^d rate,

North between sections 28 & 29

40,000 Set post corner for $\frac{1}{4}$ section from which

A Pine 36 in dia - bears S 80° W, 90 links

do - do - 7 do - do - do - S, 70° E, 94 do

30,000 Set post corner, for sections 20, 21,

28 & 29, from which

A Pine 12 in dia bears S 5° W 36 links

do - do - 15 do - do - do - S, 30° E, 63 do

no trees near in sections 20 & 21

dry pits and raised mound
as per instructions,

Land rolling, good grass,
Soil 2^d rate,

x

27

527

Township 4 North, Range 36 East Will. Mer,

East on random between
Sections 21 & 28 Var. 21° East

40.00 Set temporary $\frac{1}{4}$ section corner

80.37 Intersected N & S line 5-6 link

South of post corner

S 89° 36' W on true line,

40.18 Set post corner for $\frac{1}{4}$ section

from which -

A Pine 12 in-dia-bears N 40° E, 155 links

do - do - 20 do - do - do - S, 8° W, 125 do -

75.50 Road to Steam Saw Mill course N, W,

80.37 To post corner,

Land polling, good grass,

Soil 2 $\frac{1}{2}$ Kate,

North between sections 20 & 21.

40.00 Set post corner for $\frac{1}{4}$ section, in prairie,

drove charred stake, dug pits
and raised mound as per instructions

80.00 Set post corner for sections 16, 17, 20 & 21

drove charred stake, dug pits
and raised mound as per

528

Township 4 North Range 36 East Will, Mex,
instructions.

Land broken, good grass.
Soil 2nd rate,

X

Cast on random between sections 16 & 21.
Bar 18° East

- 40.00 ^{40.09} Set temporary $\frac{1}{4}$ section corner,
- 80.29 Intersected N & S line 88 links South
of post corner,
S 89° 22' W on true line
- 15.70 Bottom of Marine course North, 175
- 40.14 Set post corner for $\frac{1}{4}$ section drove 300
churned stake dug pits and raised
Stone mound as per instructions,
- 80.29 To post corner,

Land broken, good grass,
Soil 2nd rate,

X

North between sections 16 & 17.

- 40.00 Set Basalt Stone 8 x 10 x 14. for $\frac{1}{4}$ section
corner,
- 55.00 Dry creek 4 links wide course N.W. 250
- 80.00 Set post corner for sections 8. 9. 16 & 17.

Township 4 North, Range 36 East, Will, Mo.,

on hillside facing the S. W.

300

Drove charred stake, dug pits and
raised mound as per instructions.

Land broken, good grass,

X Soil 2^d rate,

East on random between sections

9 & 16

Road 21° East

40.00 Set temporary 4 section corner,

80.42 Intersected N & S line 53 links
North of post corner

N 82° 37' W on true line,

40.21 Set Basalt Stone 6 x 10 x 15. for 4 section
on hill side facing the South,

80.42 To post corner

Land rolling, good
grass, Soil 2^d rate,

October 6th 1866

X

North between sections 8 & 9,

14.00 Road course West,

+
75

Township 4 North Range 36 East Will. Mer,

40.00 Set Bassalt Stone corner for
1/4 section 7 x 9 x 15.

200

80.00 Set post corner for sections 4, 5, 8 & 9
on hillside facing the North
drove charred stake, dug pits
and raised mounds as per
instructions.

+ Land broken good
grass, Soil 2^d rate.

Cast on random between
Sections 4 & 9.

Per 1930' East

40.00 Set temporary 1/4 section corner

80.33 Intersected N & South line
30 links South of Post
corner

S. 89° 47' W on true line

40.10 Set Bassalt stone 7 x 12 x 14
corner for 1/4 section

75

80.33 To post corner,
Land broken,

Township 4 North, Range 36 East, Will. Mer,
 good grass soil 2^d rate,

North between sections 4 & 5,

1.50 Creek 5 links wide course West 50

40.00 Set Basalt Stone 6x9x15 +
 200

for $\frac{1}{4}$ section corner,

6.9.10 Intersected 1st Standard Parallel

North 12.43 West of post corner

for sections 32 & 33,

Set post Closing corner for

sections 4 & 5 drove churred

stake dug pits and raised

ground as per instructions.

Land broken

good grass, Soil 2^d rate,

October 7th 1866,

X

North between sections 31 & 32,

17.00 Pine Creek course West 300

40.00 Set Basalt stone 5x9x15 corner +
 300

for $\frac{1}{4}$ section,

80.00 Set post corner for sections

532

Township 4 North, Range 36 East, Will, Mo.

29, 30, 31 & 32 in Prairie, drove charred stake, dug pit, and raised mound as per instructions
Land broken, good grass
Soil 2nd rate,

X

East on random between sections 29 & 32.

Bear 20° 30' East,

41,111 Set temporary $\frac{1}{4}$ section corner

79,58 Intersected N & South line at post corner

West on true line,

39,79 Set post corner for $\frac{1}{4}$ section drove charred stake, and raised mound as per instructions,

79,58 To post corner,

Land broken, good grass

X

Soil 2nd rate,

West on random between sections

X

30 & 31,

Township 4 North, Range 36 East, Will. Mer,

40.00 Set temporary $\frac{1}{4}$ section corner
 67.05 Intersected N & S line 58 links

South of post corner

$S 89^{\circ} 35'$ East on true line,

37.05 Set post corner for $\frac{1}{4}$ section
 from which,

A Pine 6 in dia bears $N, 50^{\circ} E, 26$ links

do - do - 8 do - do - do - $S, 70^{\circ} W, 18$ do -

77.05 To post corner.

Land broken, good grass,

X Soil 2nd Rate,

North between sections 28 & 30

40.00 Set post corner for $\frac{1}{4}$ section, from which

A Pine 20 in dia bears $S, 65^{\circ} E, 81$ links

do - do - 24 do - do - do - $S, 63^{\circ} W, 116$ do -

80.00 Set post corner sections 19, 20, 28 &

30 from which

A Sarch 30 in dia bears $N, 65^{\circ} E, 205$ links

do - do - 20 do - do - do - $S, 45^{\circ} E, 225$ do -

no other tree near by pits

and raised mound as per

34
534

Township 4 North, Range 36 East Will, Mer,

instructions.

Land broken good grass

Soil 2^d rate,

x

East on random between

sections 20 & 29.

Bar 21° East

4000 Set temporary $\frac{1}{4}$ section corner

7981 Intersected N & South line 32 links

South of post corner

S 89° 46' W on true line

3990 Set Basalt Stone 5 x 10 x 15, for
 $\frac{1}{4}$ section corner,

6150 Bottom of ravine course N W,

150

7981 To post corner,

+
140

land broken, good

grass, Soil 2^d rate,

x

West on random between

sections 19 & 30

4000 Set temporary $\frac{1}{4}$ sec
 $\frac{1}{4}$ corner

7741 Intersected N & S line 63 links

Township 4 North, Range 36 East, Will, Minn,
 South of post corner,

S 89° 33' East on true line,

37.01 Set post corner for $\frac{1}{4}$ section from which
 A Pine 24 in-dia bears S, 11° W, 67 links
 do - do - 20 do - do - do - S, 23°, W, 130 do,

54.50 Summit of ridge + 300

77.01 To post corner 140

Land broken, good grass

X Soil 2^d rate,

North between sections

19 & 20

15.00 Bottom of ravine course N, W, 150

40.00 Set Bassalt Stone 6 x 10 x 14
 corner for $\frac{1}{4}$ section corner 160

80.00 Set post corner, for sections
 17, 18, 19 & 20, deposited Marked
 Stone and raised Stone Mound
 as per instructions,

Land broken, good grass,

Soil 2^d rate,

October 8th 1866

X

Township 4 North, Range 36 East, Will. Mer.

East on random between sections
17 & 20.

Bur 21° East

40.00	Set temporary $\frac{1}{4}$ section corner	
79.91	Intersected N & S line 70 links South of corner S 89° 30' W on true line.	
39.95	Set Basalt stone 9 x 10 x 12. for $\frac{1}{4}$ section corner,	100
46.00	Bottom of ravine course N, W,	200
79.00		+
71.00	Summit of ridge course N	300
79.91	To post corner,	150
	Land broken good grass Soil poor 2 $\frac{1}{2}$ rate,	

West on random between
sections 18 & 19

40.00	Set temporary $\frac{1}{4}$ section corner	
76.81	Intersected N & S line 49 links south of post corner S 89° 31' East on true line	
36.81	Set post corner for $\frac{1}{4}$ section corner	

37 L 537

Township 4 North, Range 36 East, Will, Mer,

deposited marked stone, and
raised stone mound as per
instructions.

76,81 To post corner,

Land broken good grass

X Soil 2^d Rate.

North between sections 17 & 18,

40,00 Set post corner for $\frac{1}{4}$ section

in ravine course North,

deposited marked stone, and
raised stone mound as per
instructions.

80,00 Set post corner for sections

7 X 8 X 17 X 18, deposited marked

stone and raised stone mound

as per instructions.

Land broken good

grass, hill sides rocky

X no timber.

East in ranchone between

Township 40 North, Range 36 East, Will, Mer,
sections 8 & 17.

Bar 21° East

4000 Set temporary $\frac{1}{4}$ section corner

7987 Intersected N & S line

41 links South of post

Corner,

S 89° 42' W on true line

^{39.93} 3993 Set post corner for $\frac{1}{4}$ section 315-

on right bank of Dry Creek

from which

A Palm 10 in dia bears S 78° E, 9 links

do - Alder 6 do - do - do - S, 5° W, 22 do,

^{40.75} 4075 Dry Creek 5 links wide course N, W,

7987 To post corner,

Land very broken, good

X grass soil good 3 $\frac{1}{2}$ rate,

West on random between

sections 7 & 18.

4000 Set temporary $\frac{1}{4}$ section corner

7688 Intersected N & S line 79

links South of Post corner.

39 539

Township 4 North Range 36 East Will Mer

S89° 26' East on true line,

3678 Set Basalt Stone corner for

1/4 section Stone 8x11x15.

7400 Bottom of main course N 250 250

7678 Go post corner,

Land broken good

X grass, Soil 2 1/2 rate,

North between sections 748,

1500 Dry Creek 10 links wide course West 150

4000 Set ~~Basalt~~^{Stone} corner for 1/4 section 300

8x10x14

5300 Road course West,

8000 Set post corner for sections

5, 6, 748, drove churred

Stake, dug pits and raised

Mound as per instructions

Land broken good

grass, Soil 2 1/2 rate,

X

East on random between

Sections 548

54040

Township 4 North Range 36 East Will, Mex,

Bar 19°30' East,

- 40.00
40.00 Set temporary $\frac{1}{4}$ section corner
8008 Intersected North & S line
5'4 links South of Post corner
S89°37' W on true line
- 40.04 Set post corner for $\frac{1}{4}$ section
above charred stakes, dug pits
and raised mound as per
instructions.
- 80.08 To post corner,
Land broken, good
X grass, Soil 2^d rate,

West on random between
sections 647.

- 40.00 Set temporary $\frac{1}{4}$ section corner
76.80 Intersected N & S line 86 links
South of Post corner,
S89°23' on true line
- 76.80 Road course NW
- 36.80 Set post corner for $\frac{1}{4}$ section
corner, drove charred,

414 541
Township 4 North, Range 36 East, Will. Mer,

Stake, clay pits and raised
mound as per instructions

76.80 To post corner,

Land broken, good
grass Soil 2 $\frac{1}{2}$ rate,
X

North between sections
5 & 6.

26.00 Enter field course of fence 70
N. W.

40.00 Set post corner for $\frac{1}{4}$ section ²⁰ 70
drove charred stake dug pits
and raised mound as
per instructions,

57.75 Creek 6 links wide course West 60

64.00 Leave field.

68.41 Intersected 1st Standard 30

Parallel 1271 links West
of post corner for sections
31 & 32 T5 N Range 36 East,
Set closing corner for
sections 5 & 6. Deposited

Y
 Township 4 North, Range, 36 East, Will, Mer.

marked Stone and Mark
 Stone Monnet as per
 instructions.

Land broken good
 grass. Soil good
 L. & W. note,

X

These are some six or seven
 settlers in this Township holding
 Claims under the preemption
 law and a considerable
 portion of the Township
 will be entered whenever
 there is an opportunity given
 to the Farmers in Walla Walla
 Valley for the timber;
 which is very palatable,
 October 10th 1866.

543

Names of the persons employed

to assist in running
measuring or marking the
lines in corners of the
Subdivisions of Township
No. 4 North of Range 36 East
of Willamette Meridian
Showing the respective
capacities in which
they acted.

John A. Bigg } Chairman
Charles D. Harchitz }
Samuel C. Harchitz Assessor

I hereby certify that I assisted
 William H. Odell, Deputy Surveyor
 in surveying the exterior boundary
 and subdividing Township
 number four (4) North of Base
 Line of Range thirty seven (37)
 East of Willamette Meridian,
 and that said Township
 has been in all respects to the
 best of my knowledge and
 belief well and faithfully
 surveyed and the boundary
 monuments planted accord-
 -ing to the instructions
 furnished by the Surveyor General
 of A. Trigg Chairman

State of Oregon }
 County of Umatilla } SS Subscribed
 and sworn to before me this
 25th day of October 1866.

William Senallen Justice of the Peace

We hereby certify that we assisted
 William H. Odell Deputy Surveyor
 in surveying the exterior boundaries
 and subdividing Township number
 four North of the Base Line of Range
 No, thirty six East of Willamette
 meridian, and that said
 Township has been in all respects
 to the best of our knowledge
 and belief, well and faithfully
 surveyed and the boundary
 monuments planted according
 to the instructions furnished
 by the Surveyor General.

C. D. Hardisty Chairman

J. C. Hardisty Assessor

State of Oregon

Umatilla County ss. Subscribed and

sworn to before me this

22 day of November 1866.

+ William S. Allen J. P.

I William H. Odell, Deputy surveyor,

do solemnly swear that, in pursuance of a contract with C. F. Applegate surveyor of the public lands of the United States in the State of Oregon, bearing date July 2nd 1866, and in strict conformity to the laws of the United States and of the instructions furnished by said Surveyor General, I have faithfully surveyed the subdivisions of Township No 4 North of the Base Line of Range 36 East of the Willamette Meridian, in the State aforesaid, and I do further solemnly swear that the foregoing are the true and original field notes of such survey

William H. Odell

State of Oregon }
County of Lane } ss.

Subscribed and Sworn to before me this 12th day of January 1867,

Joel Ware
Notary Public

Surveyor General's Office
 Eugene City Jan 17, 1869

The foregoing field notes of
 the survey of the subdivisions
 of Town 4 N R 3 E & W 1/2
 nor are executed by Wm
 McCall dep Sur under
 contract No 114 dated
 July 2nd 1866. Having
 been critically examined
 the necessary explanations
 and corrections made the
 said field notes and the
 surveys they describe are
 hereby approved

E. L. Appleton
 Sur Genl of Ore