

561

# Index

Township 4 North Range 37 East Will, Mer.

	14		
18	13	17	
	13		
19	12	20	
	11	10	
30	10	29	7
9		8	
31	7	32	6
3		4	

I Charles Sanders do solemnly swear that I will faithfully perform the duties of chainman that I will level the chain over uneven ground and plumb the tally pins whether sticking or dropping the same, and that I will report the true distance to all notable objects and the true length of all lines that I assist in measuring according to the best of my skill and ability

Charles Sanders

Territory of Washington }  
 County of Walla Walla } ss. Subscribed  
 and sworn to before me  
 this 3<sup>rd</sup> day of October 1866

B. A. Seaton

Clerk of the U. S. District  
 Court - 1st Judicial District  
 Washington Territory

I C. A. Neal do solemnly  
 swear that I will well and  
 faithfully perform the duties of  
 Assessor in conformity to the  
 instructions furnished me  
 according to the best of my  
 skill and ability.

C. A. Neal

Washington Territory }  
 County of Walla Walla } ss

Subscribed and sworn

to before me this 9<sup>th</sup> day  
 of October 1866,

B. A. Saylor,  
 Clerk of the U. S. District  
 Court, First Judicial District  
 Washington Territory

Field Notes of Part  
 of the Exterior lines of  
 Township No 4 North of Range  
 37 East of Willamette Meridian,  
 Commencing at the South  
 East Corner of Township No 4 North  
 of Range 36 East of Willamette Meridian  
 Thence

East on South boundary of section 31

40.00  
 4000

Set post corner for  $\frac{1}{4}$  section, from which  
 A Larch 12 in-dia-bears N $33^{\circ}$ E, 12 links

80.00  
 8000

do- do- 8 do- do- do- S $5^{\circ}$ W, 32 do-

Set post corner sections 31, 32, 5 & 6,  
 from which

A Fir 8 in-dia-bears S $6^{\circ}$ E 18 links

do, do, 6 do, do, do, N $45^{\circ}$ E, 11 do-

do- do- 20 do, do- do- S $40^{\circ}$ W 40 do-

do- do- 7 do- do- do- N $54^{\circ}$ W 32 do-

This line passes through  
 thick timber Fir Larch & Pine  
 Undergrowth the same

4 2564

Township 8 North Range 37 East Will Mex

East between sections 32 & 5,

Bar 21° East,

40.00 Set post corner for 4 section from which

A Pine 8 in-dia. bears N. 12° W, 22 links

• do Fir 6 do- do- do S, 15° W, 27 do

80.00 Set post corner for sections 4. 5. 32 & 33

from which

A Fir 20 in-dia. bears S. 55° W, 19 links

do- do- 15 do- do- do- S, 40° E, 59 do

do- do- 20 do- do- do- N, 60° E, 40 do

do- do- 18 do- do- do- N, 3° W, 9 do

Land gently rolling covered  
with thick timber generally of small  
growth, Fir Spruce and Pine  
undergrowth the same,

The southern boundary of  
this Township should be surveyed  
and the south West half of the  
Township should be subdivided  
because of the valuable timber  
The North East half is cut up by

a deep canyon very steep and difficult  
to cross,

The lateness of the season prevented  
my further prosecuting the journey  
October 11<sup>th</sup> 1866.

X



6 568

Field Notes of a part of the subdivision  
lines of Township 4 North of the  
Base line of Range 37 East of  
Willamette Meridian,

Commencing at the  
South East corner of section 32,  
North between sections 32 & 33,

Bar  $19^{\circ}30'$  East,

40.00 Set post corner for 1/4 section from which  
A Pine 12 in dia bears  $N84^{\circ}W$  18 links  
do. Fir 10 dia- do- do-  $N81^{\circ}E$  26 do,

80.00 Set post corner for sections 28, 29, 32 & 33  
from which

A Fir 8 in-dia-bears  $S68^{\circ}W$ , 27 links  
do, do- 8 do- do- do-  $S75^{\circ}E$  21 do-  
do- do- 20 do- do- do-  $N30^{\circ}W$ , 52 do-  
do- do- 8 do- do- do-  $N20^{\circ}E$ , 56 do-

Land gently rolling,  
excellent timber small  
growth, Fir, Larch & Pine,  
Rancho growth the same,

Township 4 North Range 37 East of Will-Mer-

North between sections 28 & 29  
Bar 20 East.

3.75  
 3.75 Spring branch 2 links wide course West  
 40.00  
 40.00 Set post corner for 1/4 section from which  
 A Fir 12 in dia bears N. 15° W, 10 links  
 do, do- 14 do- do- do- S, 20° E, 17. do-  
 40.00  
 80.00 Set post corner for sections 20, 21  
 28 & 29, from which  
 A Fir 12 in dia bear N, 36° E, 70 links  
 do- do- 15 do- do- do- N, 47° W, 30 do-  
 do- Larch 20 do- do- do- S 35° W, 25 do-  
 do- Fir 10 do- do- do- S 61° E 40 do-  
 Land gently rolling good  
 Timber Fir Larch & Pine  
 Small growth very thick  
 October 12<sup>th</sup> 1866.

North between sections 31 & 32,

23.75  
 23.75 Pine Creek channel dry course West 30  
 40.00  
 40.00 Set post corner for 1/4 section,  
 from which -



568

Township 4 North, Range 37 East, Williston

A Larch 20 in dia - bears  $N 32^{\circ} W$ , 52 links

do - do - 6 do - do - do -  $S 80^{\circ} E$ , 10 do

8000 Stake post corner for sections 29,

30, 31 & 32 from Larch tree 18

in - dia from which

A Fir 20 in dia bears  $N 80^{\circ} E$  40 links

do - do - 24 do - do - do -  $S 45^{\circ} E$ , 16 do

do - do - 6 do - do - do -  $S 73^{\circ} W$ , 40 do

do - do - 10 do - do - do -  $N 50^{\circ} W$ , 33 do

Land gently rolling

excellent timber - Fir, Larch

& Pine, much growth the same

x with few and Willow.

East on random between  
sections 29 & 32

Bar  $20^{\circ}$  East

40.00 Set temporary  $\frac{1}{4}$  section corner

79.91 Intersected N & S line 54 links  
North of post corner,

$N 89^{\circ} 37' W$  on true line

39.95 Set post corner for  $\frac{1}{4}$  section

Township 4 North, Range 37 East, Will. Mer,

from which

A Larch 20 in dia - bears N 20° W 22 links

do do - 18 do do do - S, 25° E, 30 do -

79.91 To post corner

79.91

Land gently rolling  
excellent timber - small  
growth, Fir Larch & Pine,  
Undergrowth the same

West on random between sections

30 & 31.

40.00

Set temporary 1/4 section corner

80.16

Intersect N & S line 30 links  
North of Post corner

North, 85° 47' E on true line

40.16

Set post corner for 1/4 section from which

A Fir 10 in, dia - bears N 6° E - 22 links

do do - 12 do do do - S, 32 W, 15 do -

80.16 To post corner,

80.16

Land gently rolling  
excellent timber, Fir, Larch  
and Pine,

10  
570

Township 4 North Range 37 East, Will, Mer,

North between sections 29 & 30

4000 Stake corner for 1/4 section on a White  
Fir 12 in - dia - from which  
a Fir 8 in - dia - bears N, 5° W, 16 links  
a Larch 7 do - do - do - S, 30° E, 6 do,

8000 Set post corner for sections 19, 20  
29 & 30. From which

a Pine 18 in dia bears S 54° W 166 links  
do do - 36 do do - do - N, 87° W, 136 do  
do - do - 42 do - do - do - N, 40° E, 52 do.  
do - do - 36 do - do - do - S, 60° E, 116 do -

Land gently rolling,

Well timbered Fir Larch  
& Pine,

X

East on range line between  
sections 20 & 29

Bar 19° East

4000 Set temporary post corner,  
7983 Intersected N & S line 67 links  
North of post corner,

X N 89° 31' W on true line,

Township 4 North Range 37 East Will Mer -

39.91 Set post corner for 1/4 section from which

<sup>39.91</sup> A Fir 18 in dia bears North 8 links

do - do - 20 do - do - do - S 48° E 11 do -

<sup>79.50</sup> 79.50 Road course North

<sup>79.81</sup> 79.81 To post corner,

Land gently rolling  
excellent timber, Fir Larch &  
Pine, Undergrowth the same

X

West on ranche between sections 19430

<sup>40.00</sup> 40.00 Set temporary 1/4 section corner

<sup>80.24</sup> 80.24 Intersected North and south  
line 31 links North of  
post corner,

N 83° 47' E on true line

<sup>40.24</sup> 40.24 Set post corner for 1/4 section  
from which -

A Pine 18 in dia - bears S 80° W, 310 links

do - do - 15 do - do - do - N 30° E 75 do -

<sup>80.24</sup> 80.24 To post corner,

Land gently rolling  
Timber Pine Larch & Fir,

X

12  
572

Township 4 North, Range 37 East, Will. Mer,

North between sections 19 & 20

75 Road course N, W,

7,00 Same Road course N, E,

4,000 Set post corner for 1/4 section,

from which

A Fir 5-in-dia bears N, 78° W, 13 lbs

do - do - 7. do - do - do - N, 45° E, 8 do -

45,70 Same Road course N, W,

6,000 A cluster of Cubins bears west about -

10,00

8,000 Set post corner for sections

17, 18, 19 & 20 from which

A Pine 18 in-dia - bears S 2° W 120 links

do - do - 20 do - do - do - N 60° E 138 do -

do - do - 24 do - do - do - S, 62° E, 188 do -

do - do - 20 do - do - do - N, 73° W, 150 do -

This line passes through thick  
timber Mostly Larch & Fir some  
pine, Land gently rolling  
Soil 2<sup>nd</sup> rate,

X

Township 4 North, Range 37 East, Will, Mex-

West boundary between sections 18 & 19,

Bear 19° 30' East,

40.00  
40.00 Set temporary  $\frac{1}{4}$  section corner,

80.50  
80.50 Intersect N & S line 42 links North  
of post corner

N 89° 42' E on true line

40.50  
40.50 Set post corner for  $\frac{1}{4}$  section from which

A Pine 24 in. dia. bears N 2° E 19 links

No No- 18 do- do- do- S 15° W 50 do-

63.00  
63.00 Road course North

80.50  
80.50 To post corner,

Land rolling, good grass,

Soil 2<sup>d</sup> rate Limber scattering

Pine very little undergrowth,

X

North between sections 17 & 18,

40.00 Set post corner for  $\frac{1}{4}$  section above 40.00

Charred stake ~~eye pits~~ and raised

Stone mound as per instructions

51.00 Bottom of ravine course N.W. 75-

80.00 Set post corner for sections 7, 8, 17, 18

& 18. Above charred stake ~~eye pits~~ Stone

142 574

Township 4 North, Range 37 East, Will, Mex.  
as per instructions.

+ Land very broken, good  
grass, Soil rocky,

West on random between  
sections, 7 & 18

Far 21' East,

40.00 Set temporary  $\frac{1}{4}$  section corner

80.72 Intersected N & S line 48

links North of post corner,

N 89° 39' East on true line

40.72 Set post corner for  $\frac{1}{4}$  section

Above charred stake, and

raised mound of stones

as per instructions,

70.00 Bottom of Ravine Course NW 500

80.72 To post corner,

Land broken, good

grass Soil 2<sup>d</sup> rate,

October 22<sup>d</sup> / 1866

At least two tiers of sections adjoining on the East in this Township should be subdivided because of the valuable timber but the lateness of the season renders it impracticable to prosecute the surveys farther, —

A list of the names of the persons employed to assist in running, measuring or marking the lines and corners, described in the foregoing field notes of Township 4 North, of Range 37 East of Willamette Meridian, showing the respective capacities in which they acted;

John A. Bigg } Chairmen  
 Charles Saunders }  
 C. O'Neal Axeman.



We hereby certify that we assisted William  
 H. Odell, deputy surveyor in surveying  
 two miles of the exterior boundaries and  
 subdividing to the extent set forth in  
 the foregoing field notes; Township  
 number four North of the Base Line  
 of Range thirty seven East of  
 Willamette Meridian, and that  
 said Township has been in all respects  
 to the best of our knowledge and  
 belief, well and faithfully surveyed  
 and the boundary monuments  
 planted according to the instructions  
 furnished by the Surveyor General,  
 J. A. Pigg Chairman  
 Charles Sanders Chairman

La Vil Heron  
 Territory of Washington }  
 County of Walla Walla } 88 Subscribed  
 and sworn to before me this  
 24<sup>th</sup> day of October 1866.

W. Parker  
 Notary Public



X

I William H. Odell, Deputy  
 Surveyor, do solemnly swear that  
 in pursuance of a contract with  
 O. L. Applegate, surveyor of the public  
 of the United States in the State  
 of Oregon, bearing date July 2<sup>nd</sup> day  
 1866. and in strict conformity to  
 to the laws of the United States and  
 the instructions furnished by said  
 Surveyor General I have faithfully  
 surveyed the exterior boundary  
 and subdivisions of Township No.  
 4 North of the Base line of Range 37 East of  
 Willamette Meridian in the State of  
 Oregon aforesaid, and do further  
 solemnly swear that the foregoing are  
 are the true and original field notes  
 of such survey. William H. Odell

State of Oregon }  
 County of Lane 1867. Subscribed and  
 Sworn to before me this  
 5<sup>th</sup> day of January 1867.  
 Joel Han  
 Notary Public



Surveyor General's Office  
Ogden City, January 11<sup>th</sup> 1867

The foregoing field notes  
of the survey of the Eastern  
Boundary and Subdivisions  
of Township 604 N Range  
37 East T12E mer or W executed  
by Mr A Odell deputy sur  
veyor under contract No 114 dated  
July 2nd, 1866 having  
been critically examined  
the necessary explanations  
and corrections made  
the said field notes and  
the survey they describe  
are hereby approved

E. L. Applegate  
Sur Genl of W

+