

INDEX DIAGRAM

Township 4 South, Range 30 East,

	6	5	4	3	<u>11</u> 2	<u>7</u> 1	
		<u>15</u>					<u>3</u>
	7	<u>14</u> 8	9	10	11	12	
<u>4</u>				<u>12</u>		<u>7</u>	
<u>4</u>	18	17	16	15	<u>10</u> 14	13	
<u>3</u>		<u>14</u>	<u>13</u>	<u>11</u>	<u>9</u> <u>10</u>	<u>6</u> <u>6</u>	<u>2</u>
	19	20	21	22	23	24	
		<u>14</u>			<u>8</u> <u>9</u>		<u>1</u>
	30	29	28	27	26	25	
					<u>8</u>	<u>5</u>	<u>1</u>
	31	32	<u>12</u> 33	34	35	36	

Remonumentation of Certain Original Corner Points,
T. 4 S., R. 30 E., Willamette Meridian, Oregon

CHAINS

A fir, 14 ins. diam., bears N. 63° E., 34 lks. dist., mkd. T4S R31E S18 BT.

A fir, 11 ins. diam., bears S. 82° W., 48 lks. dist., mkd. T4S R30E S24 BT.

Deposit corner stone alongside iron post.

The cor. of secs. 1, 6, 7, and 12, determined at record bearing and distance from the remaining original bearing trees:

A pine, 17 ins. diam., bears N. 34° E., 30 lks. dist., with scribe marks R31E S6 BT visible on open blaze.

A pine, 17 ins. diam., bears N. 35° W., 45 lks. dist., with scribe marks T4S R visible on open blaze.

At the corner point

Set an iron post, 28 ins. long, 2½ ins. diam., 22 ins. in the ground, and in a mound of stone, 3 ft. base, to top, with brass cap mkd.

T 4 S			
R 30 E	R 31 E		
S 1	S 6		
S 12	S 7		
1978			

from which new bearing trees

A fir, 13 ins. diam., bears S. 66° E., 37½ lks. dist., mkd. T4S R31E S7 BT.

A ponderosa pine, 17 ins. diam., bears S. 67° W., 60½ lks. dist., mkd. T4S R30E S12 BT.

West Boundary, T. 4 S., R. 30 E.,
Willamette Meridian, Oregon

(Remonumenting corners established by Edward W. Sanderson
U. S. Deputy Surveyor, in 1882)

The cor. of secs. 13, 18, 19, and 24, monumented with the original basalt stone, 14 x 10 x 5 ins., firmly set 4 ins. in the ground, mkd. with 3 notches on N. and S. edges, from which the remains of the original bearing trees:

A root hole, bears N. 45° E., 47 lks. dist., with a down pine alongside, 35 ins. diam., no marks visible.

A decayed larch stump, size indeterminate, bears S. 12° E., 40 lks. dist., no marks visible.

A larch, 20 ins. diam., bears N. 10° W., 43 lks. dist., with scribe marks 4S R29E visible on partially open blaze. (Record, 38 lks.)

Remonumentation of Certain Original Corner Points,
T. 4 S., R. 30 E., Willamette Meridian, Oregon

CHAINS

At the corner point

Set an iron post, 28 ins. long, $2\frac{1}{2}$ ins. diam., 24 ins. in the ground, with brass cap mkd.

T 4 S			
R 29 E		R 30 E	
S 13		S 18	
S 24		S 19	
1978			

from which new bearing trees

A white fir, 7 ins. diam., bears N. 78° E., 25 lks. dist., mkd. T4S R30E S18 BT.

A ponderosa pine, 15 ins. diam., bears S. $57\frac{1}{2}^\circ$ E., 60 lks. dist., mkd. T4S R30E S19 BT.

A white fir, 12 ins. diam., bears S. $16\frac{1}{2}^\circ$ W., 61 lks. dist., mkd. T4S R29E S24 BT.

Deposit corner stone alongside iron post.

The $\frac{1}{4}$ sec. cor. of secs. 13 and 18, determined at record distance from the remains of the original bearing trees:

A decayed larch stump, size indeterminate, bears N. 79° E., 16 lks. dist., no marks visible. (Record, N. 62° E.)

A larch snag, 26 ins. diam., bears N. 34° W., 26 lks. dist., with scribe marks $\frac{1}{4}$ S BT visible on open blaze.

At the corner point

Set an iron post, 28 ins. long, $2\frac{1}{2}$ ins. diam., 24 ins. in the ground, with brass cap mkd.

T 4 S			
$\frac{1}{4}$			
R 29 E		R 30 E	
S 13		S 18	
1978			

from which new bearing trees

A white fir, 8 ins. diam., bears N. 62° E., 44 lks. dist., mkd. $\frac{1}{4}$ S18 BT.

A white fir, 10 ins. diam., bears S. 34° W., $15\frac{1}{2}$ lks. dist., mkd. $\frac{1}{4}$ S13 BT.

The cor. of secs. 7, 12, 13, and 18, monumented with the remains of the original corner tree, a pine stump, 15 ins. diam., with a down pine alongside, 15 ins. diam., with scribe marks T4S S visible on open blaze on one side, and T4S S13 visible on open blaze on opposite side, from which the remains of the original bearing trees:

A sawed pine stump, 32 ins. diam., bears S. 51° E., 26 lks. dist., with scribe marks BT visible on open blaze. (Record, S. 64° E.)

Remonumentation of Certain Original Corner Points,
T. 4 S., R. 30 E., Willamette Meridian, Oregon

CHAINS

A sawed larch stump, 20 ins. diam., bears S. 60° W.,
30 lks. dist., no marks visible.

A pine, 28 ins. diam., bears N. 24° W., 37 lks.
dist., with scribe marks T4S R29E S12 visible
on open blaze. (Record, N. 28° W., 43 lks.)

At the corner point

Set an iron post, 28 ins. long, 2½ ins. diam., 24 ins.
in the ground, inside pine stump, with brass cap mkd.

T 4 S	
R 29 E	R 30 E
S 12	S 7
S 13	S 18
1978	

from which new bearing trees

A fir, 15 ins. diam., bears N. 59½° E., 52 lks.
dist., mkd. T4S R30E S7 BT.

A fir, 14 ins. diam., bears S. 85° E., 41 lks.
dist., mkd. T4S R30E S18 BT.

A fir, 18 ins. diam., bears S. 53½° W., 68 lks.
dist., mkd. T4S R29E S13 BT.

Subdivisions, T. 4 S., R. 30 E.,
Willamette Meridian, Oregon

(Remonumenting corners established by George S. Pershin,
U. S. Deputy Surveyor, in 1882)

The cor. of secs. 25, 26, 35, and 36, monumented with the
original unmarked basalt stone, 15 x 10 x 5 ins., firmly
set 4 ins. in the ground, and in a mound of stone, 2 ft.
base, 6 ins. high, from which the remains of the original
bearing trees:

A sawed pine stump, 20 ins. diam., bears N. 80° E.,
96 lks. dist., with scribe marks BT visible on
open blaze.

A pine, 24 ins. diam., bears S. 57° E., 85 lks.
dist., with healed blaze. (Record, 75 lks.)

A pine, 30 ins. diam., bears S. 55° W., 43 lks.
dist., with scribe marks T4S R30E visible on
open blaze. (Record, S. 48° W.)

A sawed pine stump, 26 ins. diam., bears N. 77° W.,
82 lks. dist., with scribe marks BT visible on
open blaze.

At the corner point

Set an iron post, 28 ins. long, 2½ ins. diam., 10 ins.
in the ground, to solid rock, and in a mound of stone, 3
ft. base, to top, with brass cap mkd.

CERTIFICATE OF SURVEY

(I) ~~(We)~~, Craig L. Wanless, Cadastral Surveyor, HEREBY CERTIFY upon honor that, in pursuance of special instructions bearing date of the 3rd day of May, 19 57, (I) ~~(We)~~ have remonumented certain original corner points, township 4 south, range 30 east,

of the Willamette Meridian, in the State of Oregon, which are represented in the foregoing field notes as having been executed by (me), ~~(us)~~ and under (my) ~~(our)~~ direction; and that said survey has been made in strict conformity with said special instructions, the Manual of Instructions for the Survey of the Public Lands of the United States, and in specific manner described in the foregoing field notes.

October 19, 1978 (Date) Craig L. Wanless (Cadastral Surveyor)

CERTIFICATE OF APPROVAL

BUREAU OF LAND MANAGEMENT Washington, D.C. Denver, Colorado

The foregoing field notes of the remonumentation of certain original corner points, township 4 south, range 30 east, Willamette Meridian, Oregon,

executed by Craig L. Wanless, Cadastral Surveyor, having been critically examined and found correct, are hereby approved.

FEB 07 1980 (Date) [Signature] (Chief, Division of Cadastral Survey) Chief, Cadastral Survey Examination and Approval Staff

CERTIFICATE OF TRANSCRIPT

I CERTIFY That the foregoing transcript of the field notes of the above-described surveys in, is a true copy of the original field notes.

(Date) (Chief, Division of Cadastral Survey) GPO 849-626