

Form 9180-6  
(April 1974)

UNITED STATES  
DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT

ORIGINAL

# FIELD NOTES

OF THE

REMONUMENTATION OF CERTAIN ORIGINAL CORNER POINTS,

TOWNSHIP 3 SOUTH, RANGE 31 EAST,

---

---

---

---

---

---

---

---

---

---

---

---

---

---

---

---

---

---

---

---

---

---

---

---

---

---

Of the WILLAMETTE Meridian,

In the State of OREGON

EXECUTED BY

Craig L. Wanless, Cadastral Surveyor

---

---

---

---

Under special instructions dated May 3, 19 57, approved May 6, 1957,

, which provided for the surveys included under U.S. Survey/Group  
Number 350, and assignment instructions dated March 27, 19 78.

---

Survey commenced May 10, 19 78

Survey completed May 18, 19 78



# INDEX DIAGRAM

Township 3 South, Range 31 East,

6	5	4	3	2	1	
7	8	9	10	11	12	
18	17	16	15	14	13	
19	20	21	22	23	24	<u>6</u>
30	29	28	27	26	25	<u>6</u>
		<u>11</u> <u>12</u>	<u>9</u> <u>10</u>	<u>8</u>	<u>7</u>	<u>5</u>
31	32	<u>11</u> 33	34	<u>8</u> 35	<u>7</u> 36	<u>5</u>
<u>4</u>	<u>4</u>	<u>3</u>	<u>3</u>	<u>2</u>	<u>2</u>	<u>1</u>



## T. 3 S., R. 31 E., Willamette Meridian, Oregon

## CHAINS

The following field notes describe the remonumentation of certain original corner points, township 3 south, range 31 east, Willamette Meridian, Oregon, as provided for in the General Special Instructions, Group Number 350, Oregon, dated May 3, 1957, "Investigation of Collateral or Physical Evidence of Corner Positions and Accessories Followed by Remonumentation of Corner Points, with New Accessories when Needed".

The remonumentation of original corner points was made at the request of the United States Forest Service, in conjunction with their Land Line Location Program.

The mean magnetic declination is  $20^{\circ} 30'$  E.

South Boundary, T. 3 S., R. 31 E.,  
Willamette Meridian, Oregon

(Remonumenting corners established by George S. Pershin, U. S. Deputy Surveyor, in 1878, and changed to corners of minimum control by George S. Pershin, U. S. Deputy Surveyor, in 1879)

The cor. of secs. 34 and 35 only, on the S. bdy. of the Tp., monumented with the original unmarked basalt stone, 18 x 10 x 5 ins., firmly set 6 ins. in the ground, and in a mound of stone, 2 ft. base, 1 ft. high, from which the remains of the original bearing trees:

A sawed pine stump, 13 ins. diam., bears N.  $28^{\circ}$  E., 27 lks. dist., with a down pine alongside, 13 ins. diam., with scribe marks T3S R31E S35 BT visible on open blaze.

A pine, 20 ins. diam., bears S.  $56^{\circ}$  W., 36 lks. dist., with healed blaze.

A sawed pine stump, 12 ins. diam., bears N.  $2^{\circ}$  W., 40 lks. dist., with scribe marks BT visible on open blaze.

At the corner point

Set an iron post, 28 ins. long,  $2\frac{1}{2}$  ins. diam., 22 ins. in the ground, and in a mound of stone, 3 ft. base, to top, with brass cap mkd.

T 3 S R 31 E  
S 34 | S 35  
T 4 S R 31 E  
S 1  
1978

from which new bearing trees

A fir, 14 ins. diam., bears N.  $64\frac{1}{2}^{\circ}$  E., 140 lks. dist., mkd. T3S R31E S35 BT.

A fir, 14 ins. diam., bears N.  $66^{\circ}$  W., 74 lks. dist., mkd. T3S R31E S34 BT.

Deposit corner stone alongside iron post.



Remonumentation of Certain Original Corner Points,  
T. 3 S., R. 31 E., Willamette Meridian, Oregon

CHAINS

The cor. of secs. 33 and 34 only, on the S. bdy. of the Tp., monumented with the original unmarked basalt stone, 20 x 10 x 8 ins., firmly set 6 ins. in the ground, and in a mound of stone, 3 ft. base, 6 ins. high, from which the remains of the original bearing trees:

A pine snag, 50 ins. diam., bears N. 10° E., 180 lks. dist., no marks visible. (Record, 80 lks.)

A sawed pine stump, 20 ins. diam., bears N. 18° W., 198 lks. dist., with scribe marks BT visible on open blaze. (Record, 98 lks.)

At the corner point

Set an iron post, 28 ins. long, 2½ ins. diam., 18 ins. in the ground, and in a mound of stone, 3 ft. base, to top, with brass cap mkd.

T 3 S R 31 E  
S 33 | S 34  
T 4 S R 31 E  
S 2  
1978

from which new bearing trees

A ponderosa pine, 16 ins. diam., bears N. 34° E., 121 lks. dist., mkd. T3S R31E S34 BT.

A ponderosa pine, 14 ins. diam., bears N. 65° W., 204 lks. dist., mkd. T3S R31E S33 BT.

Deposit corner stone alongside iron post.

The ¼ sec. cor. of sec. 33 only, on the S. bdy. of the Tp., determined at record bearing and distance from the remains of the original bearing trees:

A pine snag, 38 ins. diam., bears N. 77° W., 49 lks. dist., with scribe marks ¼ S visible on open blaze.

At the corner point

Set an iron post, 28 ins. long, 2½ ins. diam., 18 ins. in the ground, to solid rock, and in a mound of stone, 3 ft. base, to top, with brass cap mkd.

T 3 S R 31 E  
¼ S 33  
1978

from which new bearing trees

A ponderosa pine, 12 ins. diam., bears N. 35° E., 33 lks. dist., mkd. ¼ S33 BT.

A ponderosa pine, 10 ins. diam., bears N. 24° W., 62 lks. dist., mkd. ¼ S33 BT.

Corner is located at corner of fences, fences extend N. and W.



Remonumentation of Certain Original Corner Points,  
T. 3 S., R. 31 E., Willamette Meridian, Oregon

## CHAINS

The cor. of secs. 32 and 33 only, on the S. bdy. of the Tp., determined at record distance from the remains of the original bearing trees:

A pine snag, 28 ins. diam., bears S. 71° E., 50 lks. dist., with scribe marks T4S R31E S4 visible on open blaze. (Record, S. 76° E.)

A sawed fir stump, 21 ins. diam., bears S. 66° W., 19 lks. dist., with healed blaze. (Record, S. 50° W.)

A sawed and decayed pine stump, size indeterminate, bears N. 20° W., 97 lks. dist., no marks visible.

At the corner point

Set an iron post, 28 ins. long, 2½ ins. diam., 22 ins. in the ground, and in a mound of stone, 3 ft. base, to top, with brass cap mkd.

T 3 S R 31 E  
S 32 | S 33  
 T 4 S R 31 E  
 S 3  
 1978

from which new bearing trees

A fir, 13 ins. diam., bears N. 75° E., 67 lks. dist., mkd. T3S R31E S33 BT.

A ponderosa pine, 12 ins. diam., bears N. 40° W., 106 lks. dist., mkd. T3S R31E S32 BT.

The ¼ sec. cor. of sec. 32 only, on the S. bdy. of the Tp., monumented with the original unmarked basalt stone, 14 x 10 x 8 ins., firmly set 6 ins. in the ground, from which the remains of the original bearing trees:

A sawed pine stump, 28 ins. diam., bears S. 58° W., 58 lks. dist., with scribe marks BT visible on open blaze.

A sawed pine stump, 20 ins. diam., bears N. 72° W., 81 lks. dist., with scribe marks ¼ S BT visible on open blaze.

At the corner point

Set an iron post, 28 ins. long, 2½ ins. diam., 24 ins. in the ground, with brass cap mkd.

T 3 S R 31 E  
¼ S 32  
 1978

from which new bearing trees

A ponderosa pine, 10 ins. diam., bears N. 28½° E., 42 lks. dist., mkd. ¼ S32 BT.

A ponderosa pine, 12 ins. diam., bears N. 55° W., 45 lks. dist., mkd. ¼ S32 BT.

Deposit corner stone alongside iron post.



Remonumentation of Certain Original Corner Points,  
T. 3 S., R. 31 E., Willamette Meridian, Oregon

## CHAINS

The cor. of secs. 31 and 32 only, on the S. bdy. of the Tp., determined at record distance from the remains of the original bearing trees:

A fir, 38 ins. diam., bears N. 55° E., 23 lks. dist., with scribe marks T3S R31E S32 visible on open blaze. (Record, pine)

A sawed pine stump, 33 ins. diam., bears S. 50° E., 35 lks. dist., with scribe marks BT visible on open blaze.

A fir, 26 ins. diam., bears S. 84° W., 20 lks. dist., with healed blaze. (Record, S. 71° W.)

At the corner point

Set an iron post, 28 ins. long, 2½ ins. diam., 22 ins. in the ground, and in a mound of stone, 3 ft. base, to top, with brass cap mkd.

T 3 S R 31 E  
S 31 | S 32  
 T 4 S R 31 E  
 S 4  
 1978

from which a new bearing tree

A ponderosa pine, 29 ins. diam., bears N. 41° W., 124 lks. dist., mkd. T3S R31E S31 BT.

The ¼ sec. cor. of sec. 31 only, on the S. bdy. of the Tp., monumented with the original basalt stone, 17 x 12 x 6 ins., loosely set 1 in. in the ground, mkd. ¼ on N. face, from which the remains of the original bearing trees:

A pine snag, 22 ins. diam., bears N. 20° E., 54 lks. dist., with scribe marks ¼ S visible on open blaze.

A decayed pine stump, size indeterminate, bears S. 20° E., 41 lks. dist., no marks visible on open blaze.

At the corner point

Set an iron post, 28 ins. long, 2½ ins. diam., 22 ins. in the ground, with brass cap mkd.

T 3 S R 31 E  
¼ S 31  
 1978

from which new bearing trees

A fir, 10 ins. diam., bears N. 70° E., 24 lks. dist., mkd. ¼ S31 BT.

A fir, 11 ins. diam., bears N. 5½° W., 37½ lks. dist., mkd. ¼ S31 BT.

Deposit corner stone alongside iron post.



UNITED STATES  
DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT

FIELD ASSISTANTS

NAMES	CAPACITY
Edward W. Moyer	Engineering Aid

Office of the Director, Bureau of Land Management, Washington, D.C. 20250

DATE: \_\_\_\_\_

Prepared by: \_\_\_\_\_

Checked by: \_\_\_\_\_

Approved by: \_\_\_\_\_

Special Agent in Charge



CERTIFICATE OF SURVEY

(I) ~~(XX)~~, Craig L. Wanless, Cadastral Surveyor, HEREBY CERTIFY upon honor that, in pursuance of special instructions bearing date of the 3rd day of May, 19 57, (I) ~~(XX)~~ have remonumented certain original corner points, township 3 south, range 31 east,

of the Willamette Meridian, in the State of Oregon, which are represented in the foregoing field notes as having been executed by (me), ~~(XX)~~ and under (my) ~~(XX)~~ direction; and that said survey has been made in strict conformity with said special instructions, the Manual of Instructions for the Survey of the Public Lands of the United States, and in specific manner described in the foregoing field notes.

October 19, 1978  
(Date)

*Craig L. Wanless*  
(Cadastral Surveyor)

(Date)

(Cadastral Surveyor)

CERTIFICATE OF APPROVAL

BUREAU OF LAND MANAGEMENT  
~~Washington, D.C.~~  
Denver, Colorado

The foregoing field notes of the remonumentation of certain original corner points, township 3 south, range 31 east, Willamette Meridian, Oregon,

executed by Craig L. Wanless, Cadastral Surveyor, having been critically examined and found correct, are hereby approved.

FEB 07 1980  
(Date)

*J. Voorhees*  
(Chief, Division of Cadastral Survey)

Chief, Cadastral Survey Examination and Approval Staff

CERTIFICATE OF TRANSCRIPT

I CERTIFY That the foregoing transcript of the field notes of the above-described surveys in \_\_\_\_\_, is a true copy of the original field notes.

(Date)

(Chief, Division of Cadastral Survey) GPO 849-526