

UNITED STATES  
DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT

ORIGINAL

FIELD NOTES

OF THE

REMONUMENTATION OF CERTAIN ORIGINAL CORNER POINTS,

TOWNSHIP 5 SOUTH, RANGE 30 EAST,

[Lined area for field notes]

Of the WILLAMETTE Meridian,

In the State of OREGON

EXECUTED BY

Craig L. Wanless, Cadastral Surveyor

[Lined area for signature and title]

Under special instructions dated May 3, 1957, approved May 6, 1957,

\_\_\_\_\_, which provided for the surveys included under U.S. Survey/Group  
Number 350, and assignment instructions dated March 27, 1978.

Survey commenced April 5, 1978

Survey completed April 18, 1978

# INDEX DIAGRAM

Township 5 South, Range 30 East,

					<u>7</u>	<u>3</u>
6	5	4	3	2	1	
	<u>17</u>	<u>14</u>	<u>11</u> <u>11</u>			
7	8	9	<u>10</u> 10	<u>9</u> 11	12	
<u>17</u>	<u>16</u>	<u>13</u>		<u>8</u>		
18	<u>16</u> 17	16	<u>10</u> 15	<u>8</u> 14	13	
<u>15</u>		<u>12</u> <u>13</u>			<u>7</u>	
19	20	21	22	23	<u>6</u> 24	<u>3</u>
	<u>15</u>		<u>9</u>		<u>6</u>	<u>2</u>
30	29	28	27	26	<u>5</u> 25	<u>2</u>
<u>14</u>		<u>12</u>			<u>5</u>	<u>1</u>
31	32	33	34	35	36	

4

Remonumentation of Certain Original Corner Points,  
T. 5 S., R. 30 E., Willamette Meridian, Oregon

## CHAINS

from which new bearing trees

A fir, 10 ins. diam., bears N. 31° E., 54 lks.  
dist., mkd. T5S R31E S19 BT.

A fir, 8 ins. diam., bears S. 13½° E., 17 lks.  
dist., mkd. T5S R31E S30 BT.

A ponderosa pine, 9 ins. diam., bears S. 71° W.,  
58 lks. dist., mkd. T5S R30E S25 BT.

A fir, 8 ins. diam., bears N. 38½° W., 11 lks.  
dist., mkd. T5S R30E S24 BT.

Deposit corner stone alongside iron post.

The ¼ sec. cor. of secs. 19 and 24, on the E. bdy. of the  
Tp., monumented with the original unmarked basalt stone,  
15 x 10 x 5 ins., firmly set 6 ins. in the ground, and  
in a mound of stone, 2 ft. base, 6 ins. high, from which  
the remains of the original bearing trees:

A pine, 27 ins. diam., bears N. 57° E., 38 lks.  
dist., with healed blaze. (Record, 35 lks.)

A pine snag, 33 ins. diam., bears N. 35° W., 33  
lks. dist., with scribe mark S visible on open  
blaze. (Record, N. 42° W.)

At the corner point

Set an iron post, 28 ins. long, 2½ ins. diam., 22 ins.  
in the ground, and in a mound of stone, 3 ft. base, to  
top, with brass cap mkd.

T 5 S  
¼  
R 30 E | R 31 E  
S 24 | S 19  
1978

from which a new bearing tree

A ponderosa pine, 8 ins. diam., bears S. 71° W.,  
17 lks. dist., mkd. ¼ S24 BT.

Deposit corner stone alongside iron post.

The cor. of Tps. 4 and 5 S., Rs. 30 and 31 E., monumented  
with the original unmarked basalt stone, 18 x 14 x 10  
ins., firmly set 5 ins. in the ground, and in a mound of  
stone, 4 ft. base, 1 ft. high, from which the remains of  
the original bearing trees:

A sawed pine stump, 22 ins. diam., bears N. 50° E.,  
54 lks. dist., with fragmentary scribe marks  
visible on open blaze. (Record, N. 56° E.)

A sawed pine stump, 26 ins. diam., bears S. 33° E.,  
118 lks. dist., with scribe marks BT visible  
on open blaze.

A pine, 21 ins. diam., bears S. 70° W., 39 lks.  
dist., with scribe marks T5S R30E S1 B visible  
on open blaze. (Record, S. 62° W.)

Remonumentation of Certain Original Corner Points,  
T. 5 S., R. 30 E., Willamette Meridian, Oregon

CHAINS

A pine, 29 ins. diam., bears N. 80° W., 80 lks. dist., with healed blaze.

At the corner point

Set an iron post, 28 ins. long, 2½ ins. diam., 22 ins. in the ground, and in a mound of stone, 3 ft. base, to top, with brass cap mkd.

T 4 S			
R 30 E		R 31 E	
S 36		S 31	
S 1		S 6	
T 5 S			
1978			

from which new bearing trees

A ponderosa pine, 9 ins. diam., bears N. 34° E., 27½ lks. dist., mkd. T4S R31E S31 BT.

A ponderosa pine, 11 ins. diam., bears S. 52½° E., 31 lks. dist., mkd. T5S R31E S6 BT.

Deposit corner stone alongside iron post.

West Boundary, T. 5 S., R. 30 E.,  
Willamette Meridian, Oregon

(Remonumenting a corner established by Edward W. Sanderson  
U. S. Deputy Surveyor, in 1882)

The ¼ sec. cor. of secs. 25 and 30, on the W. bdy. of the Tp., monumented with the original basalt stone, 20 x 10 x 8 ins. (record, 18 x 8 x 7 ins.), firmly set 6 ins. in the ground, and in a mound of stone, 2 ft. base, 6 ins. high, mkd. ¼ on W. face, from which the remains of an original bearing tree:

A root hole, bears S. 50° E., 52 lks. dist., with a sawed pine alongside, 36 ins. diam., with scribe marks BT visible on open blaze. (Record, S. 52° E.)

At the corner point

Set an iron post, 28 ins. long, 2½ ins. diam., 20 ins. in the ground, and in a mound of stone, 3 ft. base, to top, with brass cap mkd.

T 5 S			
¼			
R 29 E		R 30 E	
S 25		S 30	
1978			

from which new bearing trees

A lodgepole pine, 6 ins. diam., bears N. 75° E., 66½ lks. dist., mkd. ¼ S30 BT.

A fir, 8 ins. diam., bears N. 45° W., 65½ lks. dist., mkd. ¼ S25 BT.

Deposit corner stone alongside iron post.



CERTIFICATE OF SURVEY

(I) (~~XX~~), Craig L. Wanless, Cadastral Surveyor, HEREBY CERTIFY upon honor that, in pursuance of special instructions bearing date of the 3rd day of May, 19 57, (I) (~~XX~~) have remonumented certain original corner points, township 5 south, range 30 east,

of the Willamette Meridian, in the State of Oregon, which are represented in the foregoing field notes as having been executed by (me), (~~us~~) and under (my) (~~our~~) direction; and that said survey has been made in strict conformity with said special instructions, the Manual of Instructions for the Survey of the Public Lands of the United States, and in specific manner described in the foregoing field notes.

October 17, 1978 (Date) Craig L. Wanless (Cadastral Surveyor)

CERTIFICATE OF APPROVAL

BUREAU OF LAND MANAGEMENT Washington, D.C. Denver, Colorado

The foregoing field notes of the remonumentation of certain original corner points, township 5 south, range 30 east, Willamette Meridian, Oregon,

executed by Craig L. Wanless, Cadastral Surveyor, having been critically examined and found correct, are hereby approved.

FEB 07 1980 (Date) J.D. Voorhes (Chief, Division of Cadastral Survey) Chief, Cadastral Survey Examination and Approval Staff

CERTIFICATE OF TRANSCRIPT

I CERTIFY That the foregoing transcript of the field notes of the above-described surveys in, is a true copy of the original field notes.

(Date) (Chief, Division of Cadastral Survey) GPO 849-626