

FIELD NOTES

Of the survey of the Sabinsson
Lines of Township 43 with
Range 30 East, Willamette Meridian,
 Oregon, as surveyed by George S.
Pershing, U. S. Deputy Surveyor,
 under his Contract No. 430, dated
March 23rd, 1882

Survey commenced, June 12th 1882
 Survey completed, June 20 1882

NAMES AND DUTIES OF ASSISTANTS.

-, Compassman.
- Frank F. Ellis....., Chainman.
- William P. Millins....., Chainman.
-, Chainman.
-, Chainman.
- Valentine Brown, Axeman.
-, Axeman.
-, Flagman.

PRELIMINARY OATHS OF ASSISTANTS:

We, Frank F. Ellis and
William P. Mellins

do solemnly swear that we will faithfully execute the duties of Chain Carriers, that we will level the chain over even and uneven ground, and plumb the tally pins, either by sticking or dropping the same; that we will report the true distance to all notable objects, and the true length of all lines that we will assist in measuring, to the best of our skill and ability, and in accordance with the instructions given us in

the survey of the Subdivision
lines of Township 4 South
Range 30 East Willamette Meridian, Oregon.

Frank F. Ellis, Chainman.

William P. Mellins, Chainman.

_____, Chainman.

_____, Chainman.

Subscribed and sworn to before me, this twelfth

day of June 1882.

[SEAL.]

George S. Perstman

A. U. S. Dep. Sur

~~We~~ Valentine Brown and

_____, do solemnly swear that we will well and truly perform the duties of Axemen in the establishment of corners and other duties, according to instructions given us, and to the best of our

skill and ability, in the survey of the Subdivision ^{me} cons of my

T. 4 South R. 30 East Willamette Meridian Oregon.

Valentine Brown, Axeman.

_____, Axeman.

Subscribed and sworn to before me, this twelfth

day of June 1882.

[SEAL.]

George S. Perstman

A. U. S. Dep. Sur

INDEX.

Referring the Lines to the Pages of the Field Notes.

T. *4 South* R. *30 East* Will. Mer.

6	120	5	88	4	66	3	44	2	22	1
118		116		86		64		42		20
7	114	8	84	9	62	10	40	11	18	12
112		110		82		60		38		16
18	108	17	80	16	58	15	36	14	14	13
106		104		78		56		34		12
19	102	20	76	21	54	22	32	23	10	24
100		98		74		52		30		8
30	96	29	72	28	50	27	28	26	6	25
94		92		70		48		26		4
31	90	32	68	33	46	34	24	35	2	36

Meanders of _____ Pages _____ to _____

Meanders of _____ Pages _____ to _____

Subdivisions of T. 4 South R. 30 East

Willamette Meridian, Oregon.

East on a random line
between Sec. 25 & 36

ba. $19^{\circ} 00'$ East -

Pundulating

4000 Set temporary $\frac{1}{4}$ sec. cor

7998 Intersected East boundary
& lrs. north of cor. to sec.
25 and 36 which is a

Stone $14 \times 12 \times 5$ marked with
5 notches on N. edge from which

A Pine 16 ins. di. lrs. N. $62^{\circ} E$. 26 lrs dist.

marked T. 4 S. R. 31 E. S. 30 BT

A Pine 20 ins di. lrs S. $72^{\circ} W$. 32 lrs dist

marked T. 4 S. R. 30 E. S. 36 BT

A Fir 8 ins di. lrs. N. $14^{\circ} W$. 38 lrs dist

marked: T. 4 S. R. 30 E. S. 25 BT

no other tree

Thence I run
N. $89^{\circ} 57'$ West on a true line

between Sec. 25 and 36

ba. $19^{\circ} 30'$ East -

8

1868

Subdivisions of T. 4 S out R. 30 East

Willamette Meridian, Oregon.

East on a random line
between Sec. 24 and 25 -
Va. $20^{\circ}15'$ East -

21.00 Wagon road Co. N. N. & S. E

40.00 Set temporary $\frac{1}{4}$ Sec. cor.

79.94 Intersected East Boundary

32 lbs. North of cor. to Sec

24 and 25 which is a

Stone $20 \times 12 \times 8$ marked
with 4 notches on N. edge

A Pine 24 ins. di. lbs. N. 48° E. 182 lbs dist

marked T4 S. R. 31 E. S. 19 B. T.

A Pine 28 in. di. lbs S. 38° E. 196 lbs dist

marked T4 S. R. 31 E. S. 30 B. T.

A Pine 10 ins. di. lbs. N. 90° W 92 lbs dist -

marked T4 S. R. 30 E. S. 24 B. T

no tree S. W.

Thence I run

N. $89^{\circ}46'$ West on a true line

between Sec 24 and 25 -

Va $19^{\circ}30'$ East

12

Subdivisions of T. 4 South R. 30 East

Willamette Meridian, Oregon.

East on a random line between
Sections 13 and 24

on a $21^{\circ} 00'$ East -

15.50 A Spring branch co S. E.

40.00 Set temporary $\frac{1}{4}$ Sec. cor.

80.22 Intersected E boundary 58 lks.

North of cor. to Sec. 13 and 24

which is a stone $16 \times 12 \times 8$ in

Marked with B notches on N.

edge

A Pine 22 ins. di. lrs. N. 59° E. 53 lks dist

Marked. T 4 S. R. 31 E. S 18 B, T

A Pine 16 ins. di. lrs. S 52° E 61 lks. dist

Marked. T 4 S. R. 31 E. S 19 B, T

A Pine 20 ins. di. lrs. S 34° W. 78 lks dist

Marked T 4 S R. 30 E. S 24 B, T

A Pine 8 ins. di. lrs. N. 68° W. 77 lks dist

Marked T 4 S. R. 30 E. S. 13 B, T

Thence \mathcal{D} run

N. $89^{\circ} 35'$ West on a true line be-

tween Sec 13 and 24

16
77 76

Subdivisions of T.4 S. and R. 30 East
Willamette Meridian, Oregon.

East on a random line
between Sec. 12 and 13

ba. $22^{\circ} 45'$ East

(undulating)

4000 Set temporary $\frac{1}{4}$ Sec. cor

4600 Enter thick timber co. N.W. & S.E.

79.76 Intersected E. boundary 28 lks
South of cor. to Sec 12 and 13
which is a post-4 ins square

Set firmly in the ground marked

S. 7 on N.E. T.4 S. R. 31 E. S. 18 on S.E.

S. 13 on S. W. and T.4 S. R. 30 E. S. 12 on

N.W. from which

A Tanarack 12 ins di. lrs. N. 10° E. 14 lks dist

marked T.4 S. R. 31 E. S. 7 B.T.

A Fir 10 ins di. lrs. S. 57° E. 54 lks dist

marked T.4 S. R. 31 E. S. 18 B.T.

A Pine 16 ins di. lrs. S. 25° W. 50 lks dist

marked T.4 S. R. 30 E. S. 13 B.T.

A Tanarack 18 ins di. lrs. N. 51° W. 25 lks dist

marked T.4 S. R. 30 E. S. 12 B.T.

Thence Down

Subdivisions of T. 4 South R. 30 East

Willamette Meridian, Oregon.

East on a random line
between Sec. 1 and 12
Pa, $24^{\circ} 45'$ East

Along up N. face of slope
20,00 A Spring branch to North

4000 Set temporary $\frac{1}{4}$ Sec. cor

80,32 Intersect Co boundary 14 lbs ⁺³⁰⁰

South of cor. to Sec. 1 and 12
which is a Stone $16 \times 10 \times 8$ ins
Marked with one notch on
North edge

A Pine 12 ins di. lbs. N. $34^{\circ} E$ 30 lbs dist

Marked T. 4 S. R. 31 E. S. 6. B. T.

A Pine, 8 ins. di. lbs. S. $45^{\circ} E$. 27 lbs dist

Marked: T. 4 S. R. 31 E. S. 7. B. T.

A Pine 16 ins di. lbs. S $54^{\circ} W$. 34 lbs dist

Marked T. 4 S. R. 30 E. S. 12 B. T.

A Pine 13 ins di. lbs. N. $35^{\circ} W$. 45 lbs dist

Marked T. 4 S. R. 30 E. S. 1 B. T.

Thence A run

186

FINAL OATHS FOR SURVEYS.

A list of the names of the individuals employed by George S. Pershin, U. S. Deputy Surveyor, to assist in running, measuring and marking the lines and corners described in the foregoing field notes of the survey of the Subdivisional lines of Township 4 South Range 30 East Willamette Meridian, Oregon, showing the respective capacities in which they acted:

-, Compassman.
-, Chainman.
- Frank F. Ellis, Chainman.
- William P. Mullins, Chainman.
-, Chainman.
- Valentine Brown, Axeman.
-, Axeman.
-, Flagman.

FINAL OATHS OF ASSISTANTS.

We hereby certify that we assisted George S. Pershin, U. S. Deputy Surveyor, in surveying all those parts or portions of the Subdivisional lines of Township 4 South Range 30 East Willamette Meridian, Oregon, as are represented in the foregoing field notes as having been surveyed by him and under his direction; and that said survey has been in all respects, to the best of our knowledge and belief, well and faithfully surveyed, and the corner monuments established, according to the instructions furnished by the U. S. Surveyor General of Oregon.

-, Compassman.
- Frank F. Ellis, Chainman.
- William P. Mullins, Chainman.
-, Chainman.
-, Chainman.
- Valentine Brown, Axeman.
-, Axeman.
-, Flagman.

Subscribed and sworn to before me, this twentieth day of June 1882
George S. Pershin
A Dep. U. S. Sur

[SEAL.]

FINAL OATH OF DEPUTY SURVEYOR.

I, George S. Pershin

United States Deputy Surveyor, do solemnly swear that in pursuance of instructions received from James C. Tolman

U. S. Surveyor General for Oregon, bearing date of the 23rd day of March

, 1882, I have well, faithfully, and truly, in my own proper person, and in strict conformity with the instructions furnished by the U. S. Surveyor General for Oregon, the Surveying Manual, and the laws of

the United States, surveyed all those parts or portions of Sections
of Township 4 South Range 30 East

Willamette Meridian, in the State of Oregon, as are represented in the foregoing Field Notes as having been surveyed by me and under my directions; and I do further solemnly swear that all the corners of said survey have been established and perpetuated in strict accordance with the Surveying Manual, printed instructions, the special written instructions of the U. S. Surveyor General for Oregon, and in the specific manner described in the field notes, and that the foregoing are the true field notes of such survey, and should any fraud be detected I will suffer the penalty of perjury under the provisions of an Act of Congress approved August 8, 1846.

George S. Pershin
U. S. Deputy Surveyor.

Subscribed and sworn to before me, this 14th
day of July 1882

Ed. F. Lewis
Notary Public

188

FINAL OATH OF DEPUTY SURVEYOR

Office U. S. Surveyor General,

Portland, Oregon, *Aug 12* 1882

The following Field Notes of the Survey of
the Subdivisional lines of Township
No 14 South, Range No 30 East
Willamette Meridian Oregon
executed by *George S. Perkin U.S. Dept,*
Surv under *his* contract No. *130*
dated *March 23^d* 1882, having been
critically examined, the necessary corrections and ex-
planations made, the said field notes and the survey
they describe, are hereby approved.

James C. Tolman
Surveyor General.

