

FIELD NOTES

OF THE

REMONUMENTATION OF CERTAIN ORIGINAL CORNER POINTS,

TOWNSHIP 4 SOUTH, RANGE 32 EAST,

Of the WILLAMETTE Meridian,

In the State of OREGON

EXECUTED BY

Craig L. Wanless, Cadastral Surveyor

Under special instructions dated May 3, 19 57, approved May 6, 1957,

, which provided for the surveys included under ~~U.S. Survey~~/Group
Number 350, and assignment instructions dated July 18, 19 77.

Survey commenced July 18, 19 77

Survey completed August 3, 19 77

INDEX DIAGRAM

Township 4 South, Range 32 East,

	6	5	4	3	2	1	
<u>5</u>	<u>25</u>	<u>24</u> <u>25</u>		<u>17</u> <u>18</u>	<u>13</u>		
<u>5</u>	7	<u>24</u> 8	9	<u>17</u> 10	11	12	
<u>4</u>	<u>23</u>	<u>22</u> <u>23</u>	<u>20</u> <u>21</u>	<u>16</u>	<u>12</u>	<u>9</u>	
	18	17	16	<u>15</u> 15	14	<u>9</u> 13	
		<u>21</u> <u>22</u>	<u>19</u> <u>20</u>	<u>14</u> <u>15</u>	<u>11</u> <u>12</u>	<u>8</u>	<u>3</u>
	19	20	<u>19</u> 21	22	23	<u>8</u> 24	
			<u>18</u>	<u>14</u>	<u>10</u> <u>11</u>	<u>7</u> <u>7</u>	<u>3</u>
	30	29	28	27	26	25	<u>2</u>
				<u>13</u>		<u>6</u> <u>6</u>	<u>2</u>
	31	32	33	34	35	36	

T. 4 S., R. 32 E., Willamette Meridian, Oregon

CHAINS

The following field notes describe the remonumentation of certain original corner points, township 4 south, range 32 east, Willamette Meridian, Oregon, as provided for in the General Special Instructions, Group Number 350 Oregon, dated May 3, 1957, "Investigation of Collateral or Physical Evidence of Corner Positions and Accessories Followed by Remonumentation of Corner Points, with New Accessories when Needed".

The remonumentation of original corner points was made at the request of the United States Forest Service, in conjunction with their Land Line Location Program.

The mean magnetic declination is 20° E.

South Boundary, T. 4 S., R. 32 E.,
Willamette Meridian, Oregon

(Remonumenting a corner established by George S. Pershin,
U. S. Deputy Surveyor, in 1881)

The cor. of secs. 2, 3, 34, and 35, on the S. bdy. of the
Tp., determined at record bearing and distance from the
original bearing trees:

A ponderosa pine, 34 ins. diam., bears N. 88° E.,
76 lks. dist., with scribe marks 32E S visible
on open blaze.

A ponderosa pine, 30 ins. diam., bears S. 31° E.,
165 lks. dist., with healed blaze.

At the corner point

Set an iron post, 28 ins. long, 2½ ins. diam., 22 ins.
in the ground, with brass cap mkd.

T 4 S R 32 E
S 34 S 35
S 3 S 2
T 5 S
1977

from which a new bearing tree

A ponderosa pine, 23 ins. diam., bears S. 87° W.,
81 lks. dist., mkd. T5S R32E S3 BT.

No other suitable trees available within limits.

Corner is located 15 lks. west of dirt road, 12 lks.
wide, bears N. 25° E. and S. 25° W., and 4 lks.
N. 45° W. of wire fence corner, fences extend E., W.,
and N.

East Boundary, T. 4 S., R. 32 E.,
Willamette Meridian, Oregon

(Remonumenting corners established by George S. Pershin,
U. S. Deputy Surveyor, in 1881)

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FIELD ASSISTANTS

NAMES	CAPACITY
Larry C. Livingston	Forestry Aid
June Klein	Engineering Aid

JAN 2 1980

Chief, Technical Survey Examination and Approval Staff

I CERTIFY THAT THE FOLLOWING LISTED FIELD ASSISTANTS ARE CURRENTLY EMPLOYED BY THE BUREAU OF LAND MANAGEMENT AND ARE QUALIFIED TO ASSIST IN THE FIELD AS DESCRIBED:

CERTIFICATE OF SURVEY

(I) (~~XX~~), Craig L. Wanless, Cadastral Surveyor, HEREBY CERTIFY upon honor that, in pursuance of special instructions bearing date of the 3rd day of May, 1957, (I) (~~XX~~) have remonumented certain original corner points, township 4 south, range 32 east,

of the Willamette Meridian, in the State of Oregon, which are represented in the foregoing field notes as having been executed by (me), (~~XX~~) and under (my) (~~XXX~~) direction; and that said survey has been made in strict conformity with said special instructions, the Manual of Instructions for the Survey of the Public Lands of the United States, and in specific manner described in the foregoing field notes.

January 16, 1978
(Date)

Craig L. Wanless
(Cadastral Surveyor)

(Date)

(Cadastral Surveyor)

CERTIFICATE OF APPROVAL

BUREAU OF LAND MANAGEMENT
~~Washington, D.C.~~
Denver, Colorado

The foregoing field notes of the remonumentation of certain original corner points, township 4 south, range 32 east, Willamette Meridian, Oregon,

executed by Craig L. Wanless, Cadastral Surveyor, having been critically examined and found correct, are hereby approved.

JAN 23 1980
(Date)

J. D. [Signature]
(Chief, Division of Cadastral Survey)

Chief, Cadastral Survey Examination and Approval Staff

CERTIFICATE OF TRANSCRIPT

I CERTIFY That the foregoing transcript of the field notes of the above-described surveys in, is a true copy of the original field notes.

(Date)

(Chief, Division of Cadastral Survey) GPO 849-626