

Form 9180-6
(April 1974)

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

ORIGINAL

FIELD NOTES

OF THE

REMONUMENTATION OF CERTAIN ORIGINAL CORNER POINTS,

TOWNSHIP 4 SOUTH, RANGE 32 EAST,

Lined area for field notes, consisting of approximately 25 horizontal lines.

Of the WILLAMETTE Meridian,

In the State of OREGON

EXECUTED BY

Craig L. Wanless, Cadastral Surveyor

Under special instructions dated May 3, 19 57, approved May 6, 1957,

, which provided for the surveys included under U.S. Survey/Group
Number 350, and assignment instructions dated July 18, 19 77.

Survey commenced July 18, 19 77

Survey completed August 3, 19 77

INDEX DIAGRAM

Township 4 South, Range 32 East,

	6	5	4	3	2	1	
<u>5</u>	<u>25</u>	<u>24</u> <u>25</u>		<u>17</u> <u>18</u>	<u>13</u>		
<u>5</u>	7	<u>24</u> 8	9	<u>17</u> 10	11	12	
<u>4</u>	<u>23</u>	<u>22</u> <u>23</u>	<u>20</u> <u>21</u>	<u>16</u>	<u>12</u>	<u>9</u>	
	18	17	16	<u>15</u> 15	14	<u>9</u> 13	
		<u>21</u> <u>22</u>	<u>19</u> <u>20</u>	<u>14</u> <u>15</u>	<u>11</u> <u>12</u>	<u>8</u>	<u>3</u>
	19	20	<u>19</u> 21	22	23	<u>8</u> 24	
			<u>18</u>	<u>14</u>	<u>10</u> <u>11</u>	<u>7</u> <u>7</u>	<u>3</u>
	30	29	28	27	26	25	<u>2</u>
				<u>13</u>		<u>6</u> <u>6</u>	<u>2</u>
	31	32	33	34	35	36	

Remonumentation of Certain Original Corner Points,
T. 4 S., R. 32 E., Willamette Meridian, Oregon

CHAINS

At the corner point

Set an iron post, 28 ins. long, 2½ ins. diam., 20 ins. in the ground, and in a mound of stone, 3 ft. base, to top, with brass cap mkd.

T 4 S	
R 32 E	R 33 E
S 13	S 18
S 24	S 19
1977	

from which a new bearing tree

A fir, 10 ins. diam., bears N. 36° W., 96 lks. dist., mkd. T4S R32E S13 BT.

Deposit corner stone alongside iron post.

West Boundary, T. 4 S., R. 32 E.,
Willamette Meridian, Oregon

(Remonumenting corners established by George S. Pershin,
U. S. Deputy Surveyor, in 1880)

The cor. of secs. 7, 12, 13, and 18, on the W. bdy. of the Tp., monumented with the original unmarked basalt stone, 15 x 10 x 10 ins., firmly set 4 ins. in the ground, and in a mound of stone, 3 ft. base, 1 ft. high, from which the remains of the original bearing trees:

A pine, 20 ins. diam., bears N. 68° E., 162 lks. dist., with fragmentary scribe marks visible on partially healed blaze.

A pine, 38 ins. diam., bears S. 62° W., 121 lks. dist., with fragmentary scribe marks visible on partially healed blaze.

At the corner point

Set an iron post, 28 ins. long, 2½ ins. diam., 20 ins. in the ground, and in a mound of stone, 3 ft. base, to top, with brass cap mkd.

T 4 S	
R 31 E	R 32 E
S 12	S 7
S 13	S 18
1977	

from which new bearing trees

A lodgepole pine, 9 ins. diam., bears S. 41° E., 26 lks. dist., mkd. T4S R32E S18 BT.

A lodgepole pine, 9 ins. diam., bears N. 38½° W., 24½ lks. dist., mkd. T4S R31E S12 BT.

Deposit corner stone alongside iron post.

Remonumentation of Certain Original Corner Points,
T. 4 S., R. 32 E., Willamette Meridian, Oregon

CHAINS

The $\frac{1}{4}$ sec. cor. of secs. 7 and 12, on the W. bdy. of the Tp., monumented with a mound of stone, 3 ft. base, 1 ft. high, from which the remains of the original bearing trees:

A pine, 13 ins. diam., bears N. 47° E., 58 lks. dist., with healed blaze.

A root hole, bears S. 82° W., 20 lks. dist., with a down pine alongside, size indeterminate, with scribe marks $\frac{1}{4}$ S visible on open blaze.

At the corner point

Set an iron post, 28 ins. long, $2\frac{1}{2}$ ins. diam., 24 ins. in the ground, with brass cap mkd.

T 4 S	
$\frac{1}{4}$	
R 31 E	R 32 E
S 12	S 7
1977	

from which a new bearing tree

A fir, 16 ins. diam., bears N. $36\frac{1}{2}^\circ$ W., $31\frac{1}{2}$ lks. dist., mkd. $\frac{1}{4}$ S12 BT.

Corner is located 10 lks. east of wire fence, extending N. and S.

The cor. of secs. 1, 6, 7, and 12, on the W. bdy. of the Tp., determined at record bearing and distance from the only remaining original bearing tree:

A pine, 26 ins. diam., bears S. 63° W., 38 lks. dist., with scribe marks T4S R31E S12 visible on open blaze.

At the corner point

Set an iron post, 28 ins. long, $2\frac{1}{2}$ ins. diam., 24 ins. in the ground, with brass cap mkd.

T 4 S	
R 31 E	R 32 E
S 1	S 6
S 12	S 7
1977	

from which new bearing trees

A fir, 10 ins. diam., bears N. $15\frac{1}{2}^\circ$ E., 31 lks. dist., mkd. T4S R32E S6 BT.

A lodgepole pine, 11 ins. diam., bears S. 29° E., 58 lks. dist., mkd. T4S R32E S7 BT.

A fir, 10 ins. diam., bears N. 33° W., 80 lks. dist., mkd. T4S R31E S1 BT.

Corner is located 35 lks. east of dirt road, 10 lks. wide, bears N. 15° E. and S. 15° W.

Form 9180-8
(March 1969)

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FIELD ASSISTANTS

NAMES	CAPACITY
Larry C. Livingston	Forestry Aid
June Klein	Engineering Aid

JAN 3 1980

Chief, Cadastral Survey Examination and Approval Staff

I CERTIFY that the foregoing statement of the field assistants is true and correct and that the same have been personally examined and approved by me.

CERTIFICATE OF SURVEY

(I) (~~XX~~), Craig L. Wanless, Cadastral Surveyor, HEREBY CERTIFY upon honor that, in pursuance of special instructions bearing date of the 3rd day of May, 1957, (I) (~~XX~~) have remonumented certain original corner points, township 4 south, range 32 east,

of the Willamette Meridian, in the State of Oregon, which are represented in the foregoing field notes as having been executed by (me), (~~XX~~) and under (my) (~~XXX~~) direction; and that said survey has been made in strict conformity with said special instructions, the Manual of Instructions for the Survey of the Public Lands of the United States, and in specific manner described in the foregoing field notes.

January 16, 1978
(Date)

Craig L. Wanless
(Cadastral Surveyor)

(Date)

(Cadastral Surveyor)

CERTIFICATE OF APPROVAL

BUREAU OF LAND MANAGEMENT
~~Washington, D.C.~~
Denver, Colorado

The foregoing field notes of the remonumentation of certain original corner points, township 4 south, range 32 east, Willamette Meridian, Oregon,

executed by Craig L. Wanless, Cadastral Surveyor, having been critically examined and found correct, are hereby approved.

JAN 23 1980
(Date)

J. D. [Signature]
(Chief, Division of Cadastral Survey)

Chief, Cadastral Survey Examination and Approval Staff

CERTIFICATE OF TRANSCRIPT

I CERTIFY That the foregoing transcript of the field notes of the above-described surveys in, is a true copy of the original field notes.

(Date)

(Chief, Division of Cadastral Survey) GPO 849-626