

FIELD NOTES

OF THE

REMONUMENTATION OF CERTAIN ORIGINAL CORNER POINTS,

TOWNSHIP 4 SOUTH, RANGE 33½ EAST,

Of the WILLAMETTE Meridian,

In the State of OREGON

EXECUTED BY

Craig L. Wanless, Cadastral Surveyor

Under special instructions dated May 3, 19 57, approved May 6, 1957,

, which provided for the surveys included under U.S. Survey/Group
Number 350, and assignment instructions dated August 23, 19 77.

Survey commenced September 8, 19 77

Survey completed September 9, 19 77

INDEX DIAGRAM

Township 4 South, Range 33½ East,

6	5	4	3	2	1
7	8	9	10	11	12
18	17	16	15	14	13
				<u>3</u>	<u>2</u>
19	20	21	22	23	24
30	29	28	27	26	25
31	32	33	34	35	36

2

1

1

T. 4 S., R. 33½ E., Willamette Meridian, Oregon

CHAINS

The following field notes describe the remonumentation of certain original corner points, township 4 south, range 33½ east, Willamette Meridian, Oregon, as provided for in the General Special Instructions, Group Number 350 Oregon, dated May 3, 1957, "Investigation of Collateral or Physical Evidence of Corner Positions and Accessories Followed by Remonumentation of Corner Points, with New Accessories when Needed".

The remonumentation of original corner points was made at the request of the United States Forest Service, in conjunction with their Land Line Location Program.

The mean magnetic declination is 20° E.

South Boundary, T. 4 S., R. 33½ E.,
Willamette Meridian, Oregon

(Remonumenting a corner established by Rufus S. Moore,
U. S. Deputy Surveyor, in 1882)

The ¼ sec. cor. of secs. 2 and 35, on the S. bdy. of the
Tp., determined at record distance from the remains of
the original bearing trees:

A sawed ponderosa pine stump, 30 ins. diam., bears
N. 44° W., 94 lks. dist., with healed blaze.

A ponderosa pine, 26 ins. diam., bears S. 28° E.,
27 lks. dist., with scribe marks ¼ S visible on
open blaze. (Record, S. 7° E.)

At the corner point

Set an iron post, 28 ins. long, 2½ ins. diam., 12 ins.
in the ground, to solid rock, and in a mound of stone, 3
ft. base, to top, with brass cap mkd.

T 4 S R 33½ E
¼ S 35
S 2
T 5 S
1977

from which a new bearing tree

A ponderosa pine, 13 ins. diam., bears N. 5° E.,
169 lks. dist., mkd. ¼ S35 BT.

East Boundary, T. 4 S., R. 33½ E.,
Willamette Meridian, Oregon

(Remonumenting corners established by Rufus S. Moore,
U. S. Deputy Surveyor, in 1882)

The ¼ sec. cor. of secs. 25 and 30, on the E. bdy. of the
Tp., monumented with the original unmarked basalt stone,
15 x 15 x 6 ins., firmly set 6 ins. in the ground, from
which the remains of the original bearing trees:

Form 9180-8
(March 1969)

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FIELD ASSISTANTS

NAMES	CAPACITY
June Klein	Engineering Aid

I CERTIFY that the foregoing transcript of the field notes of the above described survey is a true copy of the original field notes.

Aide, Bureau of Land Management

Chief, Division of Geodetic Surveys

(Date) _____

CERTIFICATE OF SURVEY

(I) (~~WX~~), Craig L. Wanless, Cadastral Surveyor, HEREBY CERTIFY upon honor that, in pursuance of special instructions bearing date of the 3rd day of May, 19 57, (I) (~~WX~~) have remonumented certain original corner points, township 4 south, range 33½ east,

of the Willamette Meridian, in the State of Oregon, which are represented in the foregoing field notes as having been executed by (me), (~~WX~~) and under (my) (~~own~~) direction; and that said survey has been made in strict conformity with said special instructions, the Manual of Instructions for the Survey of the Public Lands of the United States, and in specific manner described in the foregoing field notes.

January 16, 1978 (Date) Craig L. Wanless (Cadastral Surveyor)

CERTIFICATE OF APPROVAL

BUREAU OF LAND MANAGEMENT Washington, D.C.

The foregoing field notes of the remonumentation of certain original corner points, township 4 south, range 33½ east, Willamette Meridian, Oregon,

executed by Craig L. Wanless, Cadastral Surveyor, having been critically examined and found correct, are hereby approved.

AUG 17 1978 (Date) Acting (Chief, Division of Cadastral Survey)

CERTIFICATE OF TRANSCRIPT

I CERTIFY That the foregoing transcript of the field notes of the above-described surveys in, is a true copy of the original field notes.

(Date) (Chief, Division of Cadastral Survey) GPO 849-626