

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

ORIGINAL

FIELD NOTES

OF THE

REMONUMENTATION OF CERTAIN ORIGINAL CORNER POINTS,

TOWNSHIP 4 SOUTH, RANGE 33½ EAST,

Multiple horizontal lines for handwritten notes.

Of the WILLAMETTE Meridian,

In the State of OREGON

EXECUTED BY

Craig L. Wanless, Cadastral Surveyor

Horizontal lines for signature and name.

Under special instructions dated May 3, 19 57, approved May 6, 1957,

Horizontal line for continuation of text.

_____, which provided for the surveys included under U.S. Survey/Group
Number 350, and assignment instructions dated August 23, 19 77.

Horizontal line for continuation of text.

Survey commenced September 8, 19 77

Survey completed September 9, 19 77

INDEX DIAGRAM

Township 4 South, Range 33½ East,

6	5	4	3	2	1
7	8	9	10	11	12
18	17	16	15	14	13
				<u>3</u>	<u>2</u>
19	20	21	22	23	24
30	29	28	27	26	25
31	32	33	34	35	36

2

1

1

Remonumentation of Certain Original Corner Points,
T. 4 S., R. 33½ E., Willamette Meridian, Oregon

CHAINS

A pine snag, 9 ins. diam., bears S. 83° E., 25 lks. dist., with healed blaze. (Record, S. 89° E.)

At the corner point

Set an iron post, 28 ins. long, 2½ ins. diam., 22 ins. in the ground, with brass cap mkd.

T 4 S	
¼	
R 33½ E	R 34 E
S 25	S 30
1977	

from which new bearing trees

A lodgepole pine, 8 ins. diam., bears S. 36° E., 81 lks. dist., mkd. ¼ S30 BT.

A lodgepole pine, 8 ins. diam., bears N. 39° W., 22 lks. dist., mkd. ¼ S25 BT.

Deposit corner stone and set a 5 ft. steel fence post alongside iron post.

The cor. of secs. 13, 18, 19, and 24, on the E. bdy. of the Tp., monumented with the remains of the original corner tree, a root hole, with a down and decayed fir alongside, size indeterminate, with scribe marks R33E S18 visible on open blaze and scribe marks R33½E S13 visible on another open blaze, from which the remaining original bearing tree:

A pine, 30 ins. diam., bears N. 48° E., 23 lks. dist., with scribe marks R33E S18 visible on open blaze.

At the corner point

Set an iron post, 28 ins. long, 2½ ins. diam., 24 ins. in the ground, with brass cap mkd.

T 4 S	
R 33½ E	R 34 E
S 13	S 18
S 24	S 19
1977	

from which new bearing trees

A pine, 11 ins. diam., bears S. 36° E., 17 lks. dist., mkd. T4S R34E S19 BT.

A grand fir, 15 ins. diam., bears S. 84° W., 75½ lks. dist., mkd. T4S R33½E S24 BT.

A grand fir, 14 ins. diam., bears N. 11° W., 29 lks. dist., mkd. T4S R33½E S13 BT.

Set a 5 ft. steel fence post alongside iron post.

Subdivisions, T. 4 S., R. 33½ E.,
Willamette Meridian, Oregon

Remonumentation of Certain Original Corner Points,
T. 4 S., R. 33½ E., Willamette Meridian, Oregon

CHAINS

(Remonumenting corners established by Rufus S. Moore,
U. S. Deputy Surveyor, in 1882)

The cor. of secs. 13, 14, 23, and 24, determined at
record bearing and distance from the remains of the
original bearing trees:

A pine snag, 15 ins. diam., bears N. 36° E., 12
lks. dist., with scribe marks T4S R33½E S13
visible on open blaze.

At the corner point

Set an iron post, 28 ins. long, 2½ ins. diam., 22 ins.
in the ground, in a mound of stone, 2 ft. base, to top,
with brass cap mkd.

T 4 S R 33½ E
S 14 S 13
S 23 S 24
1977

from which new bearing trees

A lodgepole pine, 10 ins. diam., bears N. 77° E.,
110 lks. dist., mkd. T4S R33½E S13 BT.

A lodgepole pine, 8 ins. diam., bears S. 48° E.,
148 lks. dist., mkd. T4S R33½E S24 BT.

A lodgepole pine, 9 ins. diam., bears S. 83° W.,
77 lks. dist., mkd. T4S R33½E S23 BT.

A fir, 9 ins. diam., bears N. 29° W., 160 lks.
dist., mkd. T4S R33½E S14 BT.

Set a 5 ft. steel fence post alongside iron post.

Corner is located 15 lks. east of gravelled road, 15 lks.
wide, bears N. and S.

The ¼ sec. cor. of secs. 14 and 23, monumented with the
original unmarked basalt stone, 16 x 12 x 6 ins., loosely
set in a mound of stone, 2 ft. base, 6 ins. high, from
which the only remaining original bearing tree:

A ponderosa pine, 22 ins. diam., bears S. 56° E.,
152 lks. dist., with fragmentary scribe marks
visible on open blaze.

At the corner point

Set an iron post, 28 ins. long, 2½ ins. diam., 10 ins.
in the ground, to solid rock, and in a mound of stone,
3 ft. base, to top, with brass cap mkd.

T 4 S R 33½ E
¼ S 14
S 23
1977

from which a new bearing tree

A ponderosa pine, 13 ins. diam., bears N. 48° W.,
121 lks. dist., mkd. ¼ S14 BT.

Remonumentation of Certain Original Corner Points,
T. 4 S., R. 33½ E., Willamette Meridian, Oregon

CHAINS

Deposit corner stone and set a 5 ft. steel fence
post alongside iron post.

CERTIFICATE OF SURVEY

(I) (~~WX~~), Craig L. Wanless, Cadastral Surveyor, HEREBY CERTIFY upon honor that, in pursuance of special instructions bearing date of the 3rd day of May, 19 57, (I) (~~WX~~) have remonumented certain original corner points, township 4 south, range 33½ east,

of the Willamette Meridian, in the State of Oregon, which are represented in the foregoing field notes as having been executed by (me), (~~WX~~) and under (my) (~~own~~) direction; and that said survey has been made in strict conformity with said special instructions, the Manual of Instructions for the Survey of the Public Lands of the United States, and in specific manner described in the foregoing field notes.

January 16, 1978 (Date) Craig L. Wanless (Cadastral Surveyor)

CERTIFICATE OF APPROVAL

BUREAU OF LAND MANAGEMENT Washington, D.C.

The foregoing field notes of the remonumentation of certain original corner points, township 4 south, range 33½ east, Willamette Meridian, Oregon,

executed by Craig L. Wanless, Cadastral Surveyor, having been critically examined and found correct, are hereby approved.

AUG 17 1978 (Date) Acting (Chief, Division of Cadastral Survey)

CERTIFICATE OF TRANSCRIPT

I CERTIFY That the foregoing transcript of the field notes of the above-described surveys in, is a true copy of the original field notes.

(Date) (Chief, Division of Cadastral Survey) GPO 849-626